SUMMARY OF QUANTITIES

Item			Quantity	
Number	Description	Unit	As Bid	Record Paid
AR150510	Engineer's Field Office	Lump Sum	1.0	
AR151450	Clearing and Grubbing	Acre	1.7	
AR152410	Unclassified Excavation	Cubic Yard	3,366.0	
AR156510	Silt Fence	Linear Foot	3,627.0	
AR156511	Ditch Check	Each	1.0	
AR156545	Riprap - Gradation No. 5	Square Yard	1,371.0	
AR701660	60° RCP, Class V	Linear Foot	2,320.0	
AR800926	CA-6 Aggregate Backfill	Cubic Yard	559.0	
AR800930	Paved Ditch, Type B-15	Linear Foot	721.0	
AR800937	Conservation Cover	Acre	34.7	
AR800974	Paved Ditch, Type B-37	Linear Foot	844.0	
AR800975	Grating for 60" RCP at End Section	Each	4.0	
AR800978	Twin 60-Inch RCP End Section	Each	2.0	en yezhoù an en
AR800979	Install Restrictor Pipe	Each	2.0	
AR905510	Topsoiling (From On Site)	Cubic Yard	15,798.0	


NOTE: 60" RCP, CLASS V PIPE SHALL USE SPIGOT JOINTS WITH O-RING GASKETS CONFORMING TO ASTM C 443-94.

LE03



HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200 Oak Brook, Illinois 60523 Telephone: 630.990.3800 Fax: 630.990.3801



JOLIET REGIONAL PORT DISTRICT

1 Hangar Road Romeoville, Illinois 60446 Telephone: 815.838.9497 Fax: 815.838.9524

CONSTRUCT RUNWAY 2-20 DRAINAGE CULVERTS AND IMPROVEMENTS

AIP PROJECT NO. 3-17-0140-B40 IDA PROJECT NO. LOT-3596

\vdash			4
			4
\sqcup			4
		~	1
			T
			T
			T
No.	Drawing Issue Description	Date	1

Date

MAY 5, 2006

Sheet Title

SUMMARY OF QUANTITIES

840-05C8046				
Praject Number				
LDH	01/12/05			
Loyout By	Date			
LDH/SJM	01/12/05			
Dasigned By	Date			
CRC	05/05/06			
Reviewed By	Dote			
LDH -				

2

5/06

Sheet No.