

05/01/2006, 08:28 AM
I:\04\Jobs\000831\031\04\TXYP\Taxilanes Re-design (June 2006)\Civil\Sheet02 Summary of Quantities.dgn
LDH

SUMMARY OF QUANTITIES

Item No.	Description	Unit	As Bid			Record Paid		
			State/Local	Local Only	Total	State/Local	Local Only	Total
AR150510	Engineer's Field Office	Lump Sum	1.00	0.00	1.00			
AR152410	Unclassified Excavation	Cubic Yard	850.00	0.00	850.00			
AR156510	Silt Fence	Linear Foot	1,711.00	0.00	1,711.00			
AR201610	Bituminous Base Course	Ton	927.00	153.00	1,080.00			
AR201620	Bituminous Base Course, Leveling	Ton	140.00	0.00	140.00			
AR209610	Crushed Agg. Base Course - 10"	Square Yard	1,615.00	0.00	1,615.00			
AR401610	Bituminous Surface Course	Ton	922.00	153.00	1,075.00			
AR401650	Bituminous Pavement Milling	Square Yard	1,440.00	0.00	1,440.00			
AR401660	Saw & Seal Bit. Joints	Linear Foot	424.00	42.00	466.00			
AR401665	Bituminous Pavement Sawing	Linear Foot	518.00	42.00	560.00			
AR401900	Remove Bituminous Pavement	Square Yard	5,930.00	1,335.00	7,265.00			
AR602510	Bituminous Prime Coat	Gallon	2,576.00	535.00	3,111.00			
AR603510	Bituminous Tack Coat	Gallon	1,510.00	200.00	1,710.00			
AR620520	Pavement Marking-Waterborne	Square Foot	1,315.00	0.00	1,315.00			
AR701512	12" RCP, Class IV	Linear Foot	226.00	0.00	226.00			
AR705412	Porous Backfill, No. 2	Cubic Yard	69.00	0.00	69.00			
AR705504	4" Perforated Underdrain	Linear Foot	873.00	0.00	873.00			
AR751410	Inlet	Each	2.00	0.00	2.00			
AR751943	Adjust Manhole	Each	1.00	0.00	1.00			
AR751946	Adjust Catch Basin	Each	2.00	0.00	2.00			
AR752412	Precast Reinforced Conc. FES 12"	Each	1.00	0.00	1.00			
AR752512	Grating for Conc. FES 12"	Each	1.00	0.00	1.00			
AR800203	Traffic Barrier Terminal	Each	1.00	0.00	1.00			
AR800995	Adjust Vehicle Gate	Lump Sum	1.00	0.00	1.00			
AR800996	Crack Control Material-Type 2	Square Yard	2,540.00	0.00	2,540.00			
AR901510	Seeding	Acre	1.00	0.00	1.00			
AR905510	Topsoiling (From On Site)	Cubic Yard	65.00	0.00	65.00			
AR905520	Topsoiling (From Off Site)	Cubic Yard	285.00	0.00	285.00			
AR908510	Mulching	Acre	1.00	0.00	1.00			
AR910400	Guardrail	Linear Foot	177.00	0.00	177.00			
AR910975	Relocate Roadway Sign	Each	3.00	0.00	3.00			

WA056



HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200
Oak Brook, Illinois 60523
Telephone: 630.990.3800
Fax: 630.990.3801



Waukegan Regional Airport
Waukegan Regional Port District

3580 North McAree Road
Waukegan, Illinois 60087
Phone: 847.244.0055
Fax: 847.244.3813

WAUKEGAN REGIONAL AIRPORT

REHABILITATE HANGAR
TAXILANES AND SERVICE
ROAD

IDA PROJECT NO. UGN-3601

No.	Drawing Issue Description	Date	By

Date

APRIL 21, 2006

Sheet Title

SUMMARY OF QUANTITIES

831-04TXVD

Project Number

SJM 11/15/05

Layout By Date

AAP 11/15/05

Designed By Date

RMH/RPH 04/04/06

Reviewed By Date

SJM

Drawn By

Sheet No.