



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 30, 2023

SUBJECT FAP Route 347 (IL 38/Roosevelt Rd)
Project NHPP-9PWJ(433)
Section FAP 0347 22 BJ2
DuPage County
Contract No. 62T16
Item No. 11, June 16, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page i of the Table of contents to the Special Provisions
3. Revised pages 25 & 26 of the Special Provisions
4. Revised sheets 2, 3, 6, 9, 11, 12, 20 & 31 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

| | |
|---|----|
| LOCATION OF PROJECT | 1 |
| DESCRIPTION OF PROJECT | 1 |
| MAINTENANCE OF ROADWAYS (D1) | 2 |
| STATUS OF UTILITIES (D1) | 2 |
| PUBLIC CONVENIENCE AND SAFETY (D1) | 5 |
| AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS (D1) | 6 |
| HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1) | 7 |
| KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY) | 12 |
| GRADING AND SHAPING SHOULDERS (D1) | 13 |
| ADJUSTMENTS AND RECONSTRUCTIONS (D1) | 13 |
| DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D1) | 14 |
| ENGINEER'S FIELD OFFICE TYPE A (D1) | 16 |
| TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1) | 17 |
| TRAFFIC CONTROL PLAN (D1) | 17 |
| FRICTION AGGREGATE (D1) | 19 |
| HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1) | 22 |
| HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | 23 |
| APPROACH SLAB REMOVAL | 24 |
| TEMPORARY SUPPORT SYSTEM | 26 |
| TEMPORARY INFORMATION SIGNING | 27 |
| DECK SLAB REPAIR | 28 |
| BRIDGE DECK LATEX CONCRETE OVERLAY | 33 |
| STRUCTURAL REPAIR OF CONCRETE | 44 |
| BLENDED FINELY DIVIDED MINERALS (BDE) | 55 |
| COMPENSABLE DELAY COSTS (BDE) | 55 |
| CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) | 59 |
| DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) | 61 |
| PERFORMANCE GRADED ASPHALT BINDER (BDE) | 71 |
| SEEDING (BDE) | 75 |
| SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) | 81 |
| SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) | 81 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) | 82 |
| SUBMISSION OF PAYROLL RECORDS (BDE) | 82 |

Revised 5/30/2023

Disposal of material shall be done in accordance with Section 440.06 of the Standard Specifications.

Method of Measurement. Approach Slab and Shoulder Removal will be measured in place for payment in square yards of approach slab removed regardless of replacement area. Full depth sawcutting shall not be measured separately for payment.

Basis of Payment. Approach slab removal will be paid for at the contract unit price per square yards for APPROACH SLAB REMOVAL, which price shall include full depth sawcutting, pavement removal, disposal of debris, and all labor, equipment, and materials required to complete the work specified herein.

Revised 5/30/2023

TEMPORARY SUPPORT SYSTEM

Description. This work shall consist of furnishing all material, equipment and labor for the design, construction and subsequent removal of a Temporary Support System. Included under this item shall be all work to support the vertical abutments which will be subject to horizontal earth loads during superstructure replacement operations and the bridge deck during removal of the bituminous patch along each abutment joint.

General. The design calculations and details for the Temporary Support System proposed by the Contractor shall be submitted to the Engineer for approval. The calculations shall be prepared and sealed by an Illinois Licensed Structural Engineer. This approval will not relieve the Contractor of responsibility for the adequacy of the support system. Any damage to the abutments caused by the attachment of the Temporary Support System shall be repaired subject to the satisfaction of the Engineer.

Existing Conditions. An Existing Structure Information Package (ESIP) will be provided by the Department to the Contractor upon request. This package will typically include existing or "As-Built" plans. The availability of structural information from the Department is solely for the convenience and information of the Contractor and shall not relieve the Contractor of the duty to make, and the risk of making, examinations and investigations as required to assess conditions affecting the work. Any data furnished in the ESIP is for information only and does not constitute a part of the Contract. The Department makes no representation or warranty, express or implied, as to the information conveyed or as to any interpretations made from the data.

Revised 5/30/2023