



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1, 2023

SUBJECT: FAP Route 693 (IL 9)
Section (FR)I-1
McLean County
Contract No. 70G18
Item No. 47, June 16, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised the Table of Contents to the Special Provisions.
3. Added page 28 to the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

INTENT OF PROJECT	1
DESCRIPTION OF PROJECT	1
TRAFFIC CONTROL PLAN	1
TRAFFIC CONTROL & PROTECTION DEVICES (ROAD & SIDEROAD/STREET CLOSURES)	3
TRAFFIC CONTROL REMOVAL	3
COOPERATION BETWEEN CONTRACTORS.....	3
DELAYED START OF MULTIPLE CONTRACTS	3
EXISTING STATE-OWNED UTILITIES.....	4
NOTIFICATION PRIOR TO LANE CLOSURES	4
TRUCKS ENTERING AND LEAVING ROAD	4
TEMPORARY TRAFFIC CONTROL DEVICE DEPLOYMENT AND REMOVAL	5
STATUS OF UTILITIES	5
COMPENSABLE DELAY COSTS (BDE)	5
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	8
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)..	17
PERFORMANCE GRADED ASPHALT BINDER (BDE)	18
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	23
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	23
SUBMISSION OF PAYROLL RECORDS (BDE)	24
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	25
WEEKLY DBE TRUCKING REPORTS (BDE).....	25
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....	25
WORKING DAYS (BDE)	27
PAVEMENT MARKINGS	28
RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	28

Revised June 1, 2023

PAVEMENT MARKINGS

The Engineer shall contact Gary Sims at 217-251-4859 to coordinate placement of pavement markings obliterated by pavement inlay operations as part of this contract.

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

Eff. 10-22-1997

Rev. 09-24-2021

Replace Article 783.03(b) with the following:

“Where removal of raised reflective markers is indicated in the plans, this shall consist of complete removal of the castings, and reflectors from the pavement structure. Where cold milling is not proposed, or where the proposed depth of cold milling is less than 1½ inches (38 mm), the holes resulting from the removal of raised reflective markers shall immediately be cleaned out with compressed air, filled with a bituminous mixture meeting the requirements of Article 1030.11 and/or Materials “M” Specification 120 (Bituminous Premix for Maintenance Use – Proprietary Mixes), and compacted to the satisfaction of the Engineer. This work shall be completed prior to cold milling, or prior to hot-mix asphalt placement if cold milling is not specified.”

Add the following at the end of Article 783.06:

“The payment for RAISED REFLECTIVE PAVEMENT MARKER REMOVAL shall include complete removal and disposal of the castings and reflectors, and furnishing, placing, and compacting the bituminous material in the holes as specified above.”

Added June 1, 2023