



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2023

SUBJECT FAP Route 312 (IL 3)
Project NHPP-HPXS(165)
Section 123B-5; 123B-6; 123B-7
Jackson County
Contract No. 78790

Item No. 158, June 16th, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Recurring Special Provisions Checksheet of the Special Provisions.
2. Revised page i of the Table of Contents in the Special Provisions.
3. Revised page 7 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

RECURRING SPECIAL PROVISIONS

The following RECURRING SPECIAL PROVISIONS indicated by an "X" are applicable to this contract and are included by reference:

<u>CHECK SHEET #</u>		<u>PAGE NO.</u>
1	X Additional State Requirements for Federal-Aid Construction Contracts	53
2	X Subletting of Contracts (Federal-Aid Contracts)	56
3	X EEO	57
4	Specific EEO Responsibilities Non Federal-Aid Contracts	67
5	Required Provisions - State Contracts	72
6	Asbestos Bearing Pad Removal	78
7	Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal	79
8	X Temporary Stream Crossings and In-Stream Work Pads	80
9	Construction Layout Stakes	81
10	Use of Geotextile Fabric for Railroad Crossing	84
11	Subsealing of Concrete Pavements	86
12	Hot-Mix Asphalt Surface Correction	90
13	Pavement and Shoulder Resurfacing	92
14	Patching with Hot-Mix Asphalt Overlay Removal	93
15	Polymer Concrete	95
16	Reserved.....	97
17	Bicycle Racks	98
18	X Temporary Portable Bridge Traffic Signals	100
19	Nighttime Inspection of Roadway Lighting	102
20	English Substitution of Metric Bolts	103
21	X Calcium Chloride Accelerator for Portland Cement Concrete	104
22	Quality Control of Concrete Mixtures at the Plant	105
23	X Quality Control/Quality Assurance of Concrete Mixtures	113
24	Reserved	129
25	Reserved	130
26	Temporary Raised Pavement Markers	131
27	Restoring Bridge Approach Pavements Using High-Density Foam	132
28	Portland Cement Concrete Inlay or Overlay	135
29	Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	139
30	Longitudinal Joint and Crack Patching	142
31	X Concrete Mix Design – Department Provided	144
32	Station Numbers in Pavements or Overlays	145




TABLE OF CONTENTS

LOCATION OF PROJECT.....	1
DESCRIPTION OF PROJECT.....	1
UTILITIES.....	2
TRAFFIC CONTROL PLAN.....	4
TRAFFIC CONTROL AND PROTECTION STANDARD BLR 21.....	5
DETOUR SIGNING.....	5
DROP-OFF NEAR THE EDGE OF TRAVELED WAY.....	6
NOTIFICATION PRIOR TO STARTING WORK.....	6
CHANGEABLE MESSAGE SIGNS.....	6
BOX CULVERT REMOVAL AND REPLACEMENT.....	7
ASSEMBLE AND MATCH MARK PRECAST CONCRETE BOX CULVERT.....	7
3D MODEL – CONTRACTOR SUPPLIED.....	7
CALCIUM CHLORIDE ACCELERATOR FOR PORTLAND CEMENT CONCRETE.....	7
AVAILABILITY OF ELECTRONIC FILES.....	8
PORTLAND CEMENT CONCRETE PAVEMENT 10”.....	8
ROCK FILL – FOUNDATION.....	9
PRECAST CONCRETE BOX CULVERTS (SPECIAL).....	9
RELOCATE SIGN, (SPECIAL).....	10
TEMPORARY SUPPORT SYSTEM.....	10
FURNISHED EXCAVATION.....	11
PIPE CULVERTS, CLASS C, TYPE 1 10”.....	11
MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES.....	12
BAR SPLICERS.....	13
BLENDED FINELY DIVIDED MINERALS (BDE).....	15
COMPENSABLE DELAY COSTS (BDE).....	15
CORRUGATED PLASTIC PIPE (CULVERT AND STORM SEWER) (BDE).....	18
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	29
FUEL COST ADJUSTMENT (BDE).....	38
PERFORMANCE GRADED ASPHALT BINDER (BDE).....	40
SEEDING (BDE).....	45
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE).....	50
STEEL COST ADJUSTMENT (BDE).....	51
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE).....	53
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	54



The furnishing, placing, and maintaining of portable changeable message signs shall be paid for per CALENDAR DAY as CHANGEABLE MESSAGE SIGN.

BOX CULVERT REMOVAL AND REPLACEMENT

IL 3 shall be allowed to be closed to all traffic for the removal and replacement of the existing culvert (SN 039-2013). A closure shall be permitted for any consecutive period starting on a Friday at 6:00 PM and ending no later than the following Monday at 6:00 AM during the period of July 31st to September 31st. Outside of this period, IL 3 shall be open to at least one lane of traffic. This closure will not be permitted on any holiday weekend as stated in Article 107.09 of the Standard Specifications. After the roadway is opened to traffic, items such as the HMA shoulder may be installed along with any other applicable items using the appropriate traffic control standard.

If the road is not open by 6:00 AM Monday, a traffic control deficiency will be applied per Article 105.03(b), except that the daily monetary deduction will be \$5,000 per day.

ASSEMBLE AND MATCH MARK PRECAST CONCRETE BOX CULVERT

Precast box culverts shall be constructed according to Section 540, except as modified by this special provision. This special provision applies to the proposed precast concrete box culvert on Section 123B-5.

It shall be the Contractor's responsibility to ensure that the precast concrete box culvert sections are assembled and match marked prior to the sections arriving at the jobsite and to the road closure to secure a proper fit on each joint. Any sections that do not provide a proper fit shall be rejected by the Engineer and replaced by the Contractor with no additional compensation.

This work will not be paid for separately but shall be considered included in the unit price for precast box culverts of the size specified.

3D MODEL – CONTRACTOR SUPPLIED

If the CONTRACTOR develops a 3D model of the project site, then it shall be provided to the Engineer. The cost of providing the 3D model to the Department shall be incidental to the contract.

CALCIUM CHLORIDE ACCELERATOR FOR PORTLAND CEMENT CONCRETE

The use of calcium chloride accelerator shall be according to the Recurring Special Provisions Check Sheet #21. The Contractor shall be only allowed to calcium chloride accelerator for the structure location that involves the "Weekend Closure" to remove and replace the existing structure, the proposed PCC pavement located over SN 039-2013 (E)/ SN 039-7126(P).

