

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0005 80% FED 20% STATE	0014 80% FED 20% STATE					CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	0005 80% FED 20% STATE	0014 80% FED 20% STATE				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	110	110						70300100	SHORT TERM PAVEMENT MARKING	FOOT	3100	2600	500				
25200110	SODDING, SALT TOLERANT	SQ YD	110	110						70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	580.8	580.8					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	30	30						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19600	19600					
40600300	AGGREGATE (PRIME COAT)	TON	150	150						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2750	2750					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	100	100						70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	350	350					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	230	230					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1137	1137						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2900	440	2460				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	330	330						70400100	TEMPORARY CONCRETE BARRIER	FOOT	500		500				
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	80	80						70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	500		500				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5310	5310					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	617.8	580.8	37					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	570	570					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20196	19600	596					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	13240	13240					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2933	2750	183					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	672	672					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	350	350						
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	282	282					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	268	230	38					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	110	110					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	236	236						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	16	16					* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	17		17					
50102400	CONCRETE REMOVAL	CU YD	71.8		71.8				* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	80		80					
50157300	PROTECTIVE SHIELD	SO YD	130		130				78300100	PAVEMENT MARKING REMOVAL	SO FT	401		401					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	75.6		75.6				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	250	200	50					
50300260	BRIDGE DECK GROOVING	SO YD	1080		1080				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2703	2703						
50300300	PROTECTIVE COAT	SO YD	387	220	167				89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	11970		11970				X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SO YD	15	15						
50800515	BAR SPLICERS	EACH	58		58				X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1810	1810						
52000110	PREFORMED JOINT STRIP SEAL	FOOT	163		163				X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	7280	7280						
X5539700	STORM SEWERS TO BE CLEANED	FOOT	1500	1500					X6030205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	12	12						
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	9	9					X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3					X7010240	TRAFFIC CONTROL SURVEILLANCE (SPECIAL)	CAL DA	15		15					
60404950	FRAMES AND GRATES, TYPE 24	EACH	9	9															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	9	9															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	0.5	0.5														
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6		6														

* Specialty Items
 X Non-Participating (100% STATE)

FILE NAME =	USER NAME = gulltaumefp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwworking\gulltaumefp\01088275\DIS2610-stf-pln.dgn	DRAWN -	REVISED -	351			539 W-1-RS	COOK	56	3	
PLOT SCALE = 50,000' / 1" = 1/4"	CHECKED -	REVISED -	CONTRACT NO. 60K57							
PLOT DATE = 4/12/2011	DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							

SCALE: SHEET NO. OF SHEETS STA. TO STA.