

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 0004	0021 SIGNAL	0021 LIGHTING				CODE NO	ITEM		UNIT	ROADWAY 0004	0021 SIGNAL	0021 LIGHTING	
*73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4	4					*88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2			
*78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	610	610					*88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8			
*78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	1450	1450					*88600100	DETECTOR LOOP, TYPE I	FOOT	240		240			
*78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	200	200					*89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	340		340			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20					*89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	3976		3976			
*81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	770		770				*89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		2			
*81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	60		60				*89502380	REMOVE EXISTING HANDHOLE	EACH	4		4			
*81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	500			500			*89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	2		2			
*81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	153		153				*X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	2	2				
*81400100	HANDHOLE	EACH	3		3				*X0326148	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	7			7		
*81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2675			2675			X0504200	CONCRETE HEADWALL	EACH	1	1				
*81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	1700			1700			X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3021		846	2175			X7030030	REFLECTIVE WET TEMPORARY TAPE TYPE III, 4 INCH	FOOT	3000	3000				
*83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	120			120			*X8210015	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, 400 WATT	EACH	7			7		
*84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	7			7			* 86200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	2		2			
*84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	7			7			Z0001050	AGGREGATE SUBGRADE 12"	SO YD	1625	1625				
*85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2				Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	980		980				Z0018913	DRILL AND GROUT 8 TIE BARS	EACH	1500	1500				
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	675		675				Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	40	40				
*87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	285		285				Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	52	52				
*87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2				*Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3			3		
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8				*Z0033044	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	2		2			
*87900200	DRILL EXISTING HANDHOLE	EACH	4		4				*Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2		2			
*88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4		4												
*88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6		6												
*88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4												
*88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2												
									* SPECIALTY ITEMS								

FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				IL ROUTE 59 AT US ROUTE 20 SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\work\p1\dot\kellers\0156262\142309-Designdwg		DRAWN -	REVISED -									338	7 HB-K-N	COOK	82	4
PLOT SCALE = 50/0000 ' / IN.		CHECKED -	REVISED -									CONTRACT NO. 60K62				
PLOT DATE = 2/22/2011		DATE -	REVISED -									FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
				SCALE:				SHEET NO. OF SHEETS STA. TO STA.								