



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 10, 2011

SUBJECT: FAP Route 345 (US 20)
Section 8R-1RS-4
Kane & Cook Counties
Contract No. 60M46
Item No. 188, June 17, 2011 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replace the Schedule of Prices.
2. Revised sheet 6 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; D. Carl Puzey;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0320882	GUTTERS TO BE CLEANED	FOOT	70.000				
X0322215	CLEAN BRG SCUP/DWNSPT	EACH	4.000				
X0322944	BR DK TH POLY OVL 3/8	SQ YD	530.000				
X0325490	F&I ACCESS DOOR	EACH	1.000				
X0325983	BRD FLYASH/SLAG 2 1/4	SQ YD	362.000				
X0326331	CLEAN/PAINT BEARINGS	EACH	15.000				
X0326394	FLOOR DRAINS CLEANED	EACH	30.000				
X0327303	REM EX SIGN LT UNT NS	EACH	17.000				
X0640200	TRAF BARRIER TERM SPL	EACH	1.000				
X2020110	GRADING & SHAP SHLDRS	UNIT	966.000				
X4060826	P LB MM IL-4.75 N50	TON	15,954.000				
X4063500	PRELIM TEST STRIP	EACH	1.000				
X4400100	PCC SURF REM VAR DP	SQ YD	2,809.000				
X5017305	PROTEC SHIELD PERM	SQ YD	911.000				
X5539700	SS CLEANED	FOOT	1,152.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X6030310	FR & LIDS ADJUST SPL	EACH	10.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7030030	WET REF TEM TAPE T3 4	FOOT	5,200.000				
Z0001495	BR APPROACH SHLD REM	SQ YD	20.000				
Z0001899	JACK & REM EX BEARING	EACH	15.000				
Z0004562	COMB C C&G REM & REPL	FOOT	310.000				
Z0012102	CONC BR DECK SCAR 3/8	SQ YD	530.000				
Z0012142	BR DECK SCAR 2 1/4	SQ YD	362.000				
Z0012754	STR REP CON DP = < 5	SQ FT	499.000				
Z0012755	STR REP CON DP OVER 5	SQ FT	172.000				
Z0016001	DECK SLAB REP (FD-T1)	SQ YD	0.700				
Z0016002	DECK SLAB REP (FD-T2)	SQ YD	132.500				
Z0016200	DECK SLAB REP (PART)	SQ YD	491.500				
Z0018002	DRAINAGE SCUPPR DS-11	EACH	1.000				
Z0018400	DRAINAGE STR ADJ	EACH	35.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0018500	DRAINAGE STR CLEANED	EACH	94.000				
Z0021904	SILICONE JT SEAL 1	FOOT	307.000				
Z0021907	SILICONE JT SEAL 1.75	FOOT	382.000				
Z0021908	SILICONE JT SEAL 2	FOOT	167.000				
Z0021914	SILICONE JT SEAL 2.75	FOOT	231.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	2.000				
Z0030255	IMP ATTN TEMP FRN TL2	EACH	6.000				
Z0030320	IMP ATTN REL FRD TL2	EACH	6.000				
Z0030850	TEMP INFO SIGNING	SQ FT	363.700				
Z0034105	MATL TRANSFER DEVICE	TON	21,984.000				
Z0041895	POLYMER CONCRETE	CU FT	11.400				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
**DELETE Z0055400	RUMBLE STRIP	FOOT	68,255.000				
Z0073200	TEMP SHORING & CRIB	EACH	6.000				
28100805	STONE DUMP RIP CL A3	TON	12.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600200	BIT MATLS PR CT	TON	120.000				
40600300	AGG PR CT	TON	591.000				
40600400	MIX CR JTS FLANGEWYS	TON	444.000				
40600895	CONSTRUC TEST STRIP	EACH	1.000				
40600982	HMA SURF REM BUTT JT	SQ YD	669.000				
40600985	PCC SURF REM BUTT JT	SQ YD	690.000				
40601005	HMA REPL OVER PATCH	TON	453.000				
40603153	P HMA SC SMA N80	TON	21,984.000				
40603340	HMA SC "D" N70	TON	11,328.000				
42001300	PROTECTIVE COAT	SQ YD	150.000				
42001500	PCC BR APPR SHLD PAVT	SQ YD	20.000				
44000155	HMA SURF REM 1 1/2	SQ YD	368.000				
44000159	HMA SURF REM 2 1/2	SQ YD	132,331.000				
44000161	HMA SURF REM 3	SQ YD	162,840.000				
44002216	HMA RM OV PATCH 4	SQ YD	2,688.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44201761	CL D PATCH T1 10	SQ YD	101.000				
44201765	CL D PATCH T2 10	SQ YD	1,704.000				
44201769	CL D PATCH T3 10	SQ YD	272.000				
44201771	CL D PATCH T4 10	SQ YD	75.000				
48102100	AGG WEDGE SHLD TYPE B	TON	3,864.000				
50102400	CONC REM	CU YD	46.000				
50157300	PROTECTIVE SHIELD	SQ YD	2,532.000				
50300255	CONC SUP-STR	CU YD	46.000				
50500405	F & E STRUCT STEEL	POUND	2,700.000				
50800205	REINF BARS, EPOXY CTD	POUND	6,350.000				
50800515	BAR SPLICERS	EACH	24.000				
51100300	SLOPE WALL 6	SQ YD	26.400				
52000110	PREF JT STRIP SEAL	FOOT	301.000				
52100010	ELAST BEARING ASSY T1	EACH	15.000				
52100520	ANCHOR BOLTS 1	EACH	30.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
58700300	CONCRETE SEALER	SQ FT	10,471.000				
60404950	FR & GRATES T24	EACH	15.000				
60406100	FR & LIDS T1 CL	EACH	5.000				
**ADD 64200105	SHOULDER RUMBLE STRIP	FOOT	68,255.000				
67000400	ENGR FIELD OFFICE A	CAL MO	8.000				
67100100	MOBILIZATION	L SUM	1.000				
70100310	TRAF CONT-PROT 701421	L SUM	1.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100600	TRAF CONT-PROT 701336	L SUM	1.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	98.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	8.000				
70300100	SHORT TERM PAVT MKING	FOOT	6,390.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300210	TEMP PVT MK LTR & SYM	SQ FT	220.000				
70300220	TEMP PVT MK LINE 4	FOOT	310,276.000				
70300240	TEMP PVT MK LINE 6	FOOT	1,600.000				
70300250	TEMP PVT MK LINE 8	FOOT	51,420.000				
70300260	TEMP PVT MK LINE 12	FOOT	12,720.000				
70300280	TEMP PVT MK LINE 24	FOOT	480.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	2,130.000				
70400100	TEMP CONC BARRIER	FOOT	4,857.000				
70400200	REL TEMP CONC BARRIER	FOOT	4,237.000				
72000100	SIGN PANEL T1	SQ FT	666.000				
72000200	SIGN PANEL T2	SQ FT	693.000				
72000300	SIGN PANEL T3	SQ FT	2,017.000				
72400100	REMOV SIN PAN ASSY TA	EACH	40.000				
72400200	REMOV SIN PAN ASSY TB	EACH	55.000				
72400310	REMOV SIGN PANEL T1	SQ FT	54.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72400320	REMOV SIGN PANEL T2	SQ FT	10.000				
72400330	REMOV SIGN PANEL T3	SQ FT	1,696.000				
72800100	TELES STL SIN SUPPORT	FOOT	114.000				
73000100	WOOD SIN SUPPORT	FOOT	1,516.000				
73700100	REM GR MT SIN SUPPORT	EACH	4.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	110.000				
78000200	THPL PVT MK LINE 4	FOOT	155,138.000				
78000400	THPL PVT MK LINE 6	FOOT	600.000				
78000500	THPL PVT MK LINE 8	FOOT	25,710.000				
78000600	THPL PVT MK LINE 12	FOOT	6,360.000				
78000650	THPL PVT MK LINE 24	FOOT	240.000				
78008210	POLYUREA PM T1 LN 4	FOOT	7,189.000				
78100100	RAISED REFL PAVT MKR	EACH	1,657.000				
78100105	RAISED REF PVT MKR BR	EACH	107.000				
78200530	BAR WALL MKR TYPE C	EACH	743.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60M46

State Job # - C-91-113-11
 PPS NBR - 1-77865-0100
 County Name - COOK- KANE-
 Code - 31 - 89 -
 District - 1 - 1 -
 Section Number - 8R-1-RS-4

Project Number

Route

FAP 345

*REVISE : JUNE 6, 2011

**REVISE: JUNE 9, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD 78300100	PAVT MARKING REMOVAL	EACH	2,290.000				
78300200	RAISED REF PVT MK REM	EACH	1,713.000				
88600600	DET LOOP REPL	FOOT	2,218.000				