

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE										
				URBAN		KANE CO.		COOK CO.		KANE CO.		KANE CO.		
				KANE CO. ROADWAY	COOK CO. ROADWAY	US RTE 20 OVER FOX RIVER 045-0004	US RTE 20 OVER RAYMOND ST 045-0005	US RTE 20 OVER ST CHARLES ST 045-0006	US RTE 20 OVER IL RTE 25 045-0007	US RTE 20 OVER POPLAR CREEK 016-0217	US RTE 20 OVER US BUS US 20 016-0218	IL RTE 31 OVER US RTE 20 045-0017	FA 426 OVER WB US RTE 20 045-0008	
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	12	0005	0005	0014	0014	0014	0014	0014	0014	0014	0014	0014
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	120	88	31	-	-	-	-	-	-	1	-	-
40600300	AGGREGATE (PRIME COAT)	TON	591	437	154	-	-	-	-	-	-	-	-	-
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	444	328	116	-	-	-	-	-	-	-	-	-
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SO YD	669	497	172	-	-	-	-	-	-	-	-	-
40600985	CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	690	690	-	-	-	-	-	-	-	-	-	-
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	453	362	91	-	-	-	-	-	-	-	-	-
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	21984	15855	6129	-	-	-	-	-	-	-	-	-
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	11,328	8,644	2,653	-	-	-	-	-	-	31	-	-
42001300	PROTECTIVE COAT	SO YD	150	-	-	-	-	-	-	-	-	-	-	150
42001500	P.C CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SO YD	20	-	-	-	-	-	-	-	-	-	-	20
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO. YD.	368	-	-	-	-	-	-	-	-	368	-	-
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	132,331	100,746	31,585	-	-	-	-	-	-	-	-	-
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	162840	117440	45400	-	-	-	-	-	-	-	-	-
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	2688	1881	807	-	-	-	-	-	-	-	-	-
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	101	71	30	-	-	-	-	-	-	-	-	-
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1704	1200	504	-	-	-	-	-	-	-	-	-
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	272	211	61	-	-	-	-	-	-	-	-	-
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	75	50	25	-	-	-	-	-	-	-	-	-
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3864	3004	860	-	-	-	-	-	-	-	-	-
50102400	CONCRETE REMOVAL	CU. YD.	46	-	-	-	-	-	-	-	14	-	-	32
50157300	PROTECTIVE SHIELD	SO. YD.	2532	-	-	600	658	539	-	539	-	-	-	196
X5017305	PROTECTIVE SHIELD (PERMANENT)	SO. YD.	911	-	-	468	-	-	-	-	-	443	-	-
50300255	CONCRETE SUPERSTRUCTURE	CU YD	46	-	-	-	-	-	-	-	14	-	-	32
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2700	-	-	-	-	-	-	-	-	-	-	2700
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6350	-	-	-	-	-	-	2010	-	-	-	4340
50800515	BAR SPLICERS	EACH	24	-	-	-	-	-	-	24	-	-	-	-
51100300	SLOPE WALL 6 INCH	SO. YD.	26.4	-	-	-	-	-	26.4	-	-	-	-	-
52000110	PREFORMED JOINT STRIP SEAL	FOOT	301	-	-	-	-	-	-	112	-	-	-	189
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	15	-	-	-	-	-	-	-	-	-	-	15
52100520	ANCHOR BOLTS, 1"	EACH	30	-	-	-	-	-	-	-	-	-	-	30
58700300	CONCRETE SEALER	SO. FT.	10471	-	-	-	-	-	-	10471	-	-	-	-

\* SPECIALTY ITEM

FILE NAME : P:\2009\ME090806-Ver-Vor-PH\1\CADD\W021.US20\Shas\03-500sh-t-nt-US20.dgn  
 PLOT SCALE : 1:1000 / IN.  
 USER NAME : Millennia Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148  
 630.785.9110 voice, 630.839.2566 fax  
 www.mps-ill.com  
**MILLENNIA PROFESSIONAL SERVICES**

DESIGNED - CJD	REVISED -
DRAWN - CJD	REVISED -
CHECKED - TVN	REVISED -
DATE - 4/4/2011	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**US ROUTE 20 (LAKE STREET)**  
**RANDALL RD TO SHALES PARKWAY**  
 SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

**SUMMARY OF QUANTITIES**

F.A.P. RTE. 345	SECTION BR-1-RS-4	COUNTY KANE/COOK	TOTAL SHEETS 124	SHEET NO. 3
CONTRACT NO. 60M46			ILLINOIS FED. AID PROJECT	