ROUTE: IL 31 (Bull Valley Rd. to IL 120)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
Bull Valley	IL 120	NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	5	60	7
		NB		12	6	72	8
		NB		12	6	72	8
		NB		12	6	72	8
		NB		12	6	72	8
		NB		12	6	72	8
		NB		12	6	72	8
		NB		12	6	72	8
		NB		3	80	240	27
		NB		12	12	144	16
		NB		12	12	144	16
		NB		12	12	144	16
		NB		12	12	144	16
		NB		12	12	144	16
		NB		12	12	144	16
		NB		3	20	60	7
		NB		3	20	60	7
		NB		3	20	60	7
		NB		3	20	60	7
		NB		3	20	60	7
		NB		3	20	60	7
		NB		3	20	60	7
		NB		3	20	60	7
		NB		3	20	60	7
IL 120	Bull Valley	SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7

ROUTE: IL 31 (Bull Valley Rd. to IL 120)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	5	60	7
		SB		12	6	72	8
		SB		12	6	72	8
		SB		12	6	72	8
		SB		12	6	72	8
		SB		12	6	72	8
		SB		12	6	72	8
		SB		12	6	72	8
		SB		12	6	72	8
		SB		12	8	96	11
		SB		12	15	180	20
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		18	6	108	12
		SB		12	12	144	16
		SB		12	12	144	16
		SB		12	12	144	16
		SB		12	12	144	16
		SB		12	12	144	16
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		3	20	60	7
		SB		45	8	360	40
		TOTALS:			974 FT		888 SY

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0260180\Design.dgn	USER NAME = VelichkovVV	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/13/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 31

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-009-RS	MCHENRY	33	13
		CONTRACT NO. 60N97		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		