

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				BLIVIN STREET	80% FED 20% COUNTY URBAN BRIDGE 0011
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	124		124
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	64		64
20101000	TEMPORARY FENCE	FOOT	452		452
20200100	EARTH EXCAVATION	CU YD	349		349
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	117		117
20300100	CHANNEL EXCAVATION	CU YD	1,238		1,238
20800150	TRENCH BACKFILL	CU YD	61.0		61.0
20900110	POROUS GRANULAR BACKFILL	CU YD	45.0		45.0
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	1,408		1,408
* 25000210	SEEDING, CLASS 2A	ACRE	0.13		0.13
* 25000310	SEEDING, CLASS 4	ACRE	0.10		0.10
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	24.3		24.3
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	24.3		24.3
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	24.3		24.3
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1,118		1,118
* 25200110	SODDING, SALT TOLERANT	SQ YD	290		290
* 25200200	SUPPLEMENTAL WATERING	UNIT	97		97
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	49		49
28000315	AGGREGATE DITCH CHECKS	TON	9.2		9.2
28000400	PERIMETER EROSION BARRIER	FOOT	1,250		1,250
28000500	INLET AND PIPE PROTECTION	EACH	3		3
28000510	INLET FILTERS	EACH	10		10
28100101	STONE RIPRAP, CLASS A1	SQ YD	10		10
28100109	STONE RIPRAP, CLASS A5	SQ YD	263		263
28200200	FILTER FABRIC	SQ YD	1,135		1,135
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	1,100		1,100
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.23		0.23
40600300	AGGREGATE (PRIME COAT)	TON	1.15		1.15
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	412		412
42001300	PROTECTIVE COAT	SQ YD	42		42
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	91		91
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	29		29

* SPECIALTY ITEMS

FILE NAME = W:\755-010 Blivin Phase II\CADD_Sheets\755010-ant-500.dgn

B Bollinger, Lach & Associates, Inc.
ITASCA, ILLINOIS

USER NAME = dbruckelmejer	DESIGNED - DBB	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN - DBB	REVISED -
PLOT DATE = 3/25/2011	CHECKED - CRF	REVISED -
	DATE - 03-28-11	REVISED -

**BLIVIN STREET OVER
NIPPERSINK CREEK**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 3 OF 69 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00355-00-BR	MCHENRY	69	3
CONTRACT NO. 63583				
FED ROAD DIST NO. 1 ILLINOIS FED AID PROJECT				