	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE BLIVIN STREET 80% FED 20% COUNTY URBAN BRIDGE 0011
	X2800400	PERIMETER EROSION BARRIER, SPECIAL	FOOT	10	10
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	1	1
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	1
	X5021510	COFFERDAMS (SPECIAL)	EACH	2	2
	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
*	X7810300	RECESSED REFLECTIVE PAVMENT MARKER	EACH	4	4
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	571	571
	Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	100	100
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	120	120
	Z0066600	STABILIZED DRIVEWAYS 8"	SQ YD	94	94
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	122	122
	Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 13 INCH	FOOT	42	42
△	Z0076600	TRAINEES	HOUR	500	500
	XX005968	TURBIDITY CURTAIN	SQ YD	140	140
	XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1	1
	XX008003	FORM LINER, TEXTURED SURFACE, SPECIAL	SQ FT	1,691	1,691

* SPECIALTY ITEMS

△ CONSTRUCTION CODE 0042

FILE NAME = W:\755-010 Blivin Phase II\CADD_Sheets\755010-sht-SQ0.dgn

Bollinger, Lach & Associates, Inc.
ITASCA, ILLINOIS

USER NAME = dbruckelmeyer	DESIGNED - DBB	REVISED -	
	DRAWN - DBB	REVISED -	
PLOT SCALE = 20.0000 ' / IN.	CHECKED - CRF	REVISED -	
PLOT DATE = 3/28/2011	DATE - 03-28-11	REVISED -	

BLIVIN STREET OVER NIPPERSINK CREEK

SUMMARY OF QUANTITIES

SCALE: NONE | SHEET NO. 6 OF 69 SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00355-00-BR	MCHENRY	69	6
		CONTRACT NO. 63583		

FED ROAD DIST NO. 1 | ILLINOIS | FED AID PROJECT