

NOTES: 1) EPOXY PAVEMENT MARKINGS SHALL BE INSTALLED IN GROOVED RECESSED CHANNELS CONSTRUCTED 0.040 INCHES BELOW THE SURFACE AND 1 INCH WIDER THAN THE PAVEMENT MARKING LINE. CONSTRUCTION OF THE RECESSED CHANNELS SHALL BE PAID FOR SEPARATELY PER FOOT AS GROOVING FOR RECESSED PAVEMENT MARKING OF THE WIDTH SPECIFIED AND PER SQUARE FOOT FOR GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS.

2) SEE TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKING FOR GUIDANCE

FILE NAME =	USER NAME = LUSERL	DESIGNED -	JKM	REVISED -			SPRING ROAD	F.A.U.	SECTION	COUNTY	TOTAL SHEET SHEETS NO.
g:\ch09\0082\roed\sheets\PM-503-Springpm	@3.SHT	DRAWN	JKM	REVISED ~	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SPRING ROAD PAVEMENT MARKING PLAN		2672	11-00176-00-RS	DUPAGE	17 9
	PLOT SCALE = 50.000 1/ IN.	CHECKED ~	DWB	REVISED -		Offined HOAD FATERERY MAIRING FEAT			CONTRACT NO. 63588		
	PLOT DATE = 4/6/2011	DATE -	04/06/2011	REVISED -		SCALE:	SHEET NO. 3 OF 3 SHEETS STA. 148+00.00 TO STA. 151+52.00	FED. ROAD I	DIST. NO. 1 ILLINOIS FED. A	AID PROJECT	