

DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
51ST STREET		
4+33	2' RT	1
4+41	28' RT	1
53RD STREET		
40+87	2' LT	1
47+40	8' LT	1
55TH STREET		
82+88	11' RT	1
84+94	4' RT	1
92+60	10' RT	1
FAIR ELMS AVENUE		
32+98	25' LT	1
CAROLINE AVENUE		
60+66	9' LT	1
60+68	3' LT	1
60+71	33' RT	1
62+56	5' LT	1
64+04	1' LT	1
64+11	8' LT	1
64+16	4' LT	1
64+18	28' RT	1
64+55	30' RT	1
67+58	33' RT	1
TOTAL QUANTITY =		18

INLET FILTERS		
STATION	OFFSET (FEET)	QUANTITY (EACH)
49TH STREET		
10+60	1' LT	1
53RD STREET		
40+87	2' LT	1
44+50	26' RT	1
47+15	1' LT	1
55TH STREET		
83+02	26' RT	1
FAIR ELMS AVENUE		
20+19	4' RT	1
26+98	2' LT	1
32+50	5' RT	1
CAROLINE AVENUE		
60+68	3' LT	1
64+04	1' LT	1
TOTAL QUANTITY =		10

DRAINAGE & UTILITY STRUCTURES TO BE RECONSTRUCTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
FAIR ELMS AVENUE		
19+67	30' LT	1
20+33	30' LT	1
TOTAL QUANTITY =		2

FRAME AND LIDS, TYPE 1, CLOSED LID		
STATION	OFFSET (FEET)	QUANTITY (EACH)
FAIR ELMS AVENUE		
19+67	30' LT	1
20+33	30' LT	1
CAROLINE AVENUE		
60+66	9' LT	1
64+11	8' LT	1
64+16	4' LT	1
TOTAL QUANTITY =		5

HANDHOLE TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
55TH STREET		
97+67	8' RT	1
TOTAL QUANTITY =		1

VALVE BOXES TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
FAIR ELMS AVENUE		
20+35	37' LT	1
TOTAL QUANTITY =		1

DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED		
STATION	OFFSET (FEET)	QUANTITY (EACH)
FAIR ELMS AVENUE		
33+63	30' LT	1
CAROLINE AVENUE		
64+20	4' LT	1
TOTAL QUANTITY =		2

BUFFALO BOX ADJUSTMENT, SPECIAL		
STATION	OFFSET (FEET)	QUANTITY (EACH)
FAIR ELMS AVENUE		
24+81	15' RT	1
29+58	10' RT	1
TOTAL QUANTITY =		2

TREE REMOVAL (OVER 15 UNITS DIAMETER)		
STATION	OFFSET (FEET)	QUANTITY (UNIT)
CAROLINE AVENUE		
62+46	12' LT	24
63+67	11' LT	20
TOTAL QUANTITY =		44

DRIVEWAY QUANTITY SCHEDULE						
STATION	OFFSET	EXISTING PAVEMENT	REMOVE AND REINSTALL BRICK PAVER (SQ. FT.)	DRIVEWAY PAVEMENT REMOVAL (SQ. YD.)	STABILIZED DRIVEWAYS 7" (SQ. YD.)	P.C.C. DRIVEWAY PAVMT 7 INCH (SQ. YD.)
49th Street						
11+42	RT	PCC		33		25
51st Street						
2+45	RT	BRICK	14			
53rd Street						
42+50	LT	HMA		37	12	
43+50	RT	PCC		50		36
Fair Elms Avenue						
24+95	RT	HMA		19	7	
29+35	RT	PCC		26		20
29+88	RT	PCC		24		18
30+43	RT	PCC		20		16
31+20	RT	HMA		17	7	
TOTAL QUANTITY =			14	225	26	115

EARTHWORK	
LOCATION	REMOVAL & DISPOSAL OF UNSUITABLE MAT.* (CU YD)
49TH STREET: FAIR ELMS AVENUE TO STA. 12+09.90	30
51ST STREET: FAIR ELMS AVENUE TO CENTRAL AVENUE	77
53RD STREET: LAWN AVENUE TO CAROLINE AVENUE	133
55TH STREET: WOODLAND AVENUE TO WOLF ROAD	79
FAIR ELMS AVENUE: 49TH STREET TO 51ST STREET	248
CAROLINE AVENUE: 53RD STREET TO HOWARD AVENUE	106
TOTAL QUANTITY =	673


*ALL CUT MATERIAL SHALL BE HAULED OFF SITE DUE TO NO ONSITE STORAGE LOCATION

FILE NAME =	USER NAME =	DESIGNED -- BDH	REVISED --
		DRAWN -- SMP	REVISED --
		CHECKED -- BDH	REVISED --
		DATE -- 02-09-11	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
VARIOUS ROUTES

SCALE: NONE SHEET NO. 4 OF 25 SHEETS STA. _____ TO STA. _____

	JAMES J. BENES & ASSOCIATES, INC. 950 Warrenville Road, Suite 101, Lisle, Illinois 60532 Tel. (630) 719-7570 • Fax (630) 719-7589				
	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1504	09-00090-00-SW	COOK	25	4	
CONTRACT NO. 63596				ILLINOIS FED. AID PROJECT	