



ELEVATION VIEW OF CONCRETE COLLAR

NOT TO SCALE



#4 U bar 6 required per collar

NOT TO SCALE



FRONT VIEW OF CONCRETE COLLAR

NOT TO SCALE

BILL OF MATERIALS FOR CONCRETE COLLAR									
BAR	SIZE	NO.	LENGTH	SHAPE					
h	#4	12	1'-2"						
U	#4	6	9'-2"						
Ε	DESCRIPTION	V	UNIT	QTY					
* Concrete Collar			CU YD	0.78					
* Reinforcement Bars			LB	46.09					

^{*} For Information Only

NOTES:

The collar shall be constructed entirely of CLASS SI CONCRETE and in accordance with the applicable portions of section 503 of the Standard Specifications. Reinforcement Bars shall conform to section 508.

FILE NAME =	USER NAME = mendezpj	DESIGNED -	REVISED -			CONCRETE COLLAR DETAIL		F.A.P.	SECTION	COUNTY	TOTAL SHE	ET
sht-details.dgn		DRAWN ~	REVISED -	STATE OF ILLINOIS				685			329 14	쓹
	PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	LT. STA. 432 + 58.33			000		CONTRACT	NO. 6859	39
	PLOT DATE = 3/25/2011	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO	STA.	ILLINOIS FED. AID PROJE			1101 0000	\dashv