



NOTES:

1. ALL SIGNS TO BE INSTALLED AT EACH LOCATION FROM TOP TO BOTTOM AS IN THE SAME ORDER SHOWN IN THE DRAWINGS.
2. EXISTING SIGNS TO BE REMOVED/REPLACED ARE SHOWN AS DASHED IN DRAWINGS. PROPOSED SIGNS ARE SHOWN AS SOLID IN DRAWINGS.
3. DASHED LINE INDICATES EXISTING SIGN LOCATION. SOLID LINE INDICATES PROPOSED SIGN LOCATION.
4. SEE IDOT DISTRICT 4 STANDARD 780001-D4 AND HIGHWAY STANDARD 780001 FOR PAVEMENT MARKING DETAILS.
5. SEE HIGHWAY STANDARDS 720001-01, 720006-02, 720011-02, 728001-01, 7290001-01 AND 731001-01 FOR SIGN PANEL & SIGN SUPPORT DETAILS.
6. SEE HIGHWAY STANDARD 781001-03 FOR RAISED REFLECTIVE PAVEMENT MARKER DETAILS.
7. SEE SHEET 58 OF 125 FOR SIGN SCHEDULE.

FILE NAME = P:\P-09\2193 - IDOT DUR\Task-04\DWG\SH1\4_D4-9408909-pmk-s1gn01.dgn	USER NAME = .2193 Task 4_	DESIGNED ASJ	REVISED -	<p>INFRASTRUCTURE ENGINEERING 454 Fulton Street Suite 104 Peoria, IL 61602 P: 308.631.8200 F: 308.631.9211 www.infrastructure-eng.com</p>	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">PAVEMENT MARKING & SIGNAGE LOCUST STREET-RECONSTRUCTION</p>	F.A.P. RTE. 585/22	SECTION (41Z, 135) R, N, (1CS) I	COUNTY FULTON	TOTAL SHEETS 125	SHEET NO. 50		
PLOT SCALE = 1:20	CHECKED JRS	REVISED -	SCALE: 1"=20'				SHEET NO. 1 OF 11 SHEETS	STA. 5+60.00 TO STA. 10+00.00	CONTRACT NO. 68877		ILLINOIS FED. AID PROJECT D4-94-009-09		
PLOT DATE = 12/21/2010	DATE 12/21/2010	REVISED -											