

# SUMMARY OF QUANTITIES

LOCATION OF WORK:	DEWITT COUNTY	MCLEAN COUNTY
	LOCATION # 1	LOCATION # 2
	FAP 322 (US 51)	FAP 315 (ILL 136)
	S.N. 020-0047	S.N. 057-0093
	MINOR STRUCTURE REPAIR	MINOR STRUCTURE REPAIR
	RURAL	RURAL
FUNDING:	100% STATE	100% STATE
CONSTRUCTION TYPE CODE:	0014	0014

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	12.0	5.0	7.0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	71.0	29.0	42.0
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	316.0	127.0	189.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1.0		1.0
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1.0	1.0	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	1.0	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0		1.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	980.0	390.0	590.0
X7040442	TEMPORARY WATER FILLED BARRIER	FOOT	325.0	325.0	
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0	1.0	
Z0004556	HOT - MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	71.0	29.0	42.0
Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1.0	1.0	
Z0032700	KEYWAY REPAIR	FOOT	316.0	127.0	189.0

\* SPECIALTY ITEM

\* FAP 322 / FAP 315  
 \*\* POSTING MITIGATION FY2011-2  
 \*\*\* DEWITT / MCLEAN

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\keysrb\d0248810\05708	95-shr-500.dgn	DRAWN -	REVISED -			*	**	***	16	3
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT
	PLOT DATE = 2/4/2011	DATE -	REVISED -							CONTRACT NO. 70895