

SCHEDULE OF QUANTITIES

SCHEDULE OF MAINLINE RESURFACING QUANTITIES											
LOCATION					WIDTH	LENGTH	AREA	40600100	40600300	X4060627	40603310
								BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MM) IL-9.5 FG, N50 1.0 IN	HMA SURFACE COURSE 1.5 IN
								GAL	TON	TON	TON
STA.	327+00.00	TO	STA.	438+51.20	22.0	11,151.2	27,258.5	5,451.7	109.0	1,574.0	2,315.6
TOTAL =								5,451.7	109.0	1,574.0	2,316.0
USE =								5,452.0	109.0	1,574.0	2,316.0

40600982 HMA SURFACE REMOVAL-BUTT JOINT					
STATION	TO	STATION	LENGTH (FOOT)	AVE. WIDTH (FOOT)	AREA (SQ YD)
437+16.18	TO	438+51.20	135.0	32.9	493.6
TOTAL =					493.6
USE =					494.0

SCHEDULE OF INCIDENTAL RESURFACING AT SIDE ROADS									
SIDE ROAD	STATION	AVERAGE WIDTH (FT)	DEPTH (FT)	AREA (SQ FT)	AREA (SQ YD)	40800050	40600985	40800010	40800030
						INCIDENTAL HMA SURFACE (TON)	PCC SURF. REM. BUTT JOINT (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	AGGREGATE (PRIME COAT) (TON)
600E	327+43.00	78.3	10.0	783.0	87.0	6.1		8.7	0.2
625E	340+82.50	79.5	10.0	794.7	88.3	6.2		8.8	0.2
GREEN APPLE LN	405+84.60	98.1	6.0	588.6	65.4	7.3	65.4	6.5	0.1
WESTWOOD DR	430+76.20	57.5	10.0	575.1	63.9	4.5		6.4	0.1
WESTWOOD DR	434+74.00	65.7	10.0	657.0	73.0	5.1		7.3	0.2
TOTAL =						29.2	65.4	37.7	0.8
USE =						30.0	66.0	38.0	1.0

40600990 TEMPORARY RAMP			
STATION	WIDTH (FOOT)	LENGTH (FOOT)	AREA (SQ YD)
327+00.00	22.0	5.0	12.2
438+51.20	28.3	8.3	26.2
TOTAL =			38.4
USE =			39.0

STATION	XZ193400 SURVEY MARKER TY 2, (SPECIAL) (EACH)	
	339+92.85	1.0
	364+99.09	1.0
	385+02.28	1.0
	423+44.66	1.0
TOTAL =		4.0

SCHEDULE OF INCIDENTAL RESURFACING AT ENTRANCES										
SIDE	STATION	TYPE	AVERAGE WIDTH (FT)	DEPTH (FT)	AREA TO RESURF. (SQ YD)	40800050	40600982	40600985	40800010	40800030
						INCIDENTAL HMA SURFACE (TON)	HMA SURF. REM. BUTT JT. (SQ YD)	PCC SURF. REM. BUTT JT. (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	AGGREGATE (PRIME COAT) (TON)
LT	370+18.10	CE	43.0	10.0	47.7	5.4		47.7	4.8	0.1
LT	372+33.10	CE	107.7	10.0	119.7	13.4		119.7	12.0	0.24
LT	373+84.10	CE	78.4	10.0	87.1	9.8		87.1	8.7	0.17
LT	406+64.20	CE	22.1	10.0	24.5	2.8	24.5		2.5	0.05
RT	422+58.80	CE	58.9	7.0	45.8	5.1		45.8	4.6	0.09
RT	426+55.40	PE	29.8	14.5	48.0	5.4		48.0	4.8	0.1
RT	428+63.10	PE	22.6	11.7	29.4	3.3		29.4	2.9	0.06
TOTAL =						45.2	24.5	377.7	40.2	0.8
USE =						45.0	25.0	378.0	40.0	1.0

48102100 AGGREGATE WEDGE SHOULDER, TYPE B					
SIDE	STATION	TO	STATION	LENGTH (FOOT)	SHLDRS (TON)
LT	327+00.00	TO	438+61.00	11,161.0	855.7
RT	327+00.00	TO	437+16.00	11,016.0	844.6
TOTAL =					1,700.2
USE =					1,701.0

48203007 HOT-MIX ASPHALT SHOULDERS, 2 1/2"					
SIDE	STATION	TO	STATION	LENGTH (FOOT)	SHLDRS (SQ YD)
LT	437+16.18	TO	438+51.20	135.0	79.6
RT	437+16.18	TO	438+51.20	135.0	67.1
TOTAL =					146.7
USE =					147.0

PAVEMENT MARKING SCHEDULE																									
SIDE	78001110						SIDE	70300220						70300100					70301000						
	PAINT PAVEMENT MARKING - LINE 4"							TEMPORARY PAVEMENT MARKING - LINE 4"						SHORT TERM PAVEMENT MARKING					WORK ZONE PAVEMENT MARKING REMOVAL						
					(WHITE)	(YELLOW)						(WHITE)	(YELLOW)	STATION	TO	STATION	APPS	LENGTH	STATION	TO	STATION	(FOOT)	AREA		
STATION	TO	STATION	(FEET)	(FOOT)	(FOOT)	STATION	TO	STATION	(FEET)	(FOOT)	(FOOT)	(FOOT)	(FOOT)												
LT	327+00.00	TO	438+51.20	11,151.2	11,151.2	2,787.8	LT	327+00.00	TO	438+51.20	11,151.2	11,151.2	2,787.8	327+00.00	TO	438+51.20	2.0	2230.2	327+00.00	TO	438+51.20	11151.2	3679.9		
RT	327+00.00	TO	438+51.20	11,151.2	11,151.2		RT	327+00.00	TO	438+51.20	11,151.2	11,151.2													
TOTAL =				22302.4		2787.8	TOTAL =				22302.4		2787.8						2230.2						3679.9
USE =				22302.0		2788.0	USE =				22302.0		2788.0						2230.0						368.0
TOTAL LENGTH =				25090.0			TOTAL LENGTH =				25090.0														

FILE NAME =		USER NAME = coombessf		DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION						SCHEDULE OF QUANTITIES				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwidot\coombessf\d0254836\DS70921-shit-schedule.dgn				DRAWN -	REVISED -											1531	(10,11)RS	PIATT	18	8
		PLOT SCALE = 40.0000 ' / IN.		CHECKED -	REVISED -											CONTRACT NO. 70921				
		PLOT DATE = 3/4/2011		DATE -	REVISED -							SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		