DRAINAGE ITEMS

STATION	OFFSET	PIPE CULVERT CL D, TY 115"	PIPE CULVERT CL A, TY 124"	PIPE CULVERT CL A, TY 130"	PIPE CULVERT CL A, TY 136"	CONCRETE COLLAR	INLET BOX STD 542511 (TY 24 C)	INLET BOX STD 542531 (TY 24 G)	FLUSH INLET BOX FOR MEDIAN STD 542546	MANHOLE, TY A, 4' DIAMETER TY 1 FRAME CLOSED LID	MANHOLE, TY A, 6' DIAMETER TY 1 FRAME CLOSED LID	INLET BOXES TO BE ADJUSTED (SPECIAL)	24" PIPE TEE WITH 24" RISER	30" PIPE TEE WITH 24" RISER	MEDIAN INLET BOX REMOVAL
		FOOT	FOOT	FOOT	FOOT	CU YD	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
1538+44.0	RT		8			0.45	1								1
1545+00.0	RT		8			0.45	1								1
1555+50.0	RT		8			0.45	1								1
1581+50.0	LT		8			0.45	1								1
1597+00.0	CL		19			0.45		1		1					1
1607+00.0	CL											1			
1618+87.0	CL		16			1.8			1				1		1
1625+67.0	CL		8			0.9			1						1
1633+06.8	CL		10			1.8			1				1		1
1638+80.0	LT		4			0.9			2						2
1647+38.0	RT		4			0.9			2						2
1663+00.0	CL		5	8		1.14		1			1				1
1684+00.0	RT		8			2.28			2					2	1
1698+00.0	RT	55	14			2.53			2					2	1
1717+00.0	CL		14		24	2.76		2			2				2
1725+00.0	CL											1			
1771+00.0	RT		8			0.45	1								1
1809+84.0	LT		8			0.45	1								1
196+00.0	LT		8			0.45	1								1
231+00.0	RT		8			0.45	1								1
	TOTAL	55	166	8	24	19.06	8	4	11	1	3	2	2	4	21
	USE	55	166	8	24	20	8	4	11	1	3	2	2	4	21

HIGH TENSION CABLE MEDIAN BARRIER

STATION	STATION	OFFSET	DISTANCE	TERMINAL EACH	BARRIER FOOT	MOW STRIP SQ YD
BEGIN AT SN 057-0102 (CH 53)						
1536+89.0	1537+39.0	LT	50.0	1.0		22.6
1537+39.0	1567+50.0	LT	3011.0		3011.0	1358.3
1567+50.0	1568+00.0	LT	50.0	1.0		22.6
OMISSION AT SN 057-0112 (725 E RD)						
1568+39.0	1568+89.0	RT	50.0	1.0		22.6
1568+89.0	1579+97.0	RT	1108.0		1108.0	499.8
1579+97.0	1580+47.0	RT	50.0	1.0		22.6
OMISSION AT CROSSOVER AT STA. 1581+15						
1581+81.0	1582+31.0	LT	50.0	1.0		22.6
1582+31.0	1622+84.0	LT	4053.0		4053.0	1828.4
1622+84.0	1623+34.0	LT	50.0	1.0		22.6
OMISSION AT SN 057-0114 (800 E RD)						
1623+69.0	1624+19.0	RT	50.0	1.0		22.6
1624+19.0	1630+44.0	RT	625.0		625.0	281.9
1630+44.0	1630+94.0	RT	50.0	1.0		22.6
OMISSION AT CROSSOVER AT STA. 1631+50						
1632+15.0	1632+65.0	LT	50.0	1.0		22.6
1632+65.0	1694+60.0	LT	6195.0		6195.0	2794.6
1694+60.0	1695+10.0	LT	50.0	1.0		22.6
OMISSION AT EB SIGN TRUSS AT STA. 1695+16						
1695+24.0	1695+74.0	RT	50.0	1.0		22.6
1695+74.0	1723+55.0	RT	2781.0		2781.0	1254.5
1723+55.0	1724+05.0	RT	50.0	1.0		22.6
OMISSION AT CROSSOVER AT STA. 1724+70						
1725+33.0	1725+83.0	LT	50.0	1.0		22.6
1725+83.0	1737+69.0	LT	1186.0		1186.0	535.0
1737+69.0	1738+19.0	LT	50.0	1.0		22.6
SUB-TOTAL				14	18,959	8,868.4

STATION	STATION	OFFSET	DISTANCE	TERMINAL EACH	BARRIER FOOT	MOW STRIP SQ YD
OMISSION AT SN 057-0115 (1800 N RD)						
1738+45.0	1738+95.0	RT	50.0	1.0		22.6
1738+95.0	1782+18.0	RT	4323.0		4323.0	1950.2
1782+18.0	1782+68.0	RT	50.0	1.0		22.6
OMISSION AT SN 057-0045/0046						
1786+25.0	1786+75.0	RT	50.0	1.0		22.6
1786+75.0	1806+20.0	RT	1945.0		1945.0	877.4
1806+20.0	1806+70.0	RT	50.0	1.0		22.6
OMISSION AT SN 057-0073 (US 150)						
1809+22.0	1809+72.0	LT	50.0	1.0		22.6
1809+72.0	1809+99.2	LT	27.2		27.2	12.3
STA. EQN. 1809+99.22(BK) = 189+01.45 (AH)						
189+01.5	207+25.0	LT	1823.6		1823.6	822.6
207+25.0	207+75.0	LT	50.0	1.0		22.6
OMISSION AT EB SIGN TRUSS AT STA. 207+82						
207+89.0	208+39.0	RT	50.0	1.0		22.6
208+39.0	216+90.0	RT	851.0		851.0	383.9
216+90.0	217+40.0	RT	50.0	1.0		22.6
OMISSION AT CROSSOVER AT 218+00						
218+60.0	219+10.0	LT	50.0	1.0		22.6
219+10.0	246+57.0	LT	2747.0		2747.0	1239.2
246+57.0	247+07.0	LT	50.0	1.0		22.6
OMISSION AT SN 057-0105 (CH 39)						
248+05.0	248+55.0	LT	50.0	1.0		22.6
248+55.0	253+66.0	LT	511.0		511.0	230.5
253+66.0	254+16.0	LT	50.0	1.0		22.6
SUB-TOTAL				12.0	12227.8	5786.7
TOTAL				26	31,187	14,655.1
USE				26	31,187	14,656

SURVEY MARKER, TYPE 1 (SPECIAL)

POINT	STATION
PC	1669+18.82
PT	1687+75.90

REVISED SHEET 6-6-11

FILE NAME = c:\pw_work\pwidot\keysrb\d0261049\D570927-sht-schedules.dgn	USER NAME = keysrb	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/5/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	FY11 HSIP-5	MCLEAN	101	6

CONTRACT NO. 70927

ILLINOIS FED. AID PROJECT