## **INDEX OF SHEETS**

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS
2	GENERAL NOTES
2	LIST OF STANDARDS
3	SUMMARY OF QUANTITIES
4-9	EXISTING TYPICAL SECTIONS
10-12 A	SCHEDULE OF QUANTITIES
13	DETAILS OF EXISTING JOINTED P.C.C. PAVEMENT (HINGE-JOINT) AND ADJACENT P.C.C. SHOULDER

## **GENERAL NOTES**

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-442B -- PATCHING SCHEDULES

THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

NO COMMITMENTS

## **HIGHWAY STANDARDS**

STANDARD NUMBER	NAME OF STANDARD
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AND INCH AND OF A FOOT
420001-07	PAVEMENT JOINTS
420101-04	24' (7.2m) JOINTED PCC PAVEMENT
420106-04	36' ( 10.8m ) JOINTED PCC PAVEMENT
421001-02	BAR REINFORCEMENT FOR CRC PAVEMENT
421101-08	24' (7.2m) CRC PAVEMENT (WITH WIDE FLANGE BEAM TERMINAL JOINT)
442001-04	CLASS A PATCHES
442101-07	CLASS B PATCHES
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701400-05	APPROACH TO LANE CLOSURE, FREEWAY / EXPRESSWAY
701401-06	LANE CLOSURE, FREEWAY / EXPRESSWAY
701411-07	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS ≥ 45 MPH
701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS FOR SPEEDS≥45 MPH
701901-01	TRAFFIC CONTROL DEVICES

FILE NAME =	USER NAME = berganaj	DESIGNED	-	AJB	REVISED	
c:\pw_work\pwidot\bergenej\d0262495\D57		DRAWN	-	AJB	REVISED -	
	PLOT SCALE = 40.0000 '/ in.	CHECKED	-		REVISED -	
	PLOT DATE = 4/26/2011	DATE	-	3/4/2011	REVISED -	

STATE	OF	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
INDEX OF SHEETS & LIST OF HIGHWAY STANDARDS			39	D5 PATCHING 2012-2	MCLEAN	13	2
	***************************************			CONTRACT	NO. 7	0928	
Α	SHEET NO. 1 OF 1 SHEETS	STA. N/A TO STA. N/A	ILLINOIS FED. AID PROJECT				