

HOT-MIX ASPHALT SURFACE REMOVAL

TYP. SEC. #	LOCATION	QUANTITY	
		BUTT JOINT	2"
		(SQ YD)	(SQ YD)
F. A. P. 713 (IL 61)			
(1)	STA. 303+80.00 TO STA. 303+90.00	28.89	
(1)	STA. 303+90.00 TO STA. 305+19.00		372.67
(1)	STA. 305+19.00 TO STA. 305+27.00		21.78
(2)	STA. 305+27.00 TO STA. 308+89.00		925.11
(2)	STA. 308+89.00 TO STA. 309+65.00		177.33
(2)	STA. 309+65.00 TO STA. 312+76.00		794.78
(3)	STA. 312+76.00 TO STA. 313+40.00		170.67
(3)	STA. 313+40.00 TO STA. 313+50.00	26.67	
PROJECT TOTAL		56	2,463

COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
F. A. P. 713 (IL 61)		
(2)	STA. 308+87.00 TO STA. 309+67.50 RT	80.5
PROJECT TOTAL		81

STORM SEWER REMOVAL 6"

TYP. SEC. #	LOCATION	QUANTITY (FOOT)
F. A. P. 713 (IL 61)		
(2)	STA. 308+90.00 TO STA. 309+64.00 RT	74
PROJECT TOTAL		74

REMOVING INLETS

TYP. SEC. #	LOCATION	QUANTITY (EACH)
F. A. P. 713 (IL 61)		
(2)	308+89.00, 10.5' RT	1
(2)	309+65.00, 10.16' RT	1
PROJECT TOTAL		2

SIDEWALK REMOVAL

TYP. SEC. #	LOCATION	QUANTITY (SQ FT)
F. A. P. 713 (IL 61)		
(2)	STA. 308+87.00 TO STA. 308+91.00 RT	8
(2)	STA. 309+61.50 TO STA. 309+67.50 RT	27
PROJECT TOTAL		35

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	QUANTITY (EACH)
F. A. P. 713 (IL 61)	
COUNTED IN FIELD	20
PROJECT TOTAL	20

TEMPORARY RAMP

TYP. SEC. #	LOCATION	QUANTITY (SQ YD)
F. A. P. 713 (IL 61)		
(1)	STA. 303+80.00 TO STA. 303+85.00	14.44
(3)	STA. 313+45.00 TO STA. 313+50.00	13.33
PROJECT TOTAL		28

INLETS, TYPE A

TYP. SEC. #	LOCATION	QUANTITY (EACH)
F. A. P. 713 (IL 61)		
(2)	308+89.00, 10.35' RT	1
PROJECT TOTAL		1