

PAINT PAVEMENT MARKING - LINE

TYP. SEC. #	LOCATION	5"		
		YELLOW		WHITE
		SOLID (FOOT)	SKIP-DASH (FOOT)	SOLID (FOOT)
	F. A. P. 713 ( IL 61)			
( 1 )	STA. 303+80.00 TO STA. 305+27.00			294
( 1-3 )	STA. 303+80.00 TO STA. 306+69.00	289		
( 1-3 )	STA. 303+80.00 TO STA. 313+50.00		242.50	
( 3 )	STA. 312+76.00 TO STA. 313+50.00			148
	SUBTOTAL	289	242.50	442
	PROJECT TOTAL		974	

RAISED REFLECTIVE PAVEMENT MARKER

TYP. SEC. #	LOCATION	QUANTITY (EACH)
	F. A. P. 713 ( IL 61) 40' SPACING	
( 1-3 )	STA. 303+80.00 TO STA. 313+50.00	25
	PROJECT TOTAL	25

PAVEMENT SCHEDULE

TYP SEC #	LOCATION STATION TO STATION	LENGTH	PAVEMENT WIDTH	HMA SURF THICKNESS	HMA SURF REM BUTT JOINT	HMA SURF REMOVAL 2"	HMA CONC SURF CSE "C" N50	BIT MAT PRIME COAT	AGG PRIME COAT
		FOOT	FOOT	INCH	SQ YD	SQ YD	TON	TON	TON
	F. A. P. 713 ( IL 61)	-	-	-	-	-	-	-	-
( 1 )	STA. 303+80.00 TO STA. 303+90.00	10	26	-	28.89	-	-	0.01	0.06
( 1 )	STA. 303+80.00 TO STA. 305+19.00	139	26	2	-	-	44.97	-	-
( 1 )	STA. 303+90.00 TO STA. 305+19.00	129	26	-	-	372.67	-	0.14	0.75
( 1 )	STA. 305+19.00 TO STA. 305+27.00	8	24.5	2	-	21.78	2.44	0.01	0.04
( 2 )	STA. 305+27.00 TO STA. 312+76.00	749	23	2	-	-	214.38	-	-
( 2 )	STA. 305+27.00 TO STA. 308+89.00	362	23	-	-	925.11	-	0.35	1.85
( 2 )	STA. 308+89.00 TO STA. 309+65.00	76	21	2	-	177.33	-	0.07	0.35
( 2 )	STA. 309+65.00 TO STA. 312+76.00	311	23	2	-	794.78	-	0.30	1.59
( 3 )	STA. 312+76.00 TO STA. 313+50.00	74	24	2	-	-	22.10	-	-
( 3 )	STA. 312+76.00 TO STA. 313+40.00	64	24	2	-	170.67	-	0.06	0.34
( 3 )	STA. 313+40.00 TO STA. 313+50.00	10	24	-	26.67	-	-	0.01	0.05
	PROJECT TOTAL	-	-	-	56	2,463	284	1	5