RESURFACING SCHEDULE (MAINLINE PAVEMENT)

			LENGTH	PAVT WIDTH	ROAD AREA	HMA SURF REM, BUTT JOINT	HMA SURF REM 2 1/4" & VAR	HMA SURF REM VAR DEPTH	BIT (PRIME COAT)	AGG (PRIME COAT)	LEVEL BINDER 3/4", N50	HMA SURFACE, 1-1/2"	Temp Ramp
Location	Sta to Sta		FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	SQ YD
IL 10	567+94	569+06	112.0	VAR	753.0	276.7		753.0	0.3	1.5	31.6	63.3	46.1
	569+06	676+25	10,719.0	24	28,584.0			28584.0	10.9	57.2	1,200.5	2,401.1	
	676+25	685+25	900.0	24.5	2,450.0			2450.0	0.9	4.9	102.9	205.8	
	685+25	711+50	2,625.0	24	7,000.0			7000.0	2.7	14.0	294.0	588.0	
	711+50	718+71	721.0	24.5	1,962.7			1962.7	0.7	3.9	82.4	164.9	
	718+71	720+97	226.2	24	603.1	80.0		603.1	0.2	1.2	25.3	50.7	13.3
	720+97	721+46	BRIDGE OMISSION										
	721+46	798+00	7,653.5	24	20,409.4	80.0		20409.4	7.8	40.8	857.2	1,714.4	13.3
	798+00	801+02	302.0	27	906.0			906.0	0.3	1.8	38.1	76.1	
	801+02	802+04	102.0	24	272.0			272.0	0.1	0.5	11.4	22.8	
	802+04	802+62	58.0	24	154.7		154.7		0.1	0.3	6.5	13.0	
	802+62	815+12	1,250.0	24	3,333.3		3333.3		1.3	6.7	140.0	280.0	
	815+12	815+65	53.0	24	141.3		141.3		0.1	0.3	5.9	11.9	
	815+65	815+82	17.2	24	45.9	80.0		45.9	0.0	0.1	1.9	3.9	
Total IL 10					***66,616***	***517***	***3,629***	***62,986***	***25***	***133***	***2,798***	***5,596***	***73***
Safety Edge Quantity (Additional 2.5% HMA Surface Course Mix)												***140***	

HMA SHOULDER SCHEDULE

			LENGTH	SHLD WIDTH	SHLD AREA	HMA SURF REM VD	BIT (PRIME COAT)	LEVEL BINDER 3/4", N50	HMA SURFACE, 1-1/2"
Location	Sta to Sta		FT	FT	SQ YD	SQ YD	TON	TON	TON
	773+50	776+50	300.0	8.0	266.7	266.67	0.1	11.20	22.40
IL 10/ US 136 E RADIUS	567+94	569+06	182.0	4.0	80.9	80.89	0.0	3.40	6.79
IL 10/ US 136 W RADIUS	567+94	569+06	150.0	4.0	66.7	66.67	0.0	2.80	5.60
	715+50	721+05	155.0	8.0	137.8	137.78	0.1	5.79	11.57
	720+00	720+90	90.0	8.0	80.0	80.00	0.0	3.36	6.72
	721+50	722+50	100.0	8.0	88.9	88.89	0.0	3.73	7.47
	721+35	722+50	115.0	8.0	102.2	102.22	0.0	4.29	8.59
Total IL 10			***1,092.0***		***823***	***823***	***0***	***35***	***69***

TEMPORARY PAVEMENT MARKING SCHEDULE

			LENGTH	SHORT TERM PAVEMENT MARKING	SHORT TERM PAVEMENT MARKING REMOVAL
Location	Sta to Sta			Center Skip Dash	Center Skip Dash
			FT	FT	SQ FT
IL 10	567+94	815+82	24,788.2	7436	1033
Total IL 10				***7436***	***1033***

RESURFACING SCHEDULE (PARKING LANES)

			LENGTH	PARKING LANE WIDTH	PARKING LANE AREA	HMA SURF REM 2 1/4" & VAR	BIT (PRIME COAT)	AGG (PRIME COAT)	LEVEL BINDER 3/4", N50	HMA SURFACE, 1-1/2"
Location	Sta to Sta		FT	FT	SQ YD	SQ YD	TON	TON	TON	TON
IL 10	802+04	802+62	58.0	3.5	45.1	45.1	0.02	0.1	3.8	3.8
	802+62	815+12	1,250.0	7	1678.5	1678.5	0.64	3.4	141.0	141.0
	815+12	815+65	53.0	4.5	53.0	53.0	0.02	0.1	4.5	4.5
Total IL 10			***1,361.0***		***1,777***	***1,777***	***1***	***4***	***149***	***149***

AGGREGATE SHOULDER SCHEDULE

			LENGTH	AGG SHLD WIDTH	AVERAGE DEPTH	AGG SHOULDER 2"
Location	Sta to Sta		FT	FT	IN.	TON
IL 10	567+94	720+97	15,303.1	3.0	2.00	1258.7
	721+46	802+04	8,057.5	3.0	2.00	662.8
	815+65	815+82	17.2	3.0	2.00	1.4
Total IL 10			***23,377.8***			***1923***