

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE				
					ROADWAY	RETAINING WALL NO 082-W302	RETAINING WALL NO 082-W306	BRIDGE STR NO 082-0323	BRIDGE STR NO 082-0325
		URBAN							
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	165	165				
	20100500	TREE REMOVAL, ACRES	ACRE	2.25	2.25				
	20200100	EARTH EXCAVATION	CU YD	15,870	15,870				
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,206			1,206		
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	2,695	1,489		1,206		
	20400800	FURNISHED EXCAVATION	CU YD	19,335	19,335				
	20800150	TRENCH BACKFILL	CU YD	1,126	1,126				
*	25000210	SEEDING, CLASS 2A	ACRE	2.80	2.80				
*	25000305	SEEDING, CLASS 3A	ACRE	1.90	1.90				
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	425	425				
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	425	425				
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	425	425				
*	25100105	MULCH, METHOD 1	ACRE	0.10	0.10				
*	25100115	MULCH, METHOD 2	ACRE	12.00	12.00				
*	25100630	EROSION CONTROL BLANKET	SQ YD	10,154	10,154				
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	922	922				
	28000400	PERIMETER EROSION BARRIER	FOOT	7,247	7,247				
	28000500	INLET AND PIPE PROTECTION	EACH	74	74				
	28100107	STONE RIPRAP, CLASS A4	SQ YD	988	988				
	28200200	FILTER FABRIC	SQ YD	988	988				
	31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	3,656	3,656				
	35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	6,801	6,801				
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200				
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.6	0.6				
	40600300	AGGREGATE (PRIME COAT)	TON	2.0	2.0				
	40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	208	208				
	42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	3,310	3,310				
	42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	316	316				
	42001300	PROTECTIVE COAT	SQ YD	5,070	5,070				
	44000100	PAVEMENT REMOVAL	SQ YD	245	245				

* DENOTES SPECIALTY ITEM

USER NAME = Hencoc	DESIGNED - CRH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 70	SECTION 82-1-B-1	COUNTY ST. CLAIR	TOTAL SHEETS 319	SHEET NO. 5	
PLOT SCALE = 2.0000' / 1" =	CHECKED - DBM	REVISED -			SCALE: NONE	SHEET NO. 1 OF 7 SHEETS	STA. TO STA.	CONTRACT NO. 76C75		
PLOT DATE = #DATE#	DATE - 3-30-11	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					