

## SUMMARY OF QUANTITIES

					100% STATE						
					URBAN	ROADWAY	RETAINING WALL NO 082-W302	RETAINING WALL NO 082-W306	BRIDGE STR NO 082-0323	BRIDGE STR NO 082-0325	
SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0001	0040	0040	0008	0008		
	44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	784.0	784.0						
	44004000	PAVED DITCH REMOVAL	FOOT	104	104						
	44004250	PAVED SHOULDER REMOVAL	SQ YD	966	966						
	44200616	CLASS A PATCHES, TYPE I, 14 INCH	SQ YD	3	3						
	44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	30	30						
	44213000	PATCHING REINFORCEMENT	SQ YD	30	30						
	44213200	SAW CUTS	FOOT	457	457						
	48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	919	919						
	48300510	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	SQ YD	847	847						
	50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1						
	50102400	CONCRETE REMOVAL	CU YD	614	614						
	50105220	PIPE CULVERT REMOVAL	FOOT	54	54						
	50200100	STRUCTURE EXCAVATION	CU YD	6,734.4		402.0	3,682.0	653.9	1,996.5		
	50300225	CONCRETE STRUCTURES	CU YD	4,091.6	120.0	202.4	513.5	753.4	2,502.3		
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	4,205.1	47.0	69.3	177.7	761.9	3,149.2		
	50300260	BRIDGE DECK GROOVING	SQ YD	11,563				2,179	9,384		
	50300280	CONCRETE ENCASEMENT	CU YD	23.5				8.2	15.3		
	50300300	PROTECTIVE COAT	SQ YD	16,496		618	1,589	2,729	11,560		
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1				0.2	0.8		
	50500505	STUD SHEAR CONNECTORS	EACH	56,040				7,869	48,171		
	50800105	REINFORCEMENT BARS	POUND	66	66.0						
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,988,330	33,150.0	55,800	144,690	391,330	1,363,360		
	50800515	BAR SPLICERS	EACH	141				44	97		
	51100100	SLOPE WALL 4 INCH	SQ YD	890				378	512		
	51201900	FURNISHING STEEL PILES HP 14x89	FOOT	65,137				13,894	51,243		
	51202305	DRIVING PILES	FOOT	65,137				13,894	51,243		
	51203900	TEST PILE STEEL HP 14x89	EACH	12				3	9		
	51204650	PILE SHOES	EACH	601				125	476		
	51500100	NAME PLATES	EACH	4		1	1	1	1		
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	42				42			

\* DENOTES SPECIALTY ITEM

USER NAME = Henaoc PLOT SCALE = 2,0000' / 1"	DESIGNED - ORH DRAWN - CRH CHECKED - DBM DATE - 3-30-11	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 70 SECTION 82-1-B-1 COUNTY ST. CLAIR TOTAL SHEETS 319 SHEET NO. 6 CONTRACT NO. 76C75 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
			SCALE: NONE SHEET NO. 2 OF 7 SHEETS STA. TO STA.		