

## SUMMARY OF QUANTITIES

						100% STATE					
						URBAN ROADWAY	RETAINING WALL NO 082- W302	RETAINING WALL NO 082- W306	BRIDGE STR NO 082-0323	BRIDGE STR NO 082-0325	
SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY		0001	0040	0040	0008	0008	
	60205010	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	1		1					
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9		9					
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12		12					
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4		4					
	60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	4		4					
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	4		4					
	60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1		1					
	60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	9		9					
	60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	1		1					
	60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1		1					
	60500040	REMOVING MANHOLES	EACH	7		7					
	60500050	REMOVING CATCH BASINS	EACH	2		2					
	60500060	REMOVING INLETS	EACH	8		8					
	60500105	FILLING MANHOLES	EACH	1		1					
	60602500	CONCRETE GUTTER, TYPE A	FOOT	202.5		202.5					
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	61.0		61.0					
	60605300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (MODIFIED)	FOOT	725.0		725.0					
	60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	16,487		16,487					
*	63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	1		1					
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1		1					
	63200310	GUARDRAIL REMOVAL	FOOT	512		512					
	63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	239		239					
	63700805	CONCRETE BARRIER TRANSITION	FOOT	28		28					
	63700900	CONCRETE BARRIER BASE	FOOT	733		733					
	66400305	CHAIN LINK FENCE, 6'	FOOT	573		573					
	66407800	CHAIN LINK GATES, 6' X 16' DOUBLE	EACH	2		2					
	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD								
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM								
	66900530	SOIL DISPOSAL ANALYSIS	EACH								
	67100100	MOBILIZATION	L SUM	1		1					

\* DENOTES SPECIALTY ITEM

USER NAME = Henaoc	DESIGNED - CRH	REVISED -
PLOT SCALE = 2.0000' / in.	DRAWN - CRH	REVISED -
PLOT DATE = \$DATE\$	CHECKED - DBM	REVISED -
	DATE - 3-30-11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE    SHEET NO. 4 OF 7 SHEETS    STA.    TO STA.

F.A.I. RTE. 70	SECTION 82-1-B-1	COUNTY ST. CLAIR	TOTAL SHEETS 319	SHEET NO. 8
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76C75	