

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE				
					URBAN ROADWAY	RETAINING WALL NO 082-W302	RETAINING WALL NO 082-W306	BRIDGE STR NO 082-0323	BRIDGE STR NO 082-0325
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	750	750				
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	25	25				
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,115	2,115				
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	200	200				
	78200530	BARRIER WALL MARKERS, TYPE C	EACH	180	180				
	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1				
	80300100	LOCATING UNDERGROUND CABLE	FOOT	500	500				
	81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1,220	1,220				
	81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	928	928				
	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	5,968			853	5,115	
	81400100	HANDHOLE	EACH	5	5				
	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	8	8				
*	81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	130	130				
*	81603085	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	4,500	4,500				
*	81702160	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 1/0	FOOT	1,500	1,500				
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3,054	3,054				
*	86300305	CONTROLLER CABINET, TYPE III, SPECIAL	EACH	1	1				
*	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1,492	1,492				
	87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	EACH	1	1				
	87900200	DRILL EXISTING HANDHOLE	EACH	5	5				
	89502380	REMOVE EXISTING HANDHOLE	EACH	3	3				
	X0322118	REMOVE CONCRETE FLARED END SECTIONS	EACH	2	2				
	X0322628	FILL EXISTING PIEZOMETER	EACH	2	2				
	X0323255	DRILLED WELL	EACH	3	3				
*	X0325076	WIDE AREA NETWORK	L SUM	1	1				
*	X0325077	FIBER OPTIC UTILITY MARKER	EACH	7	7				
	X0326388	COMBINED SEWERS, CLASS A, TYPE 3, 21"	FOOT	20	20				
	X0326694	PLUG EXISTING STORM SEWERS	CU YD	8.1	8.1				
	X0326804	COMBINED SEWER REMOVAL 42"	FOOT	549	549				
	X0326811	ABANDON CONDUIT IN PLACE	EACH	6	6				

* DENOTES SPECIALTY ITEM