

SUMMARY OF QUANTITIES

100% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005 LOCATION 1	0005 LOCATION 2	0005 LOCATION 3	CODE NO	ITEM	UNIT		005 LOCATION 1	005 LOCATION 2	005 LOCATION 3
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.88	1.36	0.9	0.68							
40600300	AGGREGATE (PRIME COAT)	TON	9.02	6.5	4.33	3.25							
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	1346	628	359	359							
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	10259.9	4932.1	2966.7	2361.1							
48203100	HOT-MIX ASPHALT SHOULDERS	TON	377	191	106	80							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	72	48	16	8							
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	9	6	2	1							
64200105	SHOULDER RUMBLE STRIP	FOOT	1000	600	400	300							
67100100	MOBILIZATION	L SUM	1	0.4	0.3	0.3							
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	1	1								
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.4	0.3	0.3							
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.4	0.3	0.3							
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	0.4	0.3	0.3							
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1204	604	336	264							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	136	68	38	30							
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3260	1500	1000	760							
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	513	135	81	297							
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	52	32	24	16							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	52	32	24	16							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.4	0.3	0.3							
Z0018302	DRAINAGE STRUCTURES, TYPE 1 (SPECIAL)	EACH	9	6	2	1							
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.4	0.3	0.3							
	*SPECIALTY ITEM												