

GUARDRAIL SCHEDULE

LOCATION			GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	LONG-SPAN GUARDRAIL OVER CULVERT, 25 FT SPAN	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 6B	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER DIRECT APPLIED
			FT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	FOOT	EACH	EACH
SITE ID	HAZARD STATION	SIDE													
1	100+00	LT	217.0	87.5	25.0							1	33.0	2	1
1	100+00	RT	255.0	137.5	25.0						2			3	2
2	200+00	LT	453.0	62.5		162.5					2			3	2
2	200+00	RT	454.0	62.5		162.5					2			3	2
3	300+00	LT	130.0	150.0	25.0						2		64.0	3	2
3	300+00	RT	180.0	100.0			175.0				2			4	2
4	400+00	NO WORK													
5	500+00	NO WORK													
6	600+00	LT	267.0	50.0											
6	600+00	RT	378.0	125.0					2		2			2	2
7	700+00	LT	190.0	112.5	12.5				2		2			3	2
7	700+00	RT	255.0	25.0		162.5					2			2	2
8	800+00	NO WORK													
9	900+00	LT	205.0	287.5	50.0						2			5	2
9	900+00	RT	167.0	250.0	50.0						2		60.0	5	2
10	1000+00	LT	105.0	62.5		162.5					2			3	2
10	1000+00	RT	104.0	50.0		162.5					2			3	2
11	1100+00	RT	105.0	12.5							2			1	2
12	1200+00	LT	854.0	550.0					2		4			9	4
12	1200+00	RT	473.0	225.0					2		4			5	4
13	1300+00	LT	512.0	237.5					2		3		27.0	5	3
13	1300+00	RT	445.0	162.5					2		3		12.0	4	3
14	1400+00	LT	330.0	375.0						2	3		16.0	7	3
14	1400+00	RT	365.0	112.5						2	2	1	16.0	3	3
15	1500+00	LT	180.0	75.0		162.5					2			3	2
15	1500+00	RT	180.0	87.5		162.5					2			4	2
16A	1600+00	LT	404.0	175.0		162.5				1	1			5	1
16A	1600+00	RT	479.0	250.0		162.5				1	1			6	1
16B	1600+00	LT	965.0	625.0			175.0			1	1			11	1
16B	1600+00	RT	891.0	550.0			175.0			1	1			10	1
17	1700+00	LT	304.0	75.0		162.5					2			3	2
17	1700+00	RT	329.0	125.0		162.5					2			4	2
18	1800+00	LT	534.0	475.0						2	2			8	2
18	1800+00	RT	496.0	462.5						2	2			8	2
19	1900+00	RT	279.0	75.0		162.5					2			3	2
20	2000+00	LT	241.0	50.0		162.5					2			3	2
20	2000+00	RT	241.0	162.5		162.5					1	1		5	2
21	2100+00	LT	166.0	137.5	12.5						1	1		2	2
21	2100+00	RT	291.0	187.5		162.5					2			5	2
22	2200+00	LT	254.0	137.5		162.5					2			4	2
22	2200+00	RT	217.0	37.5		162.5					1	1		3	2
23	2300+00	RT	217.0	262.5		162.5					2			6	2
24	2400+00	NO WORK													
25	2500+00	LT	267.0	387.5	37.5						2			6	2
25	2500+00	RT	267.0	375.0	37.5						2			6	2
26	2600+00	LT	172.0	100.0	25.0						1	1		2	2
26	2600+00	RT	178.0	125.0	25.0						2			2	2
27	2700+00	NO WORK													
28	2800+00	LT	175.0	87.5								2		2	2
28	2800+00	RT	113.0	137.5								1		2	1
29	2900+00	LT	348.0	225.0						1	1			4	1
29	2900+00	RT	348.0	250.0						1	1			4	1
TOTALS			14,980.0	8,875.0	325.0	2,925.0	525.0	10	4	12	86	8	228.0	199	94
USE			14,980	8,875.0	325.0	2,925.0	525.0	10	4	12	86	8	228.0	199	94