

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE - 100% STATE FUNDING	
CODE NO	ITEM	Unit		ROADWAY ST. CLAIR COUNTY 0005	ROADWAY MADISON COUNTY 0005
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20.9	1.4	19.5
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	6420	479	5941
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	23004	2136.0	20868
45200300	JOINT OR CRACK FILLING	POUND	12310	720	11590
67100100	MOBILIZATION	L SUM	1		1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	9	1	8
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		1
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1		1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	11556	245	11311
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3854	82	3772
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40087	2189	37898
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5296		5296
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1912		1912
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1112	48	1064
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1112	48	1064
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1		1
Z0034105	MATERIAL TRANSFER DEVICE	TON	6420	479	5941
Z0038122	PORTLAND CEMENT CONCRETE SURFACE REMOVAL, 2 1/4"	SQ YD	27084	1348	25736
	* SPECIALTY ITEM				

FILE NAME = 08378602-SHT01-S00.W030.dgn

USER NAME = jbailey
 PLOT SCALE = 1.0000 / / IN.
 PLOT DATE = 3/30/2011

DESIGNED - D SOMMER
 DRAWN - J BAILEY
 CHECKED - T NITTLER
 DATE - 03/23/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
255	60-(7, 8) RS-1	MADISON	29	3
CONTRACT NO. 76E98			ILLINOIS FED. AID PROJECT	