

SUMMARY OF QUANTITIES

		IM FUNDING	
		90% FEDERAL	10% STATE
		CONSTRUCTION TYPE CODE	
		0005	
		JEFFERSON	
		SN 041-0003 & 041-0004	
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	327
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	32
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19, N105	TON	232
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	79
44000154	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4"	SQ YD	214
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	997
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	94
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	2
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	32
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1180
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	404
70400100	TEMPORARY CONCRETE BARRIER	FOOT	750
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	650
78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	1180
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4
78200410	GUARDRAIL MARKERS, TYPE A	EACH	3
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1
78300100	PAVEMENT MARKING REMOVAL	SQ FT	294
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	997
Z0021922	SILICONE JOINT SEALER	FOOT	164
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0041895	POLYMER CONCRETE	CU FT	3.6