

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				RECONSTRUCTION, CAPACITY ADDED 0003	SAFETY (TRAFFIC SIGNALS) 0021
42001300	PROTECTIVE COAT	SQ YD	289	289	-
44000100	PAVEMENT REMOVAL	SQ YD	951	951	-
44000168	HOT-MIX ASPHALT SURFACE REMOVAL, 4 3/4"	SQ YD	609	609	-
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	30	30	-
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	30	30	-
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	137	137	-
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	83	83	-
# 48101200	AGGREGATE SHOULDERS, TYPE B	TON	33	33	-
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	343	343	-
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3	3	-
# 50800105	REINFORCEMENT BARS	POUND	348	348	-
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	310	310	-
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	52	52	-
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2	-
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2	-
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	4	4	-
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,004	1,004	-
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	700	700	-
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1	-
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	-
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	-
63200310	GUARDRAIL REMOVAL	FOOT	600	600	-
* # 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	93	93	-
* # 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1	-
* # 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	-
67100100	MOBILIZATION	L SUM	1	1	-
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	401	401	-
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15,464	15,464	-
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	54	54	-
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,213	1,213	-

INDICATES SPECIAL PROVISION
* INDICATES SPECIALTY ITEM

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN - RM
 LICENSE NO. - 084-00021 - EXPIRES 4/30/2011
 4/24/2011 8:07:57 AM
 ...\\p101-fp-1\work\p101\22234.dgn
 ...\\p101-fp-1\work\p101\41-081068-41-88.dgn
 ...\\p101-fp-1\work\p101\41-081068-41-88.dgn
 ...\\p101-fp-1\work\p101\41-081068-41-88.dgn



DESIGNED - DJS	REVISED - 4-14-11 PER CITY REVIEW
DRAWN - UKB	REVISED -
CHECKED - RWL	REVISED -
DATE - 04-01-2011	FILE NAME - 081068-41-QNTY.dgn

**CITY OF DeKALB, ILLINOIS
PEACE ROAD
IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-01-WR	DeKALB	33	5
FED. ROAD DIST. NO. 3 (ILLINOIS)			CONTRACT NO. 87488	
FED. AID PROJECT M-5017(045)				