



**NOTES:**

1. THE INTERCONNECT CABLE SHALL BE REMOVED AND STORED IN SUCH A WAY AS TO MAINTAIN THE INTEGRITY OF THE CABLE AND INSULATION AS DETERMINED BY THE ENGINEER. THE INTERCONNECT CABLE SHALL NOT BE SPLICED OR CUT. THE INTERCONNECT CABLE SHALL BE REINSTALLED IN THE NEW 2" CONDUIT. THIS WORK SHALL BE INCLUDED IN THE COST OF REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT.
2. TEMPORARY INTERCONNECT WILL NOT BE REQUIRED.
3. THE PROPOSED 1 1/2" CONDUIT IS FOR FUTURE CITY COMMUNICATIONS. NO CABLE SHALL BE INSTALLED IN THIS CONDUIT AS A PART OF THIS PROJECT.

RESTORATION OF WORK AREA; RESTORATION OF THE INTERCONNECT WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 LICENSE NO. 184-000291 - EXPIRES 4/30/2011  
 03/20/2011



DESIGNED -	DJS	REVISED -	
DRAWN -	UKB	REVISED -	
CHECKED -	RWL	REVISED -	
DATE -	04-01-2011	FILE NAME -	081068-PH2-TS-INTERCN.dgn

**CITY OF DeKALB, ILLINOIS  
PEACE ROAD  
IMPROVEMENTS**

**TRAFFIC SIGNAL  
INTERCONNECT PLAN**

SCALE: 1"=40'      STA. 114+10      TO STA. 126+52

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5369	06-00172-01-WR	DeKALB	33	24
CONTRACT NO. 87488				
FED. ROAD DIST. NO. 3   ILLINOIS   FED. AID PROJECT M-5017045				