

LANDSCAPE SCHEDULE

LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER) (20100110)	TREE REMOVAL (OVER 15 UNITS DIAMETER) (20100210)	SEEDING, CLASS 1A (25000110)	NITROGEN FERTILIZER NUTRIENT (25000400)	PHOSPHORUS FERTILIZER NUTRIENT (25000500)	POTASSIUM FERTILIZER NUTRIENT (25000600)	MULCH, METHOD 2 (25100115)
	UNIT	UNIT	ACRE	POUND	POUND	POUND	ACRE
BUCHANAN STREET			0.16	15	15	15	0.16
CENTER STREET			0.02	2	2	2	0.02
WASHINGTON STREET			0.42	38	38	38	0.42
STA 49+56, 24' LT	12						
STA 196+03, 23' RT	12						
STA 200+70, 18' LT		35					
STA 201+02, 18' LT		35					
STA 201+46, 22' RT		33					
STA 202+32, 21' LT		16					
STA 202+51, 35' LT		18					
STA 202+52, 58' LT		24					
STA 203+06, 38' LT	8						
STA 203+06, 38' LT	6						
STA 203+06, 38' LT	10						
TOTALS	48	161	0.60	55	55	55	0.60

PAVEMENT REMOVAL SCHEDULE

LOCATION	PAVEMENT REMOVAL (44000100)
	SQ YD
NW CORNER BUCHANAN/WASHINGTON	1.7
NW CORNER EMERSON/WASHINGTON	4.3
SW CORNER EMERSON/WASHINGTON	1.4
NE CORNER EMERSON/WASHINGTON	3.3
NW CORNER CHASE/WASHINGTON	2.5
NE CORNER CHASE/WASHINGTON	2.1
NW CORNER COLFAX/WASHINGTON	2.1
SW CORNER COLFAX/WASHINGTON	2.5
NE CORNER COLFAX/WASHINGTON	2.5
SE CORNER COLFAX/WASHINGTON	3.0
NW CORNER GREELY/WASHINGTON	4.4
NE CORNER GREELY/WASHINGTON	2.0
STA 317+44.18 TO STA 317+88.09, LT	7.7
NE CORNER CENTER/BUCHANAN	0.6
SE CORNER CENTER/BUCHANAN	0.3
SE CORNER BUCHANAN/LIVINGSTON	0.6
TOTAL	41

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (20200100)	INCIDENTAL EXCAVATION	TOTAL EXCAVATION
	CU YD	CU YD	CU YD
FOR 12" AGGREGATE SUBGRADE	735		735
FOR WIDENING & CURB AND GUTTER		173	173
FOR DRIVEWAY WIDENING		10	10
FOR SIDEWALK CONSTRUCTION		167	167
FOR HMA SHOULDERS	185		185
FOR BLOCK RETAINING WALL CONSTRUCTION		50	50
FOR RR CROSSING		20	20
TOTALS	920	420	1340

DRIVEWAY PAVEMENT REMOVAL SCHEDULE

LOCATION	DRIVEWAY PAVEMENT REMOVAL (44000200)
	SQ YD
STA 49+17.37, LT	13.1
STA 49+22.00, RT	10.8
STA 195+36.00, LT	14.8
STA 195+91.38, LT	16.5
STA 195+92.39, RT	15.2
STA 196+62.12, RT	16.8
STA 196+74.58, LT	26.8
STA 197+18.57, RT	13.2
STA 197+65.03, RT	32.4
STA 198+69.29, LT	28.4
STA 201+17.60, RT	13.6
STA 201+34.76, RT	14.1
STA 201+43.24, LT	33.7
STA 312+60.10, RT	8.6
TOTAL	258

PCC SURFACE REMOVAL - BUTT JOINT SCHEDULE

LOCATION	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT (40600985)
	SQ YD
CENTER STREET	129
CHAUCER BOULEVARD	138
WEST MIDDLE SCHOOL ENTRANCE	61
TOTAL	328

TEMPORARY RAMP SCHEDULE

LOCATION	TEMPORARY RAMP (40600990)
	SQ YD
CENTER STREET	20
BUCHANAN STREET RR CROSSING	33
CHAUCER BOULEVARD	27
WEST MIDDLE SCHOOL ENTRANCE	14
EACH END OF WASHINGTON STREET PATCHING	15
TOTAL	109

AGGREGATE FOR TEMPORARY ACCESS SCHEDULE

LOCATION	AGGREGATE FOR TEMPORARY ACCESS (40201000)
	TON
STA 49+17.37, LT	3
STA 49+22.00, RT	4
STA 195+36.00, LT	4
STA 195+91.38, LT	4
STA 195+92.39, RT	3
STA 196+62.12, RT	7
STA 196+74.58, LT	8
STA 197+18.57, RT	0
STA 197+65.03, RT	9
STA 198+69.29, LT	5
STA 201+17.60, RT	5
STA 201+34.76, RT	4
STA 201+43.24, LT	8
TOTAL	64

TREE SCHEDULE

LOCATION	AUTUMN BLAZE FREEMAN MAPLE (A2000116)
	EACH
401 WASHINGTON ST.	1
MONTICELLO CITY LIMITS	8
TOTAL	9

PIPE UNDERDRAINS SCHEDULE

LOCATION	CONCRETE HEADWALLS FOR PIPE DRAINS (60100060)	PIPE UNDERDRAINS PERF CORR STL OR ALUM 6" (60109200)
	EACH	FOOT
STA 318+50, 2' LT TO STA 318+50, 20' LT	1	18
STA 321+50, 2' LT TO STA 321+50, 20' LT	1	18
STA 325+00, 2' LT TO STA 325+00, 20' LT	1	18
STA 327+50, 2' LT TO STA 327+50, 20' LT	1	18
STA 330+00, 2' LT TO STA 330+00, 20' LT	1	18
STA 332+50, 2' LT TO STA 332+50, 20' LT	1	18
STA 334+50, 2' LT TO STA 334+50, 20' LT	1	18
TOTALS	7	126

USER: HAS
TIME: 16:03:24 PM
FILE: 44502.S.NIG.CV.L.dgn
SCALE: B084 7 IN.



DESIGNED BY: ELH	01/11	SCALE: NONE	NO.	DATE	REVISION	APVD
DRAWN BY: HAS	01/11	DATE: MAR. 25, 2011				
CHECKED BY: ELH	03/11	JOB NO. 445.02				
APPROVED BY: RDP	03/11					

MONTICELLO TRANSPORTATION IMPROVEMENT PROJECT
CITY OF MONTICELLO

SCHEDULES OF QUANTITIES

DRAWING NUMBER
10
1 OF 3