

# SUMMARY OF QUANTITIES

ROUTE:	FAP 869 (IL 14)						
LOCATION:	RURAL - STP						
FUNDING:	80% FEDERAL / 20% STATE						80% FED/10%STATE/10% CITY
COUNTY:	PERRY			FRANKLIN		FRANKLIN	
CONSTRUCTION TYPE:	ROADWAY	BRIDGE SN 073-0036	BRIDGE SN 073-0038	BOX CULVERT SN 073-2000	ROADWAY	BOX CULVERT SN 028-7119	CITY: CHRISTOPHER ROADWAY
TYPE CODE:	0004	0011	0011	0004	0004	0011	0004

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE SN 073-0036	BRIDGE SN 073-0038	BOX CULVERT SN 073-2000	ROADWAY	BOX CULVERT SN 028-7119	CITY: CHRISTOPHER ROADWAY
28200200	FILTER FABRIC	SQ YD	2489		1024	1465				IL 14 STA 493+00 TO STA 519+77
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	2598				150	2448		
35100100	AGGREGATE BASE COURSE, TYPE A	TON	427					427		
35501324	HOT•MIX ASPHALT BASE COURSE, 10"	SQ YD	1678		787	891				
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	855	281				574		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	400	75			25	300		
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15,510	2178				13,332		
40600300	AGGREGATE (PRIME COAT)	TON	128	18				110		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	5,985	845				5,140		
40600982	HOT•MIX ASPHALT SURFACE REMOVAL • BUTT JOINT	SQ YD	183	61				122		
40600990	TEMPORARY RAMP	SQ YD	162	12				150		
40603345	HOT•MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	7,189	1016				6,173		
40800050	INCIDENTAL HOT•MIX ASPHALT SURFACING	TON	537	11				526		
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	2062					1954	108	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	102		51	51				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	20					20		
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	824					824		
44000100	PAVEMENT REMOVAL	SQ YD	2286		128	154	150	1746	108	
44000153	HOT•MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	4995							4995
44000155	HOT•MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	7,606	12040				6,402		
44000160	HOT•MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	9347					9347		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	728					728		
44000400	GUTTER REMOVAL	FOOT	4667					4667		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1477					1477		
44201299	DOWEL BARS 1 1/2"	EACH	46						46	
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	220	0				220		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	2357	268				2089		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	378	53				325		
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	496				124	372		
44213200	SAW CUTS	FOOT	44						44	
44213204	TIE BARS 3/4"	EACH	36						36	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3,501	4951				3,006		
48100100	AGGREGATE SHOULDERS, TYPE A	TON	2,386	378				2,008		
48203029	HOT•MIX ASPHALT SHOULDERS, 8"	SQ YD	41997	6202				35795		
48203100	HOT•MIX ASPHALT SHOULDERS	TON	393	83				77		233
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1					

FILE NAME =	USER NAME = colenn	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw_work\pwwid\colenn\dms43654\d98183p1.m32		DRAWN -	REVISED -			869	(1-1,1,3,6)R-1,RS-3;(1,3,6)B-2		299	6	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			SCALE: 50      SHEET NO. OF SHEETS      STA.      TO STA.					
PLOT DATE = 3/25/2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT *PERRY & FRANKLIN COUNTY					