

SUMMARY OF QUANTITIES

ROUTE:	FAP 869 (IL 14)					
LOCATION:	RURAL-STP					
FUNDING:	80% FEDERAL / 20% STATE				80% FED/10%STATE/10% CITY	
COUNTY:	PERRY			FRANKLIN		FRANKLIN
CONSTRUCTION TYPE:	ROADWAY	BRIDGE SN 073-0036	BRIDGE SN 073-0038	BOX CULVERT SN 073-2000	ROADWAY	BOX CULVERT SN 028-7119
TYPE CODE:	0004	0011	0011	0004	0004	0011

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE SN 073-0036	BRIDGE SN 073-0038	BOX CULVERT SN 073-2000	ROADWAY	BOX CULVERT SN 028-7119	CITY: CHRISTOPHER ROADWAY 0004
52100520	ANCHOR BOLTS, 1"	EACH	52		24	28				IL 14 STA 493+00 TO STA 519+77
52100540	ANCHOR BOLTS, 1 1/2"	EACH	28			28				
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2					2		
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2					2		
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	2					2		
54001004	BOX CULVERT END SECTIONS, CULVERT NO. 4	EACH	2					2		
54001005	BOX CULVERT END SECTIONS, CULVERT NO. 5	EACH	1					1		
54002020	EXPANSION BOLTS 3/4 INCH	EACH	30						30	
54003000	CONCRETE BOX CULVERTS	CU YD	57.8						57.8	
54010202	PRECAST CONCRETE BOX CULVERTS 2' X 2'	FOOT	8					8		
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	52					52		
54010504	PRECAST CONCRETE BOX CULVERTS 5' X 4'	FOOT	4					4		
54010603	PRECAST CONCRETE BOX CULVERTS 6' X 3'	FOOT	74					74		
54010804	PRECAST CONCRETE BOX CULVERTS 8' X 4'	FOOT	56					56		
54010909	PRECAST CONCRETE BOX CULVERTS 9' X 9'	FOOT	48						48	
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	124					124		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	347					347		
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	32					32		
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	56					56		
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND*SIZE 24"	FOOT	104					104		
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND*SIZE 30"	FOOT	456					456		
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	541					541		
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	906					906		
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	184					184		
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	144					144		
542D0235	PIPE CULVERTS, CLASS D, TYPE 1 30"	FOOT	25					25		
542D1057	PIPE CULVERTS, CLASS D, TYPE 2 12"	FOOT	90					90		
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	120					120		
54213447	END SECTIONS 12"	EACH	32					32		
54213450	END SECTIONS 15"	EACH	54					54		
54213453	END SECTIONS 18"	EACH	10					10		
54213459	END SECTIONS 24"	EACH	8					8		
54213465	END SECTIONS 30"	EACH	2					2		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2					2		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	19					19		
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2					2		

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\colemm\dms43654\d90183p1.m32		DRAWN -	REVISED -			869	(1-1,1,3,6)R-1,RS-3x(1,3,6)B-2	*	299	8	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 98797					
PLOT DATE = 3/25/2011		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
						SCALE: 50 SHEET NO. OF SHEETS STA. TO STA.					