

SUMMARY OF QUANTITIES

ROUTE:	FAP 869 (IL 14)					
LOCATION:	RURAL - STP					
FUNDING:	80% FEDERAL / 20% STATE				80% FED/10%STATE/10% CITY	
COUNTY:	PERRY			FRANKLIN		
CONSTRUCTION TYPE:	ROADWAY	BRIDGE SN 073-0036	BRIDGE SN 073-0038	BOX CULVERT SN 073-2000	ROADWAY	BOX CULVERT SN 028-7119
TYPE CODE:	0004	0011	0011	0004	0004	0011

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE SN 073-0036	BRIDGE SN 073-0038	BOX CULVERT SN 073-2000	ROADWAY	BOX CULVERT SN 028-7119	CITY: CHRISTOPHER ROADWAY 0004
							ROADWAY SUBBASE IMPROVEMENT			IL 14 STA 493+00 TO STA 519+77
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2					2		
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	4					4		
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	16					16		
54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	2					2		
54215430	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 30"	EACH	2					2		
54248510	CONCRETE COLLAR	CU YD	8					8		
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	148					148		
55100700	STORM SEWER REMOVAL 15"	FOOT	143					143		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	164		106	58				
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1					1		
60500040	REMOVING MANHOLES	EACH	1					1		
60500060	REMOVING INLETS	EACH	6					6		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	23					23		
60602500	CONCRETE GUTTER, TYPE A	FOOT	165					165		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B*6.12	FOOT	1016					1016		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B*6.24	FOOT	322					322		
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1000				375	375	250	
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	25						25	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8		4	4				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	19		4	4	4	4	3	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1						1	
63200310	GUARDRAIL REMOVAL	FOOT	1226		423	322		305	176	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	44	4				40		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	23	3				20		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	3				21		
67100100	MOBILIZATION	L SUM	1	0.15				0.85		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2		1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		0.35	0.4		0.25		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.1				0.9		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.1	0.1	0.1		0.7		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.1				0.9		
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1				0.5		0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	10				40		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2		1	1				
70106700	TEMPORARY RUMBLE STRIPS	EACH	12		6	6				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	0.75			0.75	13.75	0.75	

*SPECIALTY ITEM

FILE NAME =	USER NAME = colemm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cc:\pwork\pwork\dot\colemm\dms13654\d901893p1.m32		DRAWN -	REVISED -			869	(1-1.1,3,6)R-1,RS-3;(1,3,6)B-2	*	299	9
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -							CONTRACT NO. 98797
PLOT DATE = 3/25/2011		DATE -	REVISED -		SCALE: 50	SHEET NO. OF SHEETS		STA. TO STA.		ILLINOIS FED. AID PROJECT