

FENCE REMOVAL SCHEDULE

STATION TO STATION	LT/RT	FENCE REMOVAL
		FOOT
FRANKLIN COUNTY		
STA 371+45 TO STA 375+47	LT	440
STA 375+77 TO STA 383+41	LT	794
PROJECT TOTAL		1234

V-GUTTER SCHEDULE

STATION	LT/RT	CLASS SI CONCRETE (OUTLET)	CONCRETE GUTTER, TYPE A
		CU YD	FOOT
FRANKLIN COUNTY			
STA 375+74 TO STA 375+86	LT	1	
STA 375+86 TO STA 377+12	LT		126
STA 377+12 TO STA 377+19	LT	2	
STA 377+19 TO STA 377+54	LT	9	
STA 377+54 TO STA 377+61	LT	2	
STA 377+61 TO STA 378+00	LT		39
STA 378+00 TO STA 378+40	LT	4	
STA 378+40 TO STA 379+00	LT	5	
		23	165

EXTRA 2' OF HMA SHOULDER REQUIRED THROUGH V-GUTTER AREA CAN BE FOUND IN RESURFACING SCHEDULE

IL 14/IL 148 INTERSECTON SCHEDULE

LOCATION STATION TO STATION	REMOVAL ITEMS						PROPOSED ITEMS								
	DRIVEWAY PAVEMENT REMOVAL	PAVEMENT REMOVAL	STORM SEWER REMOVAL 15"	REMOVING MANHOLES	REMOVING INLETS	COMBINATION CURB AND GUTTER REMOVAL	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	AGGREGATE FOR TEMPORARY ACCESS	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	STORM SEWERS, CLASS A, TYPE 1 18"	INLETS, SPECIAL	POROUS GRANULAR BACKFILL
	SQ YD	SQ YD	FOOT	EACH	EACH	FOOT	SQ YD	SQ YD	SQ YD	TON	FOOT	FOOT	FOOT	EACH	CU YD
FRANKLIN COUNTY															
MAINLINE															
STA 519+76.83 TO STA 532+34.20 (IL 14)		1746	39	1			1954	2448		62			57		7
STA 407+47.66 TO STA 1032+50.86 (IL 148)															
NORTHWEST QUADRANT	118				1	373				129	45	164	164	1	
NORTHEAST QUADRANT	227		104		1	525				152	52	302	158	91	3
SOUTHEAST QUADRANT	206					217				69	24	246			
SOUTHWEST QUADRANT	177					362				99	34	304			
TOTALS	728	1746	143	1	2	1477	1954	2448	449	217	1016	322	148	4	27

ALL CURB AND GUTTER REMOVAL IN THE PAVEMENT REPLACEMENT AREA AT THE IL14/IL 148 INTERSECTION WILL BE PAID FOR AS COMBINATION CURB AND GUTTER REMOVAL.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES: FENCE REMOVAL, V-GUTTER AND IL 14/IL 148 INTERSECTION	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			869	(1-1,1,3,6)R-1,RS-3(1,3,6)B-2	*	299	18	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			CONTRACT NO. 98797					
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE: 50	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		

*PERRY & FRANKLIN COUNTY