

# SIDEROAD & ENTRANCE SCHEDULE

STATION	LT/RT	TYPE OF ENTRANCE	EXISTING SURFACE TYPE	PROPOSED WIDTH AT END OF APRON	PROPOSED SURFACE TYPE	MINIMUM RADIUS	PROPOSED AREA*	INCIDENTAL HOT-MIX ASPHALT SURFACING TON	AGGREGATE SHOULDERS, TYPE A TON	AGGREGATE SURFACE COURSE, TYPE A TON	AGGREGATE BASE COURSE, TYPE A TON	PCC DRIVEWAY PAVEMENT 6 INCH	PCC DRIVEWAY PAVEMENT 7 INCH	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON
				FOOT			SQ FT					SQ YD	SQ YD		
PERRY COUNTY:															
178+22.65	LT	PE	AGG	18	AGG	15	47.02	3.0	2.0						
179+33.43	RT	FE	EARTH	18 NO PIPE	EARTH										
179+83.88	LT	PE	AGG	20	AGG	15	42.3	3.0							
182+57.73	LT	PE	AGG	12	AGG	15	332	2.0		13.0					
184+78.93	LT	FE	AGG		AGG		W/ SHLDR								
185+11.35	RT	FE	AGG		AGG		W/ SHLDR								
188+41.47	LT	PE	AGG	18	AGG	15	42.25	3.0							
225+50.00	RT	FE****	AGG	12 SURF	AGG	15	4868			185.0					
227+80.36	LT	FE	AGG		AGG	15	2185			83.0					
227+88.04	RT	FE****	AGG	RELOCATED											
PERRY COUNTY TOTAL															
								11.0	2.0	281.0	0.0	0.0	0.0	0.0	0.0
FRANKLIN COUNTY:															
230+81.31	RT	FE	AGG		AGG	15	2023			77.0					
236+06.39	LT	FE	AGG		AGG		W/ SHLDR								
244+33.72	LT	FE	AGG		AGG		W/ SHLDR								
251+11.82	RT	CE	AGG	35	AGG	15	72.53	4.0	4.0						
264+46.90	LT	FE	AGG		AGG		W/ SHLDR								
264+56.98	RT	ARKANSAS RD	O & C	37	HMA	50	146.02	24.0			45.0			9.0	0.1
270+94.96	LT	FE	AGG	12 SURF	AGG		W/ SHLDR								
276+87.73	RT	CE	AGG	35	AGG	15	72.41	4.0	4.0						
277+30.65	LT	PE	AGG	12	AGG	15	28.39	2.0		7.0					
283+78.96	LT	FE	EARTH	22 PIPE REQ	EARTH	15	0								
284+11.45	RT	PE	AGG	24	AGG	15	50.63	3.0		11.0					
285+32.73	RT	PE	AGG	12	AGG	15	30.19	2.0		5.0					
285+87.04	LT	FE	EARTH	22 PIPE REQ	EARTH	15	0	0.0							
287+00.00	RT	FE	AGG	12	AGG	15	200			8.0					
288+01.65	RT	PE	AGG	15	AGG	15	29.46	2.0							
291+38.50	LT	SECTION LINE RD	O & C	18	HMA	25	45.26	10.0			21.0			5.0	0.1
291+40.19	RT	SECTION LINE RD	O & C	18	HMA	25	58.11	11.0			18.0			4.0	0.1
297+77.66	LT	PE	AGG	15	AGG	15	40.03	2.0		9.0					
303+36.51	LT	PE	HMA	21	HMA	15	44.42	3.0							
305+82.52	RT	PE	AGG	12	AGG	15	39.36	2.0		7.0					
317+89.01	RT	FE	EARTH	22 PIPE REQ	EARTH	15	0								
317+96.80	LT	PE	AGG	18	AGG	25	62.99	4.0			16.0				
328+04.20	LT	CE	CONC	35	CONC	25	87.32	5.0					87.0		
330+00.00	RT	PE	AGG	12	AGG	15	25.48	2.0	2.0						
331+09.56	RT	PE	AGG	12	AGG	15	26.48	2.0	2.0						
332+80.93	RT	PE	AGG	12	AGG	15	33.31	2.0		9.0					
333+71.54	RT	PE	AGG	12	AGG	15	33.01	2.0		9.0					
336+84.61	RT	PE	AGG	12	AGG	15	25.67	2.0							
340+00.00	RT	CE	AGG	14	AGG	15	29.23	2.0		9.0					
342+32.77	RT	PE	AGG	12	AGG	15	25.2	2.0		2.0					
345+45.23	LT	MULKEYTOWN RD	HMA	29 SKEWED	HMA	25/60	107.23	38.0						7.0	0.1
345+57.90	RT	MULKEYTOWN RD ***	HMA	142 @ SHLDR	HMA	100	293.51	15.0							
347+58.45	RT	CE	AGG	35	AGG	15	72.48	4.0		14.0					
348+23.70	RT	CE	AGG	35	AGG	15	72.23	4.0		15.0					
349+91.86	RT	CE	CONC	18	CONC	15	37.85	2.0					28.0		
350+04.05	LT	PE	HMA	12	HMA	15	26.11	4.0			4.0			2.0	0.1
352+07.27	RT	PE	AGG	17	AGG	15	46.08	3.0		14.0					
354+34.42	LT	PE	AGG	12	AGG	15	44.66	3.0		6.0					
356+23.36	RT	PE	AGG	12	AGG	15	25.43	2.0		6.0					
357+08.67	RT	PE	AGG	12	AGG	15	37.39	2.0		7.0					
357+62.64	LT	PE	AGG	24	AGG	15	50.27	3.0							
359+78.68	RT	PE	AGG	12	AGG	15	32.35	2.0		7.0					
361+46.31	RT	FE	EARTH	22 PIPE REQ	EARTH	15	0	0.0							
366+32.00	RT	PE	AGG	13	AGG	15	43.2	3.0		2.0					
371+13.92	LT	FE	EARTH	22 PIPE REQ	EARTH	15	0	0.0							
371+30.50	RT	VAINZANDT RD	O & C	18	HMA	25	51.7	10.0			19.0			4.0	0.1
373+36.11	LT	CE	AGG	14	AGG	15	35.88	2.0		8.0					
374+61.71	LT	CE	AGG	21	AGG	25	61.6	4.0		9.0					
375+62.28	LT	CE	AGG	29	AGG	15	60.81	4.0							
377+36.10	LT	CE**	CONC	17	CONC	15	CL SI CON OUTLET								
377+72.00	RT	PE	AGG	24	AGG	15	49.37	3.0		38.0					
384+76.80	LT	TYRONE RD	O & C	18	HMA	30	65.42	17.0			36.0			7.0	0.1
SUBTOTAL								239.0	16.0	857.0	143.0	0.0	115.0	38.0	0.7

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES: SIDEROAD AND ENTRANCE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			869	(1-1,1,3,6)R-1,RS-3(1,3,6)B-2	*	299	20	
PLOT SCALE = #SCALE#		CHECKED -	REVISED -			CONTRACT NO. 98797					
PLOT DATE = #DATE#		DATE -	REVISED -			ILLINOIS FED. AID PROJECT *PERRY & FRANKLIN COUNTY					