

## PAVEMENT MARKING SCHEDULE

LOCATION FROM TO	MARKING DESCRIPTION	TOTAL LENGTH	PAINT PAVEMENT MARKING				POLYUREA PAVEMENT MARKING TYPE I			
			YELLOW		WHITE		YELLOW	WHITE		
			LINE 4" FOOT	LINE 4" FOOT	LINE 24" FOOT	LTRS & SYMB SQ FT	LINE 4" FOOT	LINE 4" FOOT	LINE 24" FOOT	
<b>MAINLINE</b>										
<b>PERRY COUNTY</b>										
177+00.00	190+05.50	PASSING	1306	330	2611					
190+05.50	191+94.50	PASSING / SN 073-0013	189			50	378			
191+94.50	228+20.50	PASSING	3626	910	7252					
<b>PERRY COUNTY TOTALS</b>				<b>1240</b>	<b>9863</b>		<b>50</b>	<b>378</b>		
<b>FRANKLIN COUNTY</b>										
228+20.50	262+00.00	PASSING	3380	850	6759					
262+00.00	269+25.00	NO PASSING RIGHT	725	915	1450					
269+25.00	271+50.00	PASSING	225	60	450					
271+50.00	280+00.00	NO PASSING LEFT	850	1070	1700					
280+00.00	321+00.00	PASSING	4100	1030	8200					
321+00.00	326+46.00	NO PASSING RIGHT	546	686	1092					
ILLINOIS CENTRAL RR CL STA 326+46			(6) 24" WHITE BARS							
			(4) RAILROAD "R" 6 FT					14.4		
326+46.00			(2) RAILROAD "X" 20 FT					108.0		
			NO PASSING LEFT			454	574	908		
331+00.00	343+25.00	PASSING	1225	310	2450					
343+25.00	345+57.00	NO PASSING RIGHT	232	292	464					
MULKEYTOWN ROAD RT STA 345+57			STOP BAR							
			LEFT ARROW					15.6		
345+57.00			RIGHT ARROW					15.6		
			NO PASSING RIGHT			618	778	1236		
351+75.00	358+00.00	PASSING	625	160	1250					
358+00.00	364+00.00	NO PASSING LEFT	600	750	1200					
364+00.00	368+50.00	PASSING	450	120	900					
368+50.00	375+00.00	NO PASSING RIGHT	650	820	1300					
375+00.00	379+50.00	PASSING	450	120	900					
379+50.00	386+00.00	NO PASSING LEFT	650	820	1300					
386+00.00	410+25.00	PASSING	2425	610	4850					
410+25.00	418+25.00	NO PASSING RIGHT	800	1000	1600					
418+25.00	420+25.00	PASSING	200	50	400					
420+25.00	428+75.00	NO PASSING LEFT	850	1070	1700					
428+75.00	521+05.00	PASSING	9230	2310	18460					
IL 14 / IL 148 INTERSECTION STA 519+77 TO STA 532+34 (IL 14) STA 1032+51 TO STA 407+48 (IL 148)			PASSING & EDGE LINES				140	824		
			WEST STOP BAR							19
			SOUTH STOP BAR							21
			EAST STOP BAR							19
521+05.00			NORTH STOP BAR					22		
			PASSING			995	250	1990		
531+00.00	534+00.00	NO PASSING	300	600	600					
534+00.00	542+50.00	NO PASSING LEFT	850	1070	1700					
<b>FRANKLIN COUNTY TOTALS</b>				<b>16315</b>	<b>62859</b>	<b>104</b>	<b>153.6</b>	<b>140</b>	<b>824</b>	<b>81</b>
SUBTOTALS				17555	72722	104	153.6	190	1202	81
<b>TOTALS</b>				<b>90277</b>		<b>104</b>	<b>153.6</b>	<b>1392</b>		<b>81</b>

NOTE: ALL STATIONS ARE APPROXIMATE  
TEMPORARY PVT MK TOTAL = POLYUREA PVT MK + PAINT PVT MK

## SEEDING SCHEDULE

LOCATION STATION TO STATION	SEEDING, CLASS 2 (MODIFIED)	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
<b>PERRY COUNTY</b>							
Sta. 177+00 to Sta. 229+00	5.0	5.0	808	606	606	10.0	10.1
<b>JACKSON COUNTY</b>							
Sta. 229+00 to Sta. 493+00	19.3	19.3	3086	2314	2314	39.0	38.6
<b>IMPROVEMENT TOTALS:</b>	<b>24.3</b>	<b>24.3</b>	<b>3894.0</b>	<b>2920.0</b>	<b>2920.0</b>	<b>49.0</b>	<b>48.7</b>

## RIGHT-OF-WAY MARKER SCHEDULE

STATION TO STATION	LT/RT	OFFSET FEET	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	
			METHOD A	METHOD B
			EACH	
<b>PERRY COUNTY</b>				
192+25.00	LT	80	1	
192+25.00	LT	90	1	
196+00.00	LT	90	1	
196+00.00	LT	80	1	
<b>PERRY COUNTY TOTAL</b>				<b>4</b>
<b>FRANKLIN COUNTY</b>				
278+06.00	LT	50	1	
291+16.65	LT	50	1	
291+59.71	RT	50	1	
297+94.00	LT	60	1	
310+87.00	RT	50	1	
311+09.00	LT	60	1	
326+70.82	LT	50	1	
331+65.00	RT	30	1	
331+65.00	RT	50	1	
335+45.00	RT	50		1
336+96.00	RT	60		1
339+39.00	LT	50		1
342+04.00	RT	60	1	
345+39.64	LT	40	1	
347+71.00	LT	40	1	
351+05.00	RT	60	1	
357+66.00	RT	60	1	
371+22.84	RT	60	1	
371+24.90	LT	60	1	
376+07.00	LT	60	1	
376+07.00	LT	55	1	
378+11.00	LT	55	1	
378+11.00	LT	60	1	
383+00.00	LT	60	1	
383+00.00	LT	70	1	
384+57.52	LT	70	1	
384+97.31	LT	55	1	
386+00.00	LT	55	1	
386+00.00	LT	50	1	
390+94.07	RT	60	1	
390+93.60	RT	80	1	
393+50.00	RT	80	1	
393+50.00	RT	60	1	
396+18.00	RT	60	1	
411+46.04	RT	60	1	
415+00.00	RT	60	1	
415+00.00	RT	50	1	
418+72.70	RT	50	1	
418+72.70	RT	60	1	
428+16.32	RT	60	1	
<b>FRANKLIN COUNTY TOTAL</b>			<b>37</b>	<b>3</b>
<b>PROJECT TOTAL</b>			<b>40</b>	<b>44</b>

## DITCH CHECK REMOVAL SCHEDULE

STATION	LT/RT	DITCH CHECK REMOVAL (FOR INFORMATION ONLY) SEE NOTE
<b>FRANKLIN COUNTY</b>		
265+87	RT	1
266+57	RT	1
267+17	RT	1
267+77	RT	1
268+37	RT	1
268+97	RT	1
		<b>6</b>

DITCH CHECK REMOVAL WILL BE INCLUDED IN THE COST OF EARTHWORK  
ACCORDING TO ARTICLE 201.01 (a).