

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	SHEET INDEX AND SUMMARY OF QUANTITIES
3	SITE PLAN AND GENERAL NOTES
4	CONSTRUCTION AND SAFETY NOTES AND DETAILS
5	CONSTRUCTION STAGING PLAN - STAGE 1 AND 2
6	CONSTRUCTION STAGING PLAN - STAGE 3 AND 4
7	ALIGNMENT AND CURVE DATA
8	TYPICAL PAVEMENT SECTIONS
9	STORM WATER POLLUTION PREVENTION PLAN
10	STORM WATER POLLUTION PREVENTION DETAILS
11	REMOVAL PLAN
12	PLAN AND PROFILE - ALIGNMENT 200
13	PLAN AND PROFILE - ALIGNMENT 200
14	PLAN AND PROFILE - ALIGNMENT 300
15	PLAN AND PROFILE - ALIGNMENT 300
16	PLAN AND PROFILE - ALIGNMENT 400
17	PLAN AND PROFILE - ALIGNMENT 500
18	STAKING PLAN - ALIGNMENT 200/300
19	STAKING PLAN - ALIGNMENT 200/300
20	STAKING PLAN - ALIGNMENT 400/500
21	CROSS SECTIONS - ALIGNMENT 200
22	CROSS SECTIONS - ALIGNMENT 200
23	CROSS SECTIONS - ALIGNMENT 200
24	CROSS SECTIONS - ALIGNMENT 300
25	CROSS SECTIONS - ALIGNMENT 300
26	CROSS SECTIONS - ALIGNMENT 300
27	CROSS SECTIONS - ALIGNMENT 400
28	CROSS SECTIONS - ALIGNMENT 500
29	STORM SEWER AND UNDERDRAIN SCHEDULES
30	UNDERDRAIN DETAILS
31	STORM SEWER DETAILS
32	ELECTRICAL DETAILS
33	MARKING PLAN
34	MARKING PLAN
35	LANDSCAPING PLAN
36	BORING LOCATION MAP
37	BORING LOGS - B-1 THRU B-6
38	BORING LOGS - B-7 THRU B-8

NOTICE TO CONTRACTORS AND BIDDERS
 THESE CONSTRUCTION PLANS RELY UPON THE SPECIAL PROVISIONS AND THE SPECIFICATIONS TO PROVIDE FOR A COMPLETE DESCRIPTION OF THE WORK AND CONSTRUCTION REQUIREMENTS. THE PLANS SHALL ONLY BE USED IN COMBINATION WITH ALL CONTRACT DOCUMENTS.

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	AS BID	RECORD PAID
AR110501	1-WAY CONC. ENCASED DUCT	LINEAR FOOT	63.0	
AR150510	ENGINEER'S FIELD OFFICE	LUMP SUM	1.0	
AR152410	UNCLASSIFIED EXCAVATION	CUBIC YARD	6,520.0	
AR156510	SILT FENCE	LINEAR FOOT	24.0	
AR156513	SEPARATION FABRIC	SQUARE YARD	6,538.0	
AR156520	INLET PROTECTION	EACH	5.0	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	445.0	
AR209608	CRUSHED AGG. BASE COURSE - 8"	SQUARE YARD	6,538.0	
AR209610	CRUSHED AGG. BASE COURSE - 10"	SQUARE YARD	2,113.0	
AR401613	BIT. SURF. CSE. - METHOD 1, SUPERPAVE	TON	1,375.0	
AR401650	BITUMINOUS PAVEMENT MILLING	SQUARE YARD	4,081.0	
AR401660	SAW & SEAL BIT. JOINTS	LINEAR FOOT	2,115.0	
AR401665	BITUMINOUS PAVEMENT SAWING	LINEAR FOOT	4,440.0	
AR401900	REMOVE BITUMINOUS PAVEMENT	SQUARE YARD	12,596.0	
AR403613	BIT. BASE CSE. - METHOD 1, SUPERPAVE	TON	1,750.0	
AR403620	BITUMINOUS BASE COURSE, LEVELING	TON	664.0	
AR501605	5" PCC SIDEWALK	SQUARE FOOT	3,581.0	
AR501900	REMOVE PCC PAVEMENT	SQUARE YARD	454.0	
AR602510	BITUMINOUS PRIME COAT	GALLON	2,602.0	
AR603510	BITUMINOUS TACK COAT	GALLON	3,148.0	
AR620520	PAVEMENT MARKING - WATERBORNE	SQUARE FOOT	4,600.0	
AR620525	PAVEMENT MARKING - BLACK BORDER	SQUARE FOOT	205.0	
AR701518	18" RCP, CLASS IV	LINEAR FOOT	42.0	
AR705506	6" PERFORATED UNDERDRAIN	LINEAR FOOT	1,781.0	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	2.0	
AR705640	UNDERDRAIN CLEANOUT	EACH	4.0	
AR751927	REPLACE FRAME & GRATE	EACH	1.0	
AR751943	ADJUST MANHOLE	EACH	4.0	
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH	1.0	
AR752518	GRATING FOR CONC. FES 18"	EACH	1.0	
AR800928	GRAVULAR DRAINAGE SUBBASE - 4"	SQUARE YARD	6,538.0	
AR800967	CRACK CONTROL MATERIAL	SQUARE YARD	6,156.0	
AR901510	SEEDING	ACRE	2.4	
AR905510	TOPSOILING (FROM ON SITE)	CUBIC YARD	1,010.0	
AR908510	MULCHING	ACRE	2.4	

PAYMENT WILL BE MADE UNDER THE ITEM NUMBERS, DESCRIPTIONS AND UNITS NOTED IN THE ABOVE TABLE IN ACCORDANCE WITH THE BASIS OF PAYMENT FOR EACH RESPECTIVE WORK ITEM NOTED IN THE SPECIAL PROVISIONS, COMPLETED AND ACCEPTED BY THE ENGINEER.

SHEET INDEX AND SUMMARY OF QUANTITIES

REHABILITATE NORTH HANGAR PAVEMENTS,
 IDA No. LOT-4020 AIP No. 3-17-0140-B48



Hanson Professional Services Inc.
 815 Commerce Drive Suite 200
 Oak Brook, Illinois 60523

Hanson No. 10A0072
 Filename 02-INDEX AND SOQ.DWG
 Scale N/A
 Date APRIL 22, 2011

LAYOUT	KMS	02/25/11
DRAWN	KMS	02/25/11
REVIEWED	RMH	4/22/11

Chicago-Romeoville Airport
JOLIET REGIONAL PORT DISTRICT
 1 George Michas Drive
 Romeoville, Illinois 60446
 Telephone: 815.838.9497
 Fax: 815.838.9524

DATE	REVISION

LE042