



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 6, 2022

SUBJECT: FAP Route 68 (IL 23)
Project COVD-DCKB(695)
Section (3)RS-5
LaSalle County
Contract No. 66616
Item No. 20, June 17, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Revised page 60 of the Special Provisions.
3. Revised sheet 33 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

STEEL COST ADJUSTMENT (BDE)45
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)47
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....48
SURFACE TESTING OF PAVEMENTS – IRI (BDE).....48
TRAINING SPECIAL PROVISIONS (BDE)53
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION...56
WEEKLY DBE TRUCKING REPORTS (BDE).....58
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....58
WORKING DAYS (BDE)60
RUMBLE STRIP60

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **55** working days.

RUMBLE STRIP

(Revised May 18, 2022)

This item shall be constructed as shown on the plans and in accordance with the applicable portions of Section 642 of the Standard Specifications for Road and Bridge Construction. The rumble strips shall be constructed in accordance to Highway Standard 642006 except that the rumble strips are to be constructed on the edgeline of the pavement instead of the shoulder area.

The locations for the rumble strips will be consistent with the plans and details with starts and stops as located by the Engineer.

After the rumble strips are installed, the pavement surface shall be swept clean to the satisfaction of the Engineer prior to the placement of new pavement marking. The new pavement markings shall be located over the center of the new rumble strips. The new pavement markings shall be placed within (3) days of the installation of the rumble strips.

This work shall be measured along the rumble strips parallel to centerline and paid for at the contract unit price per Foot for RUMBLE STRIP.

Measurement will include both the cut and uncut sections of the rumble strips with exceptions for gaps longer than 12 feet at locations omitted as outlined in Article 642.03 of the Standard Specifications. Gaps longer than 12 feet will not be measured for payment.

Revised June 6, 2022