	FIELD TILE REPLACEMENT														
	то	STA		SS	:NCH KFILL	MISC	CL B	SAW	DWL	PIPE	CONC	AGG	REMARKS		
				PROTECTED		CONC	PATCH	CUTS	BARS	DRAINS	HWL	SURF			
STA				CL A 8"	₩0	**	TY II		1.5"	10"	FOR P	CSE			
				*	TF BA		13"*				DRAIN	TY B			
							FT	FOOT	CU YD	CU YD	SQ YD	FOOT	EACH	FOOT	EACH
	COVD-RURAL														
222+39	TO	222+72	110	110	23	0.2	13	60	20				REPLACE EX 8" TILE AND TILE UNDER EX		
													DITCH AND UNDER ROADWAY		
222+60	TO	248+55	2,595							2,595	1		EAST EX. 10" PIPE DRAIN REPLACEMENT.		
238+80	238+80 LT			6							3				
TOTAL COVD RURAL			AL	110	29	0.2	13	60	20	2,595	1	3			

*MATERIAL SHALL BE REINFORCED CONCRETE

**SEE FIELD TILE DETAILS FOR CONSTRUCTION UNDER DITCHES

CONNECTION TO JUNCTION VAULT SHALL BE INCLUDED IN THE COST OF THE PIPE DRAINS AND STORM SEWER (PROTECTED)

PIPE DRAINS - MATERIAL FOR PIPE DRAINS SHALL BE PVC. CONNECTIONS TO INSPECTION WELLS/JUNCTIONS SHALL BE CONSIDERED AS INCLUDED IN THE COST OF THE PAY ITEM.

 $\frac{1}{2}$

DELINEATOR SCHEDULE							
LOCATION	DELINE	DELINEATORS*					
	INSTALL **	REMOVE ***					
STA	EACH	EACH					
STP-RURAL							
12+60 - 277+68	3	3					
•							
STP-URBAN							
277+68 - 345+65	1	1					

*SINGLE FACE REFLECTOR POSTS TO BE USED.

CURB REFLECTOR						
SCHEDULE						
	INSTALLATION					
LOCATION	*					
	EACH					
COVD-RURAL						
TWAIT RD (118+78 LT)	NW ISLAND	8				
TOTAL COVD-RUP	8					
COVD-URBAN						
STEVENSON RD (344+03 RT)	SW ISLAND	12				
TOTAL STP-URBA	12					
GRAND TOTA	20					

*PAY ITEM SHALL INCLUDE THE REMOVAL OF EXISTING REFLECTORS AT ISLANDS (IF PRESENT)

SEE HWY STND 782001 FOR SPACING

FLEXIBLE DELINEATOR							
SCHEDULE							
	INSTALLATION *						
LOCATION							
	EACH						
COVD-RURAL							
TWAIT RD (118+78 LT)	NW ISLAND	1					
TOTAL COVD-RUF	1						
CO	VD-URBAN						
STEVENSON RD (344+03 RT)	SW ISLAND	1					
CL MEDIAN (344+75 CL)	CL MEDIAN	1					
TOTAL STP-URBA	2						
GRAND TOTA	3						

*PAY ITEM SHALL INCLUDE THE REMOVAL OF EXISTING DELINEATORS AT ISLANDS (IF PRESENT)

SEE HWY STND HWY SND 701901 AND SPECIAL PROVISIONS FOR DETAILS

ADJUSTMENT SCHEDULE*								
	FRAMES	& LIDS	WATER VALVE					
LOCATION	то в	E ADJ	TO BE ADJ					
	SI	PL	SPL					
	EA	CH	EACH					
COVD-URBAN								
IL 23	NB	SB	NB	SB				
		-		-				
PCC JOINT TO STEVENSON RD	2	1						
STEVENSON RD TO DAYTON RD	1		1					
TOTAL	4	4		1				
	•	•						

* RESIDENT TO VERIFY LOCATIONS ON SITE. SOME ITEMS LOCATED ON SIDEROADS.

 USER NAME
 = ZAGARIK
 DESIGNED
 REVISED

 DRAWN
 REVISED

 PLOT SCALE
 = 100.0000 ' / in.
 CHECKED
 REVISED

 PLOT DATE
 = 3/18/2022
 DATE
 REVISED

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

^{**}QUANTITIES ONLY FOR HAZARDS WITHIN 15-FT OF EDGE LINE INVOLVING X-ROAD CULVERTS

^{***}REMOVAL OF EXISTING POST SHALL NOT DAMAGE ADJACENT DRAINAGE STRUCTURES (IF PRESENT)