

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				CONTRACT MAINTENANCE 100% STATE	RURAL
				ROADWAY	
				0006	
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	352		352
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	35		35
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	187		187
44213000	PATCHING REINFORCEMENT	SQ YD	574		574
44213200	SAW CUTS	FOOT	1772		1772
44213204	TIE BARS 3/4"	EACH	1254		1254
67100100	MOBILIZATION	L SUM	1		1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4		4
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	8		8
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28		28
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	430		430
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	110		110
X1700018	CLASS A PATCH - EXPANSION JOINT	FOOT	204		204

*= SPECIALTY ITEM

FILE NAME =	USER NAME = woodshankr	DESIGNED - RW	REVISED -
pw:\idot-pw.bentley.com-PWIDOT\Documents\IDOT Office\District 3\Projects\0366M60\CAD\Drawings\0366M60 - PLANS.dwg		DRAWN - RW	REVISED -
Default	PLOT SCALE = 100.0000 /in.	CHECKED - YP	REVISED -
	PLOT DATE = 3/22/2022	DATE - 2/22/2022	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET 1	OF 2	SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10,27-38&1)PP	FORD	9	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 66M60	

**PATCHING SCHEDULE
NORTHBOUND LANES**

LOCATION	PASSING LANE								DRIVING LANE								
	PATCH LENGTH	CLASS A PATCHING			CLASS A PATCH - EXPANSION JOINT	PATCH REINFORCEMENT	SAW CUTS	TIE BARS	PATCH LENGTH	CLASS A PATCHING			CLASS A PATCH - EXPANSION JOINT	PATCH REINFORCEMENT	SAW CUTS	TIE BARS	
		TYPE II 11"	TYPE III 11"	TYPE IV 11"						TYPE II 11"	TYPE III 11"	TYPE IV 11"					
MILE MARKER	FEET	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	FOOT	EACH	FEET	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	FOOT	EACH	
257.70									12		16			16	48	44	
258.20									8	11				11	40	44	
258.40									6	8				8	36	44	
258.50									10	13				13	44	44	
258.55	6	8				8		36	44								
258.55									10	13				13	44	44	
258.70	10	13			12	13		44	22	10	13		12	13	44	22	
258.70	6	8			12	8		36	22								
259.30									8	11				11	40	44	
260.40									6	8				8	36	44	
260.50	10	13			12	13		44	22	10	13		12	13	44	22	
260.90									6	8				8	36	44	
261.00									14		19			19	52	44	
261.75	10	13			12	13		44	22	10	13		12	13	44	22	
261.75	8	11			12	11		40	22	8	11		12	11	40	22	
261.80									6	8				8	36	44	
261.90									6	8				8	36	44	
262.45									10	13				13	44	44	
262.50									6	8				8	36	44	
262.40									140			187		187	304	90	
SUBTOTALS	50	66			60	66		244	154	286	159	35	187	48	381	1004	660
TOTALS	336	225	35	187	108	447		1248	814								

60
108
↑

**PATCHING SCHEDULE
SOUTHBOUND LANES**

LOCATION	PASSING LANE								DRIVING LANE							
	PATCH LENGTH	CLASS A PATCHING			CLASS A PATCH - EXPANSION JOINT	PATCH REINF	SAW CUTS	TIE BARS	PATCH LENGTH	CLASS A PATCHING			CLASS A PATCH - EXPANSION JOINT	PATCH REINF	SAW CUTS	TIE BARS
		TYPE II 11"	TYPE III 11"	TYPE IV 11"						TYPE II 11"	TYPE III 11"	TYPE IV 11"				
MILE MARKER	FEET	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	FOOT	EACH	FEET	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	FOOT	EACH
263.10	6	8			12	8		36	22	6	8		12	8	36	22
262.90										6	8			8	36	44
262.45	6	8						8	36	44						
262.05										6	8			8	36	44
261.60										8	11			11	40	44
261.55	6	8			12	8		36	22	6	8		12	8	36	22
260.55	6	8			12	8		36	22	6	8		12	8	36	22
258.75										8	11			11	40	44
258.75	8	11			12	11		40	22	8	11		12	11	40	22
258.70	8	11				11		40	44							
SUBTOTALS	40	54			48	54		224	176	54	73		48	73	300	264
TOTALS	94	127			96	127		524	440							