

CONSTR. CODE  
 I-74 - CHAMPAIGN COUNTY  
 90% FED. 10% STATE - URBAN  
 BRIDGE  
 0059  
 S.N. 010-0025 & 0026

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	950	950
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
* 78008330	POLYUREA PAVEMENT MARKING TYPE 11 - LINE 6"	FOOT	3320	3320
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
* 78011035	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	2377	2377
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8
* 78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	81	81
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	5818	5818
X0325748	ACRYLIC COATING	SQ YD	95	95
X0325749	FIBER WRAP	SQ FT	852	852
X0326208	ALTERNATE ROUTE SIGNING	L SUM	1	1
X0326331	CLEANING AND PAINTING BEARINGS	EACH	32	32
* X0327640	REAL-TIME TRAFFIC CONTROL CENTRAL BASE UNIT	CAL MO	7	7
* X0328005	REAL-TIME TRAFFIC MONITORING SENSOR UNIT	CAL MO	112	112
* X0328006	REAL-TIME TRAFFIC CONTROL WARNING SIGN	CAL MO	56	56



\*DENOTES SPECIALTY ITEM

MODEL: P:\proj3  
 FILE NAME: I:\chris\2018\10119011\FB\_103-025\_DS\_Various\_Phase\_1\Drawings\CAD\Sheet\05708778-11-500.dgn

**Prairie Engineers, P.C.**  
 404 N. Main Street  
 Columbia, IL 62238  
 (217) 604-4483  
 www.prairieengineers.com  
 professional design firm no. 104-005965  
 © Copyright Prairie Engineers of Illinois, P.C. 2022

USER NAME = Bbrennan	DESIGNED -	REVISED -
PLOT SCALE = 40.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 3/24/2022	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SALINE BRANCH 1 MILE EAST OF U.S. 45 & OVER I-74 EAST OF URBANA**  
**SUMMARY OF QUANTITIES**  
 SCALE: SHEET 3 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10-6B)BR-1	CHAMPAIGN	52	5
			CONTRACT NO. 70B78	
ILLINOIS FED. AID PROJECT				

**PRE-STAGE OVERVIEW**

**I-74:**

CLOSE OUTSIDE LANE IN EACH DIRECTION AT SN 010-0025 AND SN 010-0026 TO MILL AND RESURFACE THE OUTSIDE SHOULDERS TO THE LIMITS SHOWN IN THE REMOVAL PLANS. ONE SHOULDER SHALL BE COMPLETELY PAVED BEFORE MILLING THE OTHER SHOULDER. THE SHOULDER SURFACE COURSE SHALL BE PLACED THE SAME DAY THE STRETCH OF SHOULDER IS MILLED.

**STAGE I OVERVIEW**

**I-74:**

CLOSE THE I-74 INSIDE LANES TO TRAFFIC AT SN 010-0025 AND SN 010-0026 FOR THE REMAINDER OF STAGE I. MAINTAIN ONE LANE OF TRAFFIC PER DIRECTION. INSTALL THE TEMPORARY CONCRETE BARRIER AT SN 010-0025 AND SN 010-0026. PERFORM BRIDGE WORK AND APPROACH PAVEMENT WORK.

**STAGE II OVERVIEW**

**I-74:**

CLOSE THE I-74 OUTSIDE LANES TO TRAFFIC FOR THE REMAINDER OF STAGE II. MAINTAIN ONE LANE OF TRAFFIC PER DIRECTION. RELOCATE AND INSTALL THE TEMPORARY CONCRETE BARRIER AT SN 010-0025 AND SN 010-0026. PERFORM BRIDGE WORK AND APPROACH PAVEMENT WORK.

**STAGE III OVERVIEW**

**I-74:**

OPEN ALL LANES ON I-74 TO TRAFFIC. PERFORM CLEANUP OPERATIONS AS DIRECTED BY THE RESIDENT ENGINEER.

**NOTES:**

1. THIS IS A SUGGESTED STAGING PLAN. THE CONTRACTOR SHALL SUBMIT ANY PROPOSED CHANGES TO THIS PLAN TO THE ENGINEER, IN WRITING, FOR CONSIDERATION. NO CHANGES SHALL BE MADE TO THE PROPOSED STAGING WITHOUT WRITTEN APPROVAL FROM THE ENGINEER. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY ADDITIONAL COSTS ASSOCIATED WITH CHANGES TO STAGING REQUESTED BY THE CONTRACTOR.
2. ALL WORK REQUIRING LANE CLOSURES ON I-74 WITHOUT A BARRIER SHALL BE RESTRICTED TO NIGHTTIME LANE CLOSURES. THIS INCLUDES, BUT IS NOT LIMITED TO, SETTING TEMPORARY CONCRETE BARRIER, RELOCATING TEMPORARY CONCRETE BARRIER, SHOULDER WORK, STRIPING AND GUARDRAIL WORK. THIS WORK SHALL BE LIMITED TO SUNDAY, MONDAY, TUESDAY, WEDNESDAY OR THURSDAY BETWEEN 10:00 P.M. TO 6:00 A.M. ALL DEVICES AND THE FIRST TWO WARNING SIGNS SHALL HAVE LIGHTS AS SPECIFIED IN STANDARD 701401.
3. TEMPORARY CONCRETE BARRIER SHALL BE SECURED TO THE PAVEMENT ACCORDING TO SAFETY ENGINEERING POLICY MEMORANDUM 4-21 AND THE STANDARD SPECIFICATIONS.
4. ALL TEMPORARY AND PERMANENT SIGNAGE SHALL BE POSITIONED IN ACCORDANCE WITH THE GUIDELINES IN THE MOST RECENT EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL AND DEVICES UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

**1** ~~5. THE LANE CLOSURES AND TEMPORARY CONCRETE BARRIER FOR STAGE I TRAFFIC CONTROL SHALL NOT BE INSTALLED ON I-74 BEFORE \_\_\_\_\_, 2023, UNLESS OTHERWISE APPROVED BY THE ENGINEER.~~

MODEL: Staging Overview  
FILE NAME: 193-025.D5\_Various\_Phase\_HitWork\_Order\_2\Drawings\CADD\_Sheets\0570B78-sth-staging-GenNotes - Addendum1.dgn

**Prairie Engineers, P.C.**  
404 N. Main Street  
Columbia, IL 62238  
(217) 605-0403  
www.prairieengineers.com  
Professional Design Firm No. 154-005965  
Copyright © Prairie Engineers, P.C. 2022

USER NAME = rheinke	DESIGNED -	REVISED -  RNH - 6/7/2022
	DRAWN -	REVISED -
PLOT SCALE = 2,0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 6/7/2022	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SALINE BRANCH 1 MILE EAST OF U.S. 45 &amp; OVER I-74 EAST OF URBANA</b>			
<b>STAGING OVERVIEW</b>			
SCALE:	SHEET 1	OF 1 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(10-6B)BR-1	CHAMPAIGN	52	14
			CONTRACT NO. 70B78	
		ILLINOIS	FED. AID PROJECT	