LANDSCAPE INSTALLATION GENERAL NOTES:

- 1. VERIFICATION OF DIMENSIONS AND GRADES, BOTH EXISTING AND PROPOSED, SHALL BE THE CONTRACTOR'S RESPONSIBILITY PRIOR TO COMMENCEMENT OF WORK. THE CONTRACTOR SHALL NOTIFY THE DISTRICT ROADSIDE MANAGEMENT SPECIALIST, 618-346-3286 OF ANY
- 2. ALL SURFACE DRAINAGE SHALL BE DIRECTED AWAY FROM BUILDINGS. SURFACE DRAINAGE SHALL BE DIRECTED TO EXISTING DRAINAGE STRUCTURES DESIGNATED FOR THE COLLECTION
- 3. CONTRACTOR SHALL REPAIR IN KIND ANY AREAS DAMAGED AS A RESULT OF LANDSCAPE OPERATIONS AT NO ADDITIONAL COST TO THE CONTRACT.
- 4. ALL SODDING, SALT TOLERANT AREAS SHALL HAVE FERTILIZER APPLIED AT A 1:1:1 RATIO AS FOLLOWS: NITROGEN FERTILIZER NUTRIENT - 60 LBS/ACRE PHOSPHORUS FERTILIZER NUTRIENT - 60 LBS/ACRE POTASSIUM FERTILIZER NUTRIENT - 60 LBS/ACRE
- 5. ALL SEEDING, CLASS 3A AREAS SHALL HAVE FERTILIZER APPLIED AT A 1:1:1 RATIO AS FOLLOWS: NITROGEN FERTILIZER NUTRIENT - 90 LBS/ACRE PHOSPHORUS FERTILIZER NUTRIENT - 90 LBS/ACRE POTASSIUM FERTILIZER NUTRIENT - 90 LBS/ACRE
- 6. ALL SEEDING (SPECIAL) AREAS SHALL HAVE FERTILIZER APPLIED AS FOLLOWS: NITROGEN FERTILIZER NUTRIENT - 50 LBS/ACRE PHOSPHORUS FERTILIZER NUTRIENT - 100 LBS/ACRE POTASSIUM FERTILIZER NUTRIENT - 100 LBS/ACRE AGRICULTURAL GROUND LIMESTONE - 2 TONS/ACRE
- 7. ALL SEEDING, CLASS 4A AND SEEDING CLASS 4B AREAS SHALL NOT REQUIRE FERTILIZER NUTRIENTS.
- 8. SUPPLEMENTAL WATERING SHALL BE APPLIED AT THE DIRECTION OF THE ENGINEER AT A RATE OF 3 GAL/SQ YD, OR AT THE RATE DIRECTED BY THE ENGINEER.
- 9. THE SEEDING AND SODDING SHOWN IN THESE PLANS SHALL SUPERCEDE THE PERMANENT CONFLICTING SEEDING SHOWN IN CONTRACT 76C55 IN THE VICINITY OF THE DETENTION
- 10. THE CONTRACTOR SHALL COORDINATE THE LANDSCAPE PLANTING SCHEDULE WITH CONTRACT 76C52 (MAINLINE I-55/70 AND I-64 ROADWAY CONTRACT) TO ENSURE THAT THE EMBANKMENT GRADES ARE FINALIZED AT THE LIMITS OF CONTRACT 76C52 AND THAT THE PROPOSED LANDSCAPING IMPROVEMENTS CAN BE CONSTRUCTED WITHOUT
- 11. SELECTIVE MOWING STAKES SHALL BE INSTALLED ALONG THE BORDER BETWEEN THE SEEDING (SPECIAL) AND ALL OTHER TYPES OF SEEDING. THE SELECTIVE MOWING STAKES SHALL BE INSTALLED EVERY 200' FOR LONG & FAIRLY STRAIGHT RUNS, AND EVERY 25' FOR TIGHT CURVES.
- 12. CONTRACTOR SHALL CONTACT DAVID WALKER IDOT ELECTRICAL SERVICES SUPERVISOR AT 618.346.3274 PRIOR TO CONSTRUCTION TO SCHEDULE A WALK THROUGH OF THE SITE TO IDENTIFY ALL DEEP WELLS AND ITS EQUIPMENT.

5 8
3 4 6
EXCHANGE LS
BAUGH AVE.
ST. CLAIR AVE.
Ψ

SHEET LAYOUT

FILEL\$

USER NAME = \$USER\$ DESIGNED JM REVISED DRAWN REVISED CHECKED - ACL PLOT SCALE = \$SCALE\$ REVISED PLOT DATE = \$DATE\$ DATE 02/10/12

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

PROPOSED LANDSCAPING PLANS - GENERAL NOTES SCALE: N/A SHEET NO. 1 OF 9 SHEETS STA.

SECTION ST. CLAIR 9153 82-1LS-1 37 CONTRACT NO. 76F40 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT