REES	CODE	ALLY EQUALS FIRST THREE LETTERS OF THE BOTANICAL AND/OR THE COMMON NAME.  ITEM	QTY	EROSION CONTROL	ITEM	
·	BET RIV	TREE, BETULA NIGRA (RIVER BIRCH) 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	6	$\bigoplus$	INLET FILTERS	
0	SAL BAB	TREE, SALIX BABYLONICA (BABYLON WEEPING WILLOW), 2" CALIPER, BALLED AND BURLAPPED	5	<b>₩</b> IP&P	INLET AND PIPE PROTECTION	
	GYM KEN	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED	6	<del></del>	PERIMETER EROSION BARRIER	
·	MET GLY	TREE, METASEQUOIA GLYPTOSTROBOIDES (DAWN REDWOOD) 2" CALIPER, BALLED AND BURLAPPED	8			
	PLA OCC	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), 3" CALIPER, BALLED AND BURLAPPED	3			
	QUE ALB	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	3			
$\overline{\cdot}$	QUE BIC	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK) 3" CALIPER, BALLED AND BURLAPPED	2			
+	QUE MAC	TREE, QUERCUS MACROCARPA (BURR OAK) 3" CALIPER, BALLED AND BURLAPPED	3			
+	QUE PAL	TREE, QUERCUS PALUSTRIS (PIN OAK) 3" CALIPER, BALLED AND BURLAPPED	3			
	QUE PHE	TREE, QUERCUS PHELLOS (WILLOW OAK) 2" CALIPER, BALLED AND BURLAPPED	2			
	ROB BEN	TREE, ROBINIA PSEUDOACACIA BENJAMIN (BENJAMIN BLACK LOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	10			
ING TREES	CODE	ITEM	QTY			
$\dot{\odot}$	AME LAE	TREE, AMELANCHIER LAEVIS (ALLEGHENY SERVICEBERRY), 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	7			
	CRA COC	TREE, CRATAEGUS CRUSGALLI (COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	3			
RUBS	CODE	ITEM	QTY	SEEDING & SODDING	ITEM	QTY
· Octobro	ILE DEC	SHRUB, ILEX DECIDUA (POSSUMHAW) CONTAINER GROWN, 5-GALLON	15	0 0 0	SEEDING (SPECIAL) NITROGEN FERTILIZER NUTRIENTS - 50 LBS/ACRE PHOSPHORUS & POTASSIUM FERTILIZER NUTRIENTS - 100 LBS/ACRE EACH AGRICULTURAL GROUND LIMESTONE - 2 TON/ACRE	1.25 ACRE 63 LBS 125 LBS EACH 3 TONS
9	COR STO	SHRUB, CORNUS STOLONIFERA (RED OSIER DOGWOOD), CONTAINER GROWN, 3-GALLON	44		EROSION CONTROL BLANKET SEEDING, CLASS 3A	6,050 SQ YD
•	LIN BEN	SHRUB, LINDERA BENZOIN (SPICEBUSH), CONTAINER GROWN, 3-GALLON	37	Z	SEEDING, CLASS 3 NITROGEN, PHOSPHORUS & POTASSIUM FERTILIZER NUTRIENTS - 90 LBS/ACRE EACH EROSION CONTROL BLANKET	1.25 ACRE 113 LBS EACH 6,050 SQ YD
1	RHU GRO	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), CONTAINER GROWN, 3-GALLON	255		SEEDING, CLASS 4A	0.75 ACRE
)	RHU GLA	SHRUB, RHUS GLABRA (SMOOTH SUMAC), 3' HEIGHT, CONTAINER	19		EROSION CONTROL BLANKET	3,630 SQ YD
	RHU TYP	SHRUB, RHUS TYPHINA (STAGHORN SUMAC). 3' HEIGHT, CONTAINER	45		SEEDING, CLASS 4B EROSION CONTROL BLANKET	1.50 ACRE 7,260 SQ YD
D	SAM ELD	SHRUB, SAMBUCUS CANADENSIS (AMERICAN ELDER), 3' HEIGHT, BALLED AND BURLAPPED	19			.,200 GW 10
B	VIB LUS	SHRUB, VIBURNUM DENTATUM (ARROWWOOD VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED	33	W	SODDING, SALT TOLERANT TOPSOIL FURNISH AND PLACE, 4" NITROGEN, PHOSPHORUS & POTASSIUM FERTILIZER NUTRIENTS - 60 LBS/ACRE EACH	226 SQ YD 226 SQ YD 3 LBS EACH
Ć	VIB LEN	SHRUB, VIBURNUM LENTAGO (NANNYBERRY VIBURNUM), 3' HEIGHT, BALLED AND BURLAPPED	10			C EDO EAGIT
COVERS	CODE	BOTANICAL NAME / COMMON NAME CONT	QTY			
		HEMEROCALLIS HYBRID 'STELLA DE ORO' / STELLA DE ORO DAYLILLY 1 GALLON @ 12" or AS PERRENIAL PLANTS, ORNAMENTAL TYPE, GALLON POT)	c 665			

TENG BIGINESES/ARCHITECTS/PLANNERS PLOT DATE = \$SCALE\$

DRAWN - JB

 CHECKED
 ACL
 REVISED

 DATE
 02/10/12
 REVISED

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PROPOSED LANDSCAPING PLANS – PLANTING DETAILS, LEGEND, ABBREVIATIONS, AND SCHEDULE

SCALE: N/A

SHEET NO. 8 OF 9 SHEETS STA.