

90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE							HIGHWAY LIGHTING	NOISE WALL	
				ROADWAY	BRIDGE	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL	RETAINING WALL			
				0004	0008	0040	0040	0040	0040	0040			
				URBAN	016-1705	016-1720	016-Z024	016-1722	016-1723	016-1809	0021	0040	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SO YD	412										
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	250										
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	234										
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	256										
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	143										
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	755										
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SO YD	6014										
42001200	PAVEMENT FABRIC	SO YD	412										
42001300	PROTECTIVE COAT	SO YD	17090										
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	425										
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	35										
44000100	PAVEMENT REMOVAL	SO YD	17598										
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	1743										
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1382										

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM



D:\60428\60428.dgn	DESIGNED - NSA	REVISED -
USER NAME: alizadeh	DRAWN - NSA	REVISED -
PLOT SCALE: 1/8" = 1'-0"	CHECKED - AFC	REVISED -
PLOT DATE: 4/28/14	DATE - 04/28/14	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET 3 OF 24 SHEETS	STA. TO STA.	F.A.I. RTE. 90/94/290	SECTION 2013-010R	COUNTY COOK	TOTAL SHEETS 747	SHEET NO. 7
			ILLINOIS FED. AID PROJECT		CONTRACT NO. 60W28		

FILE PATH: C:\Users\alideh\Documents\Projects\60428\Sheet1.DWG