CODE NO.	ITEM	UNIT	90% FED. 10% STATE URBAN TOTAL QUANTITY	CONSTRUCTION CODE ROADWAY 0004 URBAN	BRIDGE 0008 016-1705	RETAINING WALL 0040 016-1720	RETAINING WALL 0040 016-Z024	RETAINING WALL 0040 016-1722	RETAINING WALL 0040 016-1723	RETAINING WALL 0040 016-1809	HIGHWAY LIGHTING 0021 URBAN	NOISE WALL 0040 NONE
Z0004552	APPROACH SLAB REMOVAL	SQ YD	262	262								
* Z0007118	UNTREATED TIMBER LAGGING	SQ FT	1000						1000			
* * Z0010614	CLEANING EXISTING MANHOLE OR HANDHOLE	EACH	2								2	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	25				25					
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	11				11					
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	400	400								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1								
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	20		20							
Z0018800	DRAINAGE SYSTEM	L SUM	1		1							
Z0022800	FENCE REMOVAL	FOOT	2181	580			1601					
Z0026404	FURNISHING SOLDIER PILES (W SECTION)	FOOT	2016						2016			
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	1042	1042								
* Z0033020	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	5								5	
* Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	22								22	

* DENOTES SPECIALTY ITEM * * DENOTES NON-PARTICIPATING ITEM (100% STATE)

FILE PATH = C:\Users\alizadehn\Desktop\Prints\Final Sheets\0168W28-sht-500.dgn

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5216
PHONE: (312) 373-7700 FAX: (312) 373-6800

0168W28-sht-500.dgn	DESIGNED - NSA	REVISED -	
USER NAME = alizadehn	DRAWN - NSA	REVISED -	
PLOT SCALE = 2.0000 ' / in.	CHECKED - AFC	REVISED -	
PLOT DATE = 4/28/2014	DATE - 04/28/14	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 16 OF 24 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-010R	COOK	747	20

CONTRACT NO. 60W28

ILLINOIS FED. AID PROJECT