LETTING ITEM NO. 05A JULY 29, 2016 LETTING

FR040 TOTAL SHEETS = 29

CITY OF FREEPORT FREEPORT, ILLINOIS

CONSTRUCTION PLANS FOR FREEPORT-ALBERTUS AIRPORT


REHABILITATE RUNWAY 6/24




J.U.L.I.E.
JOINT UTILITY LOCATING
INFORMATION FOR EXCAVATORS
www.illinois1call.com

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS, OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER SHALL ALSO BE IMMEDIATELY NOTIFIED. ANY SUCH UTILITY OR SERVICES SHALL BE RESTORED TO SERVICE AT ONCE AND PAID FOR SY THE CONTRACTOR THE CONTRACT.


CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811.






ILLINOIS PROJECT: FEP-4296

JUNE 3, 2016



LOCATION MAP



SITE PLAN



DESIGN INFORMATION

DESIGN AIRCRAFT APPROACH CATEGORY: B DESIGN AIRCRAFT GROUP: II

TOWNSHIP: 26 NORTH RANGE: 8 EAST SILVER CREEK TOWNSHIP

STEPHENSON COUNTY

(SECTION: 21)

INDEX TO SHEETS

- 1 COVER SHEET
- 2 INDEX TO SHEETS AND SUMMARY OF QUANTITIES
- SITE PLAN AND PROJECT CONTROL PLAN
- SEQUENCE OF CONSTRUCTION
- 5 SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS - SHEET 1
- SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS SHEET 2
- STORM WATER POLLUTION PREVENTION PLAN 7
- STORM WATER POLLUTION PREVENTION PLAN NOTES AND DETAILS SHEET 1
- STORM WATER POLLUTION PREVENTION PLAN NOTES AND DETAILS SHEET 2
- EXISTING CONDITIONS / PROPOSED REMOVALS SHEET 1
- 11 EXISTING CONDITIONS / PROPOSED REMOVALS SHEET 2
- EXISTING CONDITIONS / PROPOSED REMOVALS SHEET 3
- TYPICAL SECTIONS 13
- PLAN AND PROFILE RUNWAY 6/24 SHEET 1 14
- PLAN AND PROFILE RUNWAY 6/24 SHEET 2
- PLAN AND PROFILE RUNWAY 6/24 SHEET 3
- PLAN AND PROFILE RUNWAY 6/24 SHEET 4 17
- PLAN AND PROFILE RUNWAY 6/24 SHEET 5
- 19 ELECTRICAL AND PAVEMENT MARKING PLAN - SHEET 1
- ELECTRICAL AND PAVEMENT MARKING PLAN SHEET 2
- ELECTRICAL AND PAVEMENT MARKING PLAN SHEET 3
- 22 ELECTRICAL DETAILS - SHEET 1
- 23 ELECTRICAL DETAILS SHEET 2
- **ELECTRICAL DETAILS SHEET 3**
- 25 PAVEMENT MARKING DETAILS
- 26 DRAINAGE DETAILS
- RUNWAY GROOVING PLAN AND DETAILS
- BITUMINOUS OVERLAY DEPTH TABLE SHEET 1
- BITUMINOUS OVERLAY DEPTH TABLE SHEET 2

ITEM NO	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AR108158	1/C #8 5KV UG CABLE IN UD	LF	17,500.00	
AR110014	4" DIRECTIONAL BORE	LF	100.00	
AR110610	ELECTRICAL HANDHOLE	EACH	1.00	
	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	1.00	
document medicine	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	1.00	
	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	4.00	
	MIRL, STAKE MOUNTED	EACH	34.00	
	MIRL, BASE MOUNTED	EACH	17.00	
	MI THRESHOLD LIGHT BASE MTD	EACH	8.00	
	SPLICE CAN	EACH	1.00	
AR125610	17 C 2 C 2 C 2 C 2 C 2 C 2 C 2 C 2 C 2 C	PAIR	1.00	
	REMOVE STAKE MOUNTED LIGHT	EACH	32.00	
	REMOVE BASE MOUNTED LIGHT	EACH	27.00	
	REMOVE TAXI GUIDANCE SIGN	EACH	6.00	
tura in processor security	REMOVE REILS	PAIR	1.00	
	ADJUST STAKE MOUNTED LIGHT	EACH	22.00	
SILT SOFT SHARE	ADJUST BASE MOUNTED LIGHT	EACH	22.00	
	ADJUST SPLICE CAN	EACH	4.00	
	REFURBISH BASE MOUNTED LIGHT	EACH	8.00	
Non-New Supplierson		LS	1.00	
	ENGINEER'S FIELD OFFICE	LS	1.00	
United States	MOBILIZATION	The same	2000 2000 2000 2000	
	SHOULDER ADJUSTMENT	SY	35,000.00	
	SILT FENCE	LF	400.00	
	INLET PROTECTION	EACH	11.00	
	CLEAN & SEAL BITUMINOUS CRACKS	LF 	10,500.00	
	SAND MIX CRACK REPAIR	LF	24,500.00	
	POUROUS GRANULAR EMBANKMENT	CY	155.00	
	BITUMINOUS SURFACE COURSE	TON	5,900.00	
	BIT. SURFACE COURSE, LEVELING	TON	7,100.00	
	BITUMINOUS SURFACE TEST SECTION	EACH	1.00	
1	BITUMINOUS PAVEMENT GROOVING	SY	48,740.00	
	BITUMINOUS PAVEMENT MILLING	SY	17,500.00	
	BUTT JOINT CONSTRUCTION	SY	540.00	
na na area de la compansión de la compan	REM & REP BIT PAVEMENT - TYPE A	SY	350.00	
	REM & REP BIT PAVEMENT - TYPE B	SY	1,925.00	
re_navousedenge	BITUMINOUS TACK COAT	GAL.	17,600.00	
	PAVEMENT MARKING - WATERBORNE	SF	82,500.00	
that is an account of the	PAVEMENT MARKING REMOVAL	SF	29,300.00	
AR701312	12" RCP, CLASS II	LF	70.00	
AR701318	18" RCP, CLASS II	LF	30.00	
AR701324	24" RCP, CLASS II	LF	30.00	
AR701900	REMOVE PIPE	LF	130.00	
AR705945	ADJUST COLLECTION STRUCTURE	EACH	18.00	
AR751560	MANHOLE 6'	EACH	2.00	
AR751903	REMOVE MANHOLE	EACH	2.00	
AR751927	REPLACE FRAME & GRATE	EACH	2.00	
AR800864	2-#4 XLP-USE, 1-#10 GND IN 1-1/4" UNIT DUCT	LF	225.00	
AR901510	SEEDING	ACRE	7.50	
APQ08515	HEAVY-DUTY HYDRAULIC MULCH	ACRE	7.50	

IL. CONTRACT: FR040

IL. LETTING ITEM: **05A** IL. PROJECT: FEP-4296 S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX

REVISIONS			
NUMBER	BY	DATE	
0	1	2	


THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).


FREEPORT-ALBERTUS AIRPORT FREEPORT, ILLINOIS REHABILITATE RUNWAY 6/24 回る SH OF INDEX UMMAF S

DESIGN BY: KD JRO CHECKED BY: DKP APPROVED BY: DATE: 06/03/2016 JOB No: 15294-03-00

FINAL

SHEET 2 OF 29 SHEETS





- ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2F (LATEST EDITION) OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.
- CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA
- THE AIRPORT MANAGER IN CONSULTATION WITH THE RESIDENT ENGINEER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING SEQUENCE AS IT RELATES TO PEDESTRIAN, VEHICULAR AND AIRCRAFT SAFFTY
- ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE—CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPAIRING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS DUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE
- THE CONTRACTOR SHALL KEEP ALL TRUCKS. EQUIPMENT AND MATERIALS OFF OF THE EXISTING TAXIWAYS. APRONS AND RUNWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER.
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE. LIGHTING SHALL BE AS APPROVED BY THE RESIDENT ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY. CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
- THE CONTRACTOR SHALL PROVIDE PORTABLE FLOOD LIGHTING FOR NIGHTIME CONSTRUCTION. SUFFICIENT UNITS SHALL BE PROVIDED SO THAT WORK AREAS ARE ILLUMINATED TO A LEVEL OF FIVE HORIZONTAL FOOT CANDLES. THE LIGHTING LEVELS SHALL BE CALCULATED AND MEASURED IN ACCORDANCE WITH THE CURRENT STANDARDS OF THE ILLUMINATION ENGINEERING SOCIETY. LIGHTS SHALL BE POSITIONED SO AS NOT TO INTERFERE WITH AIRPORT OPERATIONS.
- 9. THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. WHEN ACTIVE AIRFIELD PAVEMENTS ARE UTILIZED AS HAUL ROADS BY THE CONTRACTOR, MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 10. MATERIALS REMOVED FROM THE PROJECT WILL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED
- 11 PAYMENT FOR TRAFFIC CONTROL INCLUDING BUT NOT LIMITED TO BARRICADES, SIGNING BUNWAY CLOSED MARKERS, AIR OPERATIONS AREA (A.O.A.) LATHE AND RIBBON, ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES WITH ONE ORANGE FLAGS (20" x 20") ON EACH BARRICADE SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER. BARRICADES SHALL BE WEIGHTED TO PREVENT BLOWING OVER. BARRICADES SHALL HAVE A STEADY BURN OR FLASHING RED LIGHT. BARRICADE INSTALLATION WILL BE REQUIRED PRIOR TO ACCESS TO THE A.O.A. BY CONTRACTOR'S WORKERS, EQUIPMENT OR MATERIAL, SIGNS SHALL BE PLACED AT EACH TAXIWAY/RUNWAY CLOSURE LOCATION AND SHALL BE ATTACHED TO THE BARRICADES. EACH BARRICADE LOCATION SHALL CONSIST OF ONE "DO NOT ENTER" SIGN AND ONE "ARCRAFT MOVEMENT AREA" SIGN.
 SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL SUPPLY AND USE
 AS DIRECTED BY THE AIRPORT, REFLECTIVE LOW PROFILE TYPE BARRICADES. ALL BARRICADES SHALL BE PLACED OUTSIDE OF ACTIVE SAFETY AREAS.
- 12. THE CONTRACTOR SHALL CONTACT THE AIRPORT MANAGER THROUGH THE RESIDENT ENGINEER FOURTEEN (14) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED.
- 13 THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING ALL CONSTRUCTION ACCESS GATES CLOSED DURING NON WORKING HOURS. THE CONTRACTOR SHALL PROVIDE A SIGN AT THE ACCESS GATE SAYING "AUTHORIZED PERSONNEL ONLY". THE CONTRACTOR SHALL CLOSE AND LOCK THE ACCESS GATE UPON LEAVING THE SIGE. THROUGHOUT THE DURATION OF THE CONTRACT, ANY DAMAGES TO THE ACCESS ROAD, ACCESS GATE OR FENCING ADJACENT TO THE PROJECT SHALL BE REPAIRED BY THE CONTRACTOR TO THE SATISFACTION OF THE RESIDENT ENGINEER, ALL COST RELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 14. CONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS AND HAVE BEACON LIGHTS ON ALL EQUIPMENT AT ALL TIMES DURING CONSTRUCTION. SEE FLAG DETAIL.
- 15. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT MANAGER AND THE RESIDENT
- 16. DURING ADVERSE WEATHER, THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK
- 17. THE TALLEST PIECE OF CONSTRUCTION EQUIPMENT IS ANTICIPATED TO BE AN ASPHALT/STONE TRUCK WHICH HAS A MAXIMUM HEIGHT OF 25 FEET IN A DUMP POSITION.
- 18. IF RUNWAY NUMERALS ARE PRESENT DURING CONSTRUCTION THEN CONTRACTOR SHALL PLACE CLOSED MERALS AS DETAILED, OTHERWISE PLACE RUNWAY CLOSED MARKER IN TURF AT ENDS OF RUNWAY AS DETAILED.
- 19. THE AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS.
- 20. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS OR CITY STREETS) WITH THE APROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL ROUTE. THE BEFORE AND AFTER CONDITION OF ON—SITE HAUL ROUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK. ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND
- 21. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE.

- 22. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S OR AS DIRECTED BY THE CONNEX OF THE CASLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO NEXT EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS. ANY NECESSARY REPAIRS TO FAA CABLES SHALL BE IN THEIR ENTIRETY, NO SPLICES SHALL BE PERMITTED IN FAA CABLES. ANY REPAIRS SHALL BE INCIDENTAL TO THE CONTRACT.
- 23. COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE RESIDENT ENGINEER, AIRPORT OPERATIONS, FAA, AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSPOLIENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE
- 24. THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY, PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- 25. DRAINAGE MODIFICATIONS SHALL BE SEQUENCED TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES AT NO
- 26. CONTRACTOR PERSONNEL, VEHICLES, EQUIPMENT AND BARRICADES SHALL NOT BE ALLOWED WITHIN THE TAXIWAY / TAXILANE OBJECT FREE AREA (TOFA) OF ACTIVE TAXIWAYS / TAXILANES AND THE RUNWAY'S
- 27. CONTRACTOR SHALL STORE EQUIPMENT AND MATERIALS IN SUCH A MANNER AS NOT TO VIOLATE FEDERAL AVIATION ADMINISTRATION PART 77 IMAGINARY SURFACES OR RUNWAY AND TAXIWAY SAFETY AREAS.
- 28. ALL EXISTING TAXIWAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER ELECTRICAL ALL EXISTING TAXIMAY AND RUNWAY AIRFIELD LIGHTING CIRCUITS, FAA CABLES AND OTHER ELECTRICAL CABLES SHALL REMAIN IN SERVICE AT ALL TIMES. ALL EXISTING LIGHTING AND VAULT EQUIPMENT SHALL REMAIN IN SERVICE UNTIL PROPOSED IMPROVEMENTS ARE INSTALLED AND OPERATIONAL, UNLESS OTHERWISE APPROVED BY THE RESIDENT ENGINEER. ANY CABLES DAMAGED BY THE CONTRACTOR SHALL BE IMMEDIATELY REPAIRED AT HIS EXPENSE. ANY NECESSARY TEMPORARY JUMPER CABLES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 29. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. CONTRACTOR IS REFERRED TO SECTION 50-17 OF THE STANDARD SPECIFICATIONS AND THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAVE BEEN OBTAINED FROM EXISTING RECORDS. NETHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE RESIDENT ENGINEER AND THE AIRPORT MANAGER ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER
- 30. ALL AIRFIELD LIGHTING AND LIGHTING GUIDANCE SYSTEMS (NAVAIDS) LOCATED WITHIN AND IMMEDIATELY ADJACENT TO THE CONTRACTORS WORK ZONE SHALL BE CHECKED FOR OPERATIONAL CONDITION PRIOR TO THE DEPARTURE FROM THE AIRPORT WITH THE AIRPORT MANAGER. ANY DEFECIENCIES IN THESE SYSTEMS DUE TO THE ACTS OF CONTRACTOR OR HIS SUBCONTRACTORS, SUPPLIERS OR CONSULTANTS SHALL BE REPAIRED IMMEDIATELY.
- 31. THE CONTRACTOR SHALL PREPARE A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD). THE SPCD SHALL DETAIL HOW THE CONTRACTOR WILL COMPLY WITH THE CONSTRUCTION SAFETY AND PHASING PLAN (CSPP). DURING THE DEVELOPMENT OF THE CSPP, IT IS NOT POSSIBLE TO DETERMINE ALL SAFETY PLAN DETAILS, SUCH AS SPECIFIC EQUIPMENT HAZARDS AND LIGHTING, CONTRACTOR'S POINTS OF CONTACT CONSTRUCTION EQUIPMENT HEIGHT, ETC. THE SUCCESSFUL CONTRACTOR MUST DEFINE SUCH DETAILS BY PREPARING AN SPCD THAT IS REVIEWED BY THE AIRPORT OPERATOR FOR APPROVAL PRIOR TO ISSUANCE OF THE NOTICE TO PROCEED. THE SPCD IS A SUBSET OF THE CSPP AND WILL BE ADDRESSED IN THE SAME FASHION AS A SHOP DRAWING FOR TECHNICAL COMPLIANCE WITH THE CSP

CONTRACTOR CROSSING RUNWAY/TAXIWAY/TAXILANE/APRON

- 1. ANYTIME THE CONTRACTOR IS REQUIRED TO UTILIZE OR CROSS ACTIVE AIRFIELD PAVEMENTS FOR ACCESS TO AND FROM THE WORK ZONE, A FULL TIME CROSSING GUARD IN RADIO CONTACT WITH AIR TRAFFIC SHALL BE FURNISHED BY THE CONTRACTOR FOR MOVEMENTS OF VEHICLES OR EQUIPMENT TO AND FROM THE WORK ZONE. THE RADIO OPERATOR SHALL BE FAMILIAR WITH AIRPORT GROUND CONTIOL PROCEDURES AND DEMONSTRATE KNOWLEDGE OF SAME TO THE AIRPORT. THE AIRPORT RESERVES THE RIGHT TO APPROVE THE CROSSING GUARDS. THE CONTRACTOR SHALL PROVIDE THEIR OWN RADIOS. THIS COST SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYMENT OF MUNICIPAL FINES (\$500 PER OCCURENCE) DUE TO AIRFIELD INCURSIONS BY HIS EMPLOYEES, SUBCONTRACTORS, SUPPLIERS,
- 2. ANY PAVEMENT DAMAGED BY CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY BY HIM TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER AT NO ADDITIONAL COST TO THE OWNER. PAVEMENT SHALL BE CONTINUALLY SWEPT TO PROVIDE DEBRIS FREE SURFACE DURING ALL HAUL ROAD OPERATIONS. THIS COST SHALL NOT BE PAID SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- WORK WITHIN THE A.O.A. SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARRICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE A.O.A. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE MEN AND EQUIPMENT TO ALLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (10) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE

LIMITATIONS ON CONSTRUCTION WITHIN RUNWAY'S AIRCRAFT OPERATIONS AREA (AOA) AND TAXIWAY/TAXILANE OBJECT FREE AREA (TOFA)

THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER TEN (10) WORKING THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER (EN (I)) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. WORK SHALL BE EXPEDITED IN THESE AREAS AND AT THE END OF EACH WORKING DAY THESE AREAS SHALL BE SMOOTHLY GRADED TO ALLOW THE RUNWAY TO BE REOPENDE AT LEAST ONE OF THE RUNWAYS SHALL REMAIN IN OPERATION AT ALL TIMES. IF NECCESSARY STEEL PLATES SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR TO COVER ANY OPEN TRENCHES OR EXCAVATION WITHIN THE RSA IF DURING RUNWAY CLOSURE AN EMERGENCY IS DECLARED, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE RUNWAY OF ALL VEHICLES, MEN AND EQUIPMENT. REFERENCE TABLE ON PREVIOUS SHEET FOR SAFETY AREA WIDTHS.

TAXIWAYS / TAXILANES:

ANY WORK WITHIN TAXIWAY / TAXILANE OBJECT FREE AREA (TOFA) WILL REQUIRE A TAXIWAY / TAXILANE CLOSURE. WORK WITHIN THE TOFA SHALL BE EXPEDITED. ANY DROP OFF SHALL BE ADEQUATELY LIGHTED, SIGNED AND BARRICADED. NO MATERIAL SHALL BE STOCKPILED WITHIN THE TOFA. SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARILY RELOCATE COUPPENT OLLOW AIRCRAFT TO PASS, THEY SHALL DO SO AT NO EXTRA COST TO THE PROJECT. THE CONTRACTOR SHALL NOTIFY THE RESIDENT ENGINEER AND AIRPORT MANAGER FIVE (5) WORKING DAYS IN ADVANCE OF ANY PLANNED CONSTRUCTION WITHIN THESE LIMITS. REFERENCE TABLE ON PREVIOUS SHEET FOR OBJECT FREE AREA WIDTHS. NO DROP-OFFS OR OPEN EXCAVATIONS WILL BE ALLOWED WITHIN THE TAXIWAY / TAXILANE SAFETY AREAS OF OPEN TAXIWAYS / TAXILANES.

PRIOR TO REOPENING A CLOSED RUNWAY, THE ENTIRE (RSA) RUNWAY SAFETY AREA (250 FEET FROM CENTERLINE AND INCLUDING BEYOND THE END OF THE RUNWAY WITHIN AIRPORT PROPERTY) AND (TOFA) TAXIWAY OBJECT FREE AREA MUST MEET FAA CRITERIA. FAA CRITERIA REQUIRES THAT THERE BE NO OPEN EXCAVATIONS OR TRENCHES IN THE SAFETY HAI THERE BE NO OPEN EXCAVATIONS OF TRENCHES IN THE SAFETY
AREA(S), THE MAXIMUM PAVEMENT DROP OFF IS 3 INCHES, AND ALL
GRADES IN ANY DIRECTION BE LESS THAN 5 PERCENT. STEEL PLATES,
TEMPORARY WEDGING OF BASE COURSE AND BITUMINOUS CONCRETE MAY
BE REQUIRED TO MEET CRITERIA ALL NECESSARY TEMPORARY MEASURES
SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

MAXIMUM ANTICIPATED HEIGHT OF CONSTRUCTION EQUIPMENT: DUMP TRUCK IN DUMP POSITION - 25'

IN THE EVENT THE CONTRACTOR PROPOSES TO LITUIZE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN WHAT IS LISTED. THE CONTRACTOR WILL BE RESPONSIBLE TO SUBMIT FAA FORM 7460 FOR AIRSPACE APPROVAL. THE RESIDENT ENGINEER WILL PROVIDE BASE AIRPORT INFORMATION FOR THE CONTRACTOR'S USE.

DESIGN AIRCRAFT APPROACH CATEGORY: B* AIRPLANE DESIGN GROUP: II

REHABILITATE RUNWAY 6/24 MAXIMUM ANTICIPATED WINGSPAN OF ADG II GULFSTREAM G450 - WINGSPAN = 77.8'

*ALP DESIGN AIRCRAFT APPROACH CATEGORY IS D, HOWEVER, REHABILITATION PROJECT IS DESIGNED TO APPROACH CATEGORY B STANDARDS.

TABLE 1 - CRITICAL POINTS APPROXIMATE ELEVATION OF ANTICIPATED LONGITUDE EQUIPMEN1 ELEVATION OF (NAD 83) (NAD 83) GROUND AND HEIGHT EQUIPMENT 1929 DATUM) 1929 DATUM C1 848 SEMI/DUMP TRUCK - 25' 873 42°14'35.77" 89°35'03.17" C2 846 SEMI/DUMP TRUCK - 25' 871 42°14'39.81' 89°34'55.62" C3 SEMI/DUMP TRUCK - 25' 42°14'47.03" 89°34'42.13" C4 845 SEMI/DUMP TRUCK - 25' 89°34'34.58" 42°14'51.08' C5 SEMI/DUMP TRUCK - 25' 840 42°14'53.53" 89°34'37.79" C6 839 SEMI/DUMP TRUCK - 25' 864 42°14'47.39" 89°34'47.15" C7 SEMI/DUMP TRUCK - 25' 42°14'40.42' 89°35'03.73" C8 SEMI/DUMP TRUCK - 25 42°14'45.28" 89°35'02.53"

	EXISTING CRITICAL AIRCF	RAFT AND REQ	UIRED SAFET	Y AREAS
	RUNWAY	6/24	13/31	18/36
	APPROACH CATEGORY	В	В	В
	DESIGN GROUP	II	I	I
	DESIGN AIRCRAFT	GULFSTREAM IV	BEECH BARON 58	CESSNA 206
	APPROACH SPEED	145 KNOTS	96 KNOTS	91 KNOTS
DALP	WINGSPAN	78 FEET	38 FEET	36 FEET
OVE	TAIL HEIGHT	24.4 FEET	9.8 FEET	9.3 FEET
APPROVED	STRENGTH (MGTW)	71,780 LB\$.	5,500 LBS.	3,600 LBS.
E L	LENGTH	90 FEET	30 FEET	29 FEET
	RUNWAY SAFETY AREA WIDTH (RSA)	500 (250' FROM φ)	120 (60' FROM ပု)	120 (60' FROM ပု)
FROM 2011	(1)(3) RWY OBJECT FREE AREA WIDTH (ROFA)	800	250	250
FR	TAXIWAY SAFETY AREA WIDTH (TSA)	79	49	49
DATA	(1)(3) TXY OBJECT FREE AREA WIDTH (TOFA)	131 (65.5' FROM _C C)	89 (44.5° FROM Q)	89 (44.5' FRM Ç)

- 1. TOFA, ROFA, RSA, CRITICAL AREAS, PART 77 AND DEPARTURE/APPROACH SURFACES ARE SHOWN FOR RUNWAY 6/24 WHICH SHALL BE CLOSED DURING THE CONSTRUCTION PHASE DURATION
- 2. RUNWAY 6/24 END COORDINATES ARE NOT CHANGING IN THIS PROJECT.
- 3. NO CONSTRUCTION WITHIN THESE LIMITS WILL BE ALLOWED WITHOUT THE RUNWAY AND/OR TAXIWAY CLOSED.
- 4. AT THE END OF THE WORK DAY, NO CONSTRUCTION EQUIPMENT SHALL BE PARKED/STORED WITHIN THE OBJECT FREE AREA(S) OF OPEN OR CLOSED RUNWAYS AND/OR TAXIWAYS. PARKED/STORED EQUIPMENT HEIGHT SH. NOT PENETRATE PART 77 SURFACE(S).

IL. CONTRACT: FR040

- IL. LETTING ITEM: 05A
- IL. PROJECT: FEP-4296 S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX

REVISIONS			
NUMBER	BY	DATE	

THIS BAR IS FOUAL TO 2"

AT FULL SCALE (34X22)

S E SERTUS AIRPORT RT, ILLINOIS E RUNWAY 6/24 STRUC ETAILS 8 Ω JF CC AND RT-ALBE EEPORT, ILITATE OF EQUENCE O FREEPORT-/ FREEF REHABILIT

ᆸ

ERAL

ш

S

NEERS 00061

U

DESIGN BY: KD DRAWN BY JRO CHECKED BY DKP APPROVED BY DATE: 06/03/2016 JOB No: 15294-03-00

FINAL

SHEET 5 OF 29 SHEETS

Ξ.

	Plane\ segmente
11:37:46 AM	Preliminary
11:37:	/Shapte
2016	1-03/0-
June 3, 2016	rtAn\ 15294
DATE: Friday,	K-\Franco
DATE:	i

WORK AREA	ALLOWABLE WORK PERIOD	OPERATION STATUS/RESTRICTIONS	
PHASE 1 RUNWAY 6/24 CRACK REPAIR	11 CALENDAR DAYS*	RUNWAY 5/24 AND CONNECTING TAXIWAYS — DAYTIME CLOSURES TAXIWAY E AND ALL APPONS — OPEN ALTERNATING DAYTIME CLOSURES OF TURF RUNWAYS — AS NEEDED	
PHASE 2 REHAB RUNWAY LIGHTING AND CIRCUIT RUNWAY HMA OVERLAY RUNWAY PAVEMENT MARKING — FIRST COAT ONLY LANDSCAPING	23 CALENDAR DAYS*	RUNWAY 6/24 AND CONNECTING TAXIWAYS - CLOSED TAXIWAY E AND ALL APRONS - OPEN ALTERNATING DAYTIME CLOSURES OF TURF RUNWAYS - AS NEEDED	
SUSPEND CONTRACT TIME — AWAITING CURE FOR BIT. PVMT. GROOVING	28 CALENDAR DAYS	RUNWAY 6/24, TURF RUNWAYS, CONNECTING TAXIWAYS, AND APRONS — OPEN	
PHASE 3 RUNWAY GROOVING RUNWAY PAVEMENT MARKING — FINAL COAT	10 CALENDAR DAYS*	RUNWAY 6/24 AND CONNECTING TAXIWAYS — CLOSED TAXIWAY E AND ALL APRONS — OPEN ALTERNATING DAYTIME CLOSURES OF TURF RUNWAYS — AS NEEDED	

* EXPEDITED WORK AREAS ON APPROACHES TO TURF RUNWAYS 18/36 AND 13/31 SHALL BE LIMITED TO TWO DAYS EACH.

SUGGESTED SEQUENCE OF CONSTRUCTION - PHASE 1

- PROVIDE ENGINEER'S FIELD OFFICE AND CONTRACTOR'S EQUIPMENT STORAGE AND PARKING
- . COORDINATE CLOSURES WITH RESIDENT ENGINEER AND AIRPORT MANAGER
- . PLACE CLOSED RUNWAY MARKERS, BARRICADES, AND INSTALL LATHING AND WARNING TAPE AS SHOWN OR AS DIRECTED BY THE ENGINEER.
- PLACE TEMPORARY EROSION CONTROL ITEMS OF WORK
- CONSTRUCT TYPE A AND B RUNWAY PAVEMENT REPAIRS, CLEAN AND SEAL BIT. CRACKS,
- . CLEAN PAVEMENTS, RESTORE DISTURBED WORK AREAS, AND REMOVE MISCELLANEOUS DEBRIS FROM WORK AREA.
- COORDINATE OPENING OF RUNWAY PAVEMENTS WITH RESIDENT ENGINEER AND AIRPORT
- · REMOVE CLOSED RUNWAY MARKERS AND BARRICADES.

SUGGESTED SEQUENCE OF CONSTRUCTION - PHASE 2

- COORDINATE CLOSURES WITH RESIDENT ENGINEER AND AIRPORT MANAGER.
- PLACE CLOSED RUNWAY MARKERS, BARRICADES, AND INSTALL LATHING AND WARNING TAPE AS SHOWN OR AS DIRECTED BY THE ENGINEER.
- MILL RUNWAY 6/24 EXISTING PAVEMENT.
- . CONSTRUCT RUNWAY 6/24 HMA PAVEMENT OVERLAY.
- REHABILITATE RUNWAY 6/24 LIGHTING AND CIRCUIT.
- CONSTRUCT RUNWAY 6/24 PAVEMENT MARKING 1ST COAT.
- LANDSCAPE TO RUNWAY 6/24 GRADING LIMITS.
- CLEAN PAVEMENTS, RESTORE DISTURBED WORK AREAS, AND REMOVE MISCELLANEOUS DEBRIS FROM WORK AREA.
- COORDINATE OPENING OF RUNWAY PAVEMENTS WITH RESIDENT ENGINEER AND AIRPORT MANAGER.
- REMOVE CLOSED RUNWAY MARKERS AND BARRICADES.

SUGGESTED SEQUENCE OF CONSTRUCTION - PHASE 3


- COORDINATE CLOSURES WITH RESIDENT ENGINEER AND AIRPORT MANAGER.
- PLACE CLOSED RUNWAY MARKERS, BARRICADES, AND INSTALL LATHING AND WARNING TAPE AS SHOWN OR AS DIRECTED BY THE ENGINEER.
- PROVIDE 28 CALENDAR DAY CURING PERIOD OR AS APPROVED BY THE ENGINEER PRIOR TO RUNWAY 6/24 BITUMINOUS PAVEMENT GROOVING (SUSPEND CONTRACT TIME).
- . CONSTRUCT RUNWAY 6/24 BITUMINOUS PAVEMENT GROOVING.
- CONSTRUCT RUNWAY 6/24 PAVEMENT MARKING 2ND COAT.
- CLEAN PAVEMENTS, RESTORE DISTURBED WORK AREAS, AND REMOVE MISCELLANEOUS
- COORDINATE OPENING OF RUNWAY PAVEMENTS WITH RESIDENT ENGINEER AND AIRPORT
- . REMOVE CLOSED RUNWAY MARKERS AND BARRICADES.

PHASE 3 - NOTES

1. NO ADDITIONAL COST TO CONTRACT FOR REMOBILIZATION AND 2ND COAT PAVEMENT MARKING

CONTRACTOR'S CONSTRUCTION ENTRANCE NOTES


- 1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT AND DEBRIS ONTO PUBLIC RIGHT-OF-WAYS. ALL SEDIMENT AND DEBRIS SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAYS MUST BE
- CONTRACTOR SHALL FURNISH CONSTRUCTION SIGNS ON BAILEYVILLE ROAD AS SHOWN OR AS REQUIRED BY STEPHENSON COUNTY D.O.T. COST OF SIGNS SHALL BE INCIDENTAL TO
- COST OF INSTALLING, MAINTAINING, REMOVING AND RESTORING ENTRANCE SHALL BE INCIDENTAL TO THE CONTRACT.
- STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED AT ALL CONSTRUCTION ENTRANCES (COST INCIDENTAL)




FLASHER BARRICADE DETAIL NOT TO SCALE

NOTES

- FLASHERS TO BE BATTERY OPERATED. LENS TO BE RED AND BE ABLE TO ROTATE 90 DEGREES. ALTERNATE FLASHER
- 2. SANDBAGS TO BE PLACED ON EACH SUPPORT BRACE AS REQUIRED TO PREVENT DISPLACEMENT BY WIND, JET OR
- 3. NO SEPARATE PAYMENT WILL BE MADE FOR THIS ITEM. COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 4. PLACE AT TEN (10') INTERVALS.
- 5. ONE 20"x20" ORANGE FLAG TO BE INSTALLED ON EACH BARRICADE.
- 6. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING BARRICADES AT ALL TIMES TO THE SATISFACTION OF THE AIRPORT MANAGER.



CONSTRUCTION EQUIPMENT AND TRUCK SIGNAL FLAG




ON PAVEMENT TEMPORARY CLOSED RUNWAY MARKER DETAIL

END OF RUNWAY


OFF PAVEMENT TEMPORARY

CLOSED RUNWAY MARKER DETAIL NOTES

- 1. CLOSED RUNWAY MARKERS SHALL BE YELLOW.
- 2. MARKERS SHALL BE MATERIAL APPROVED BY THE ENGINEER.
- CONTRACTOR SHALL MAINTAIN AND RELOCATE MARKERS AS SHOWN ON THE PLANS OR AS NEEDED TO FACILITATE CONSTRUCTION
- 4. MARKERS ON PAVEMENT SHALL BE PLACED OVER EXISTING RUNWAY NUMERALS AS SHOWN.
- COST OF FURNISHING, INSTALLING, MAINTAINING AND REMOVING MARKERS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- 6. DURING VARIOUS PHASES OF WORK, IT WILL BE NECESSARY TO CLOSE RUNWAYS TO AIR TRAFFIC ON A TEMPORARY BASIS AS COORDINATED WITH THE AIRPORT. THE CONTRACTOR SHALL MARK THE RUNWAYS TO BE CLOSED BY PLACING A YELLOW CROSS AT THE LOCATION AND DIMENSIONS DETAILED ON THIS SHEET. THE CROSSES ARE SHOWN ON THE RESPECTIVE RUNWAYS ACCORDING TO THE VARIOUS PHASES OF WORK AS DELINEATED IN THE SUGGESTED SEQUENCE OF CONSTRUCTION.



CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS (SEE STANDARD SPECIFICATIONS SECTION 50-05). THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS.



CLOSED RUNWAY MARKER DETAIL NOT TO SCALE

& ERS

FREEPORT-ALBERTUS AIRPORT FREEPORT, ILLINOIS REHABILITATE RUNWAY 6/24

U

IL. CONTRACT: FR040 IL. LETTING ITEM: 05A IL. PROJECT: FEP-4296 S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX REVISIONS

BY

THIS BAR IS FOUAL TO 2" AT FULL SCALE (34X22)

7

ᆸ

SHEI

LS C

NSTRI DETAIL

JF CC AND

SEQUENCE (GENERAL NOTES


P

NUMBER

DESIGN BY: KD DRAWN BY: JRO CHECKED BY DKP DATE: 06/03/2016 JOB No: 15294-03-00

FINAL

SHEET 6 OF 29 SHEETS



STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE AT CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION:

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

HIS PROJECT CONSISTS OF REHABILITATION OF AN EXISTING BITUMINOUS PAVEMENT AT THE REEPORT—ALBERTUS AIRPORT. THE PROJECT INCLUDES TURF SHOULDER ADJUSTMENT, VARIOUS PAVEMENT FREEPORT-ALBERTUS AIRPORT. ITEMS, ELECTRICAL WORK, PAVEMENT MARKING AND OTHER MISCELLANEOUS CONSTRUCTION WORK.

DESCRIPTION OF CONSTRUCTION ACTIVITY:

FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS GRUBBING, EXCAVATION AND GRADING:

PLACEMENT, MAINTENANCE, REMOVAL AND PROPER CLEAN-UP OF TEMPORARY EROSION CONTROL. SUCH AS

REMOVAL, ADJUSTMENTS AND INSTALLATION OF ELECTRICAL AND MISCELLANEOUS ITEMS.

VARIABLE DEPTH BITUMINOUS PAVEMENT MILLING AND PAVING.

TURF SHOULDER ADJUSTMENT, SEEDING AND MULCHING.

BITUMINOUS PAVEMENT GROOVING.

INSTALLATION OF NEW PAVEMENT MARKING.

REMOVAL AND DISPOSAL OF TEMPORARY SOIL FROSION AND SEDIMENT CONTROL MEASURES.

AREA OF CONSTRUCTION SITE:

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 22 ACRES OF WHICH 9 ACRES WILL BE DISTURBED BY GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING PROJECT FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION SITE DRAINS INTO THE PECATONICA RIVER THROUGH A STORM SEWER SYSTEM.

EROSION AND SEDIMENT CONTROL:

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, SOD, PROTECTION OF TREES, PRESERVATION OF NATURAL VEGETATION, AND ALL OTHER APPROPRIATE MESURES AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR

AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION

DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER.

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET PROTECTIONS SHALL BE INSTALLED AS CALLED OUT IN THE PLAN AND DIRECTED BY THE

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILLTO, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTSIDED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.

WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.

EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN SEVEN (7) DAYS.

THE DOWN STREAM SIDE OF ALL STOCKPILES SHALL BE ENCOMPASSED WITH EROSION CONTROL BARRIER.

AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS

CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS WITHIN THE STAGING AREA. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE

THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT PERIODICALLY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2" OR GREATER OR COUNSINGUIVALENT SNOWFALL AND DURING WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE RESIDENT ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT THE EROSION AND SEDIMENT CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY.

SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. <u>THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND EROSION</u>

THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS R
THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS. THIS REMOVAL SHALL BE INCLUDED IN

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING SOIL CONTAMINATION FROM BUILDING MATERIALS, FERTILIZERS, CHEMICALS, PAVEMENT MARKING, WASTE PILES, FUEL CONTAINMENT, AND ANY OTHER POTENTIAL HAZARDOUS MATERIALS THAT MAY EXIST ONSITE.

NO DEDICATED CONCRETE OR ASPHALT BATCH PLANTS SHALL BE LOCATED ON THIS SITE.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

COST_OF_MAINTAINING_THE_VARIOUS_TEMPORARY_EROSION_CONTROL_SYSTEMS_SHALL_BE_INCLUDED_INCLUDED IN THE UNIT BID PRICE FOR THE VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RE-SEEDED AND/OR SODDED.

MAINTENANCE AFTER CONSTRUCTION:

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE OF TEMPORARY AND PERMANENT EROSION CONTROL SYSTEMS UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF INTENT (NOI)" PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY.

PRIOR TO BEGINNING WORK, THE CONTRACTOR SHALL POST A SIGN OR OTHER NOTICE NEAR THE MAIN ENTRANCE OF THE CONSTRUCTION SITE. IF THIS IS NOT POSSIBLE, THEN IT MAY BE PERMITTED TO POST THIS NOTICE IN A LOCAL PUBLIC BUILDING. THE SIGN OR NOTICE MUST CONTAIN THE FOLLOWING:

- 1. A COPY OF THE COMPLETED NOTICE OF INTENT (NOI) AS SUBMITTED TO THE IEPA
- 2. THE LOCATION OF THE SWPPP AND NAME AND 24/7 TELEPHONE NUMBER OF THE CONTACT PERSON.

THROUGHOUT CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AND UPDATE AN "AS-BUILT" SET OF STORM WATER POLLUTION PREVENTION PLANS IN THE PROJECT FILES. THE SWPPP SHALL BE UPDATED WITHIN 7-DAYS OF ANY MODIFICATIONS TO THE PLANS. THE SWPPP AND ALL REVISIONS SHALL BE RETAINED FOR THREE YEARS AFTER FINAL STABILIZATION OF THE SITE, WHICH SHALL BE DEFINED AS VEGETATION COVER OF AT LEAST 70% OF HISTORIC CONDITIONS.

A STORM WATER POLLUTION PREVENTION PLAN EROSION CONTROL INSPECTION REPORT (FORM BC 2259) SHALL BE BE COMPLETED WITH INSPECTION FREQUENCIES AS OUTLINED HEREIN, SWPPP REPORTS SHALL BE RETAINED FOR THREE YEARS AFTER THE DATE OF FINAL STABILIZATION AS DEFINED HEREIN.

IF ANY VIOLATION OF THE PROVISIONS OF THE PLAN IS IDENTIFIED DURING THE CONDUCT OF THE CONSTRUCTION COVERED IN THIS PLAN, THE ENGINEER AND/OR CONTRACTOR SHALL COMPLETE AND FILE AN "INCIDENT OF NONCOMPLIANCE (ION)" REPORT FOR THE IDENTIFIED VIOLATION. THE FORMS SHALL BE AS PROVIDED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY, AND SHALL INCLUDE SPECIFIC INFORMATION ON THE INCIDENT T CAUSED NONCOMPLIANCE, ACTIONS THAT WERE TAKEN TO CORRECT THE NONCOMPLIANCE AND TO PREVENT REOCCURRENCE, AND A STATEMENT DETAILING ANY ENVIRONMENTAL IMPACT WHICH MAY HAVE RESULTED FROM THE NONCOMPLIANCE, ALL REPORTS OF NONCOMPLIANCE SHALL BE SIGNED BY A RESPONSIBLE AUTHORITY IN ACCORDANCE WITH PART VI. G. OF THE GENERAL PERMIT.

AFTER PROJECT FINAL ACCEPTANCE, THE CONTRACTOR SHALL COMPLETE AND SUBMIT A "NOTICE OF TERMINATION (NOT)" FORM PROPERLY SIGNED TO THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY. FORMS FOR THE IEPA SHALL BE MAILED TO THE FOLLOWING ADDRESS"

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL, MAIL CODE #15 ATTN: PERMIT SECTION 1021 NORTH GRAND AVENUE EAST P.O. BOX 19276 SPRINGFIELD, ILLINOIS 62794-9276

NPDES PERMIT #	
DATE ISSUED	
DATE EXPIRED	

GENERAL NOTES FOR SOIL EROSION AND SEDIMENT CONTROL:

- 1. ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.
- 2. NO WORK SHALL BE PERFORMED IN FLOWING WATER. WORK IN AND NEAR FLOWING WATER SHALL BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE ACCEPTABLE.
- 3. CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN
- 4. TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS
- 5. PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE, UNDER NO CIRCUMSTANCES SHALL CONTRACTOR PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDE
- 6. THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY. ADJACENT STREETS SHALL BE KEPT FREE OF SOIL AND DEBRIS
- 7. SHOULD IT BE NECESSARY TO REMOVE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS, TH CONTRACTOR SHALL FIRST OBTAIN PERMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICE THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL T THE CONTRACT
- 8. ALL OTHER SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE RESIDENT ENGINEER, STEPHENSON COUNTY, FREEPORT-ALBERTUS AIRPORT, IDOT DIVISION OF AERONAUTICS, AND THE IEPA SHALL BE IMPLEMENTED IMMEDIATELY UPON NOTIFICATION OF THE CONTRACTOR
- 9. THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE ENGINEER, PRIOR TO ANY CONCRETE POURS. THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER. LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND FINISHING TOOLS. ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY.
- 10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL MEASURES ARE CONSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS.
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT, CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL. THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION MATERIAL IS NOT DISPOSED OF IN THE WETLANDS.
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED BY AN APPROVED MEANS.
- 13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON A REGULAR BASIS. SEDIMENT SHALL BE REMOVED FROM EROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE—HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER, WHICHEVER IS LESS.
- ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY THROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OPERATIONAL
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER, ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL RECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING, MULCHING AND/OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING
- 16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.

CONTRACTOR CERTIFICATION STATEMENT

THIS CERTIFICATION STATEMENT IS A PART OF THE STORM WATER POLITITION PREVENTION PLAN FOR THE PROJECT PESCRIBED BELOW IN ACCORDANCE WITH NPDES PERMIT NO. ILR10 ISSUED BY THE ILLINOIS ENVIRONMENT, PROTECTION AGENCY.

PROJECT INFORMATION:

ROUTE: FREEPORT-ALBERTUS AIRPORT	MARKED: REHABILITATE RUNWAY 6/24
SECTION: 21	PROJECT NUMBER: FEP-4296
COUNTY: STEPHENSON	CONTRACT NUMBER: 3-17-SBGP-XX (FR040)
	IDERSTAND THE TERMS AND CONDITIONS OF THE GENER.

AL NATIONAL DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS

SIGNATURE:	DATE:	
PRINTED NAME:	TITLE:	
NAME OF FIRM:	_	
STREET ADDRESS:	_	
CITY, STATE, ZIP:	_	
PHONE NUMBER:	_	
THE INFORMATION WITHIN THIS BOX SHALL B	F COMPLETED BY THE CONTRACTOR A	۵F

TER THE AWARD OF THE CONTRACT TO OBTAIN THE REQUIRED NPDES PERMIT FROM IEPA. COMPLETION OF THIS IS A CONTRACT

	RECORD OF SITE DISTURBANCE AND STABILIZATION	
MAJOR GRADING ACTIVITIES: LOCATION:	BEGINNING DATE:COMPLETION DATE:	_
MAJOR GRADING ACTIVITIES: LOCATION:	BEGINNING DATE: COMPLETION DATE:	_
SITE STABILIZATION: LOCATION:	BEGINNING DATE:	_
SITE STABILIZATION: LOCATION:	BEGINNING DATE:COMPLETION DATE:	
CONSTRUCTION CEASED: EXPLANATION:	BEGINNING DATE:COMPLETION DATE:	_

THE INFORMATION WITHIN THIS BOX SHALL BE COMPLETED BY THE CONTRACTOR AS CONSTRUCTION PROGRESSES IN ACCORDANCE WITH THE NPDES GENERAL PERMIT FOR STORMWATER DISCHARGES. THIS INFORMATION MAY ALSO BE NOTED DIRECTLY ON THE SWPPP SITE MAP.

IL. CONTRACT: FR040

IL. LETTING ITEM: 05A

IL. PROJECT: FEP-4296 S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX

		REVISIONS	
E D	NUMBER	BY	DATE
D			
N			
E S			
0			
-			

THIS BAR IS FOUAL TO 2" AT FULL SCALE (34X22)

₫

0 ERTUS AIRPORT T, ILLINOIS ERUNWAY 6/24 ZШ ШШ Ы S **C** മഗ ōŦ 5 2 RT-ALBE EEPORT, ILITATE _ 0 두핆 POA EEPOR FRE EHABI പ്പ ഗ ШШ WAT

Σ

0

S

ш

REE


& SS & U

DESIGN BY: KD DRAWN BY JRO CHECKED BY DKP APPROVED BY DI P DATE: 06/03/2016 JOB No: 15294-03-00

FINAL

SHEET 8 OF 29 SHEETS


ELEVATION



FABRIC ANCHOR DETAIL

- 1. TEMPORARY SILT FENCE SHALL BE INSTALLED PRIOR TO ANY GRADING WORK IN THE AREA TO BE PROTECTED. THEY SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD AND REMOVED IN CONJUNCTION WITH THE FINAL GRADING AND SITE STABILIZATION.
- 2. FILTER FABRIC SHALL BE A WOVEN FABRIC MEETING THE REQUIREMENTS OF AASHTO M288 FOR UNSUPPORTED SILT FENCE WITH LESS THAN 50 PERCENT GEOTEXTILE ELONGATION.
- 3. FENCE POSTS SHALL BE WOOD POST WITH A MINIMUM CROSS-SECTIONAL AREA OF 3.0 SO. IN.

SILT FENCE DETAIL




ATTACHING TWO SILT FENCES


NOTES:

- 1. PLACE THE END POST OF THE SECOND FENCE INSIDE THE END POST OF THE FIRST FENCE.
- 2. ROTATE BOTH POSTS AT LEAST 180 DEGREES IN A CLOCKWISE DIRECTION TO CREATE A TIGHT SEAL WITH THE FABRIC MATERIAL.
- 3. DRIVE BOTH POSTS A MINIMUM OF 18 INCHES INTO THE GROUND AND BURY THE FLAP.
- 4. SILT FILTER J-HOOK PLACEMENT SHALL BE IN ACCORDANCE WITH IDOT STD. 280001-07.

ATTACHING TWO SILT FENCES DETAIL







INLET PROTECTION (INLET/MANHOLES - IN TURF)

NOT TO SCALE IDOT STANDARD 280001-07

14' MIN. (SEE NOTE 4) SECTION A-A FILTER FABRIC REINFORCED CONCRETE DRAIN SPACE SECTION B-B PAVEMENT MOUNTABLE BERM FILTER FABRIC SIDE ELEVATION - EXISTING GROUND - ROADSIDE DITCH IF NEEDED WASH RACK -(OPTIONAL) B-GROUND EXISTING PAVEMENT COARSE AGGREGATE В-* MUST EXTEND FULL WIDTH OF INGRESS AND EGRESS 10' MIN. OPERATION. POSITIVE DRAINAGE TO SEDIMENT TRAPPING DEVICE


PLAN VIEW


STABILIZED CONSTRUCTION ENTRANCE

FROM NRCS STANDARD DRAWING NO. IL-630

- FILTER FABRIC SHALL MEET THE REQUIREMENTS OF MATERIAL SPECIFIED UNDER SECTION 1080.03, OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2012.
- 2. ROCK OR RECLAIMED CONCRETE SHALL MEET ONE OF THE FOLLOWING IDOT COARSE AGGREGATE GRADATION, CA-1, CA-2, CA-3 OR CA-4. COMPACTION SHALL BE TO THE SATISFACTION OF THE ENGINEER.
- ANY DRAINAGE FACILITIES REQUIRED BECAUSE OF WASHING SHALL BE CONSTRUCTED ACCORDING TO MANUFACTURERS SPECIFICATIONS AND SHALL BE INCIDENTAL TO THE CONTRACT
- 4. MINIMUM WIDTH IS 14' FOR ONE-WAY TRAFFIC AND 20' FOR TWO WAY TRAFFIC. TWO-WAY TRAFFIC WIDTHS SHALL BE INCREASED A MINIMUM OF 4 FOR TRAILER TRAFFIC. DEPENDING ON THE TYPE OF VEHICLE OR EQUIPMENT, SPEED, LOADS, CLIMATIC AND OTHER CONDITIONS UNDER WHICH VEHICLES AND EQUIPMENT OPERATE AN INCREASE IN THE MINIMUM WIDTHS MAY BE REQUIRED.
- 5. ROADWAY SHALL FOLLOW THE CONTOUR OF THE NATURAL TERRAIN TO THE EXTENT
- 6. IF WASH RACK ARE USED THEY SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS.
- THE STABILIZED CONSTRUCTION ENTRANCE SHALL NOT BE PAID FOR BUT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

IL. CONTRACT: FR040 IL. LETTING ITEM: **05A** IL. PROJECT: FEP-4296 S.B.G. PROJECT: **3-17-SBGP-XX**





П 0 2 FREEPORT-ALBERTUS AIRPORT FREEPORT, ILLINOIS REHABILITATE RUNWAY 6/24 EVEI Z i പ ഗ LUTI DET, POLI AND


WATER NOTES

SRS. U

DESIGN BY: CHECKED BY JOB No: 15294-03-00


FINAL


SHEET 9 OF 29 SHEETS





INLET PROTECTION - SILT BASKET (PAVEMENT AND TURF)


FOR ALL RECTANGULAR AND CIRCULAR INLETS














FULL DEPTH PAVEMENT
REMOVAL AND REPLACE
WITH BITUMINOUS BASE
COURSE (403)
TO MATCH DEPTH
OF EXISTING PAVEMENT IN 3"
MAXIMUM LIFTS. COST
INCIDENTAL TO PATCH.

CLEAN AND TACK (603)
PATCH EDGES

EXISTING PAVEMENT
SHALL BE SAW CUT
FULL DEPTH TO PRODUCE
A NEAT VERITCAL FACE.
COST INCIDENTAL TO
PATCH.

EXISTING
GRANULAR BASE
TO BE REGRADED
AND COMPACTED

REMOVE AND REPLACE BITUMINOUS PAVEMENT - TYPE B

NOT TO SCALE


PAVEMENT REMOVAL AND REPLACEMENT NOTES

- 1. DEPTHS OF EXISTING PAVEMENTS SECTIONS ARE APPROXIMATE BASED ON DATA SUPPLIED BY RECORDS, AIRPORT PERSONNEL, AND PAVEMENT CORES. THE CONTRACTOR SHALL VERIFY THE TYPE AND THICKNESS OF MATERIAL TO REMOVE. NO EXTRA COMPENSATION WILL BE ALLOWED FOR ANY VARIATION IN THE PAVEMENT SECTIONS ACTUALLY ENCOUNTERED.
- PAVEMENT REMOVAL AND REPLACEMENT QUANTITIES ARE ESTIMATED. EXISTING MEDIUM TO HIGH SEVERITY TRANSVERSE CRACKS ARE SPACED AT VARIABLE INTERVALS. THE RESIDENT ENGINEER SHALL LAY OUT PAVEMENT REMOVAL AND REPLACEMENT AREAS IN THE FIELD DURING CONSTRUCTION.
- 3. AS FIELD CONDITIONS WARRANT AT THE TIME OF CONSTRUCTION, FURNISHING AND PLACING OF POROUS GRANULAR EMBANKMENT SHALL BE DONE AT SECTIONS WHERE THE REMOVE AND REPLACE BITUMINOUS PAVEMENT TYPE B WAS UTILIZED. THIS SHALL BE DONE TO REPAIR SOFT SUBGRADE AS DETERMINED BY THE RESIDENT ENGINEER BASED ON RESULTS OF GEOTECHNICAL TESTING OR PROOF ROLL AS DETERMINED BY THE RESIDENT ENGINEER. NO ADJUSTMENT IN UNIT PRICE WILL BE ALLOWED FOR AN INCREASE OR DECREASE IN QUANTITIES.

IL. CONTRACT: FR040
IL. LETTING ITEM: 05A

IL. PROJECT: FEP-4296
S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX



THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

FREEPORT-ALBERTUS AIRPORT
FREEPORT, ILLINOIS
REHABILITATE RUNWAY 6/24
TYPICAL SECTIONS

CAMFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

DESIGN BY: KD

DRAWN BY: JRO

CHECKED BY: DKP


APPROVED BY: DLP


DATE: 06/03/2016


JOB No: 15294-03-00


FINAL


SHEET 13 OF 29 SHEETS

























NEW SPLICE CAN DETAIL

NOT TO SCALE



REIL DETAIL

NOT TO SCALE



RUNWAY END IDENTIFIER LIGHT (REIL) (LED) DETAIL


NOT TO SCALE

NOTES:

 THE PROPOSED REIL SYSTEM SHALL BE L-849I (CURRENT DRIVEN) COMPLETED WITH FLASHEADS, POWER ADAPTERS, FRANGIBLE FITTINGS AND ALL NECESSARY EQUIPMENT FOR A COMPLETE AND OPERATIONAL SYSTEM. REIL UNIT FAA APPROVED TYPE L-849I.


GENERAL NOTES:

- THE CONCRETE BASE FOR BASE MOUNTED LIGHTS SHALL BE TROWEL FINISHED WITH A 45° BEVELED EDGE. SLOPE TO DRAIN (610).
- 2. TRANSFORMER HOLDER SHALL BE ANY COMMERCIALLY AVAILABLE BRICK.
- 3. BREAKING GROOVE COUPLINGS SHALL NOT BE OVER 1" ABOVE GROUND LINE.
- 4. ISOLATION TRANSFORMERS COME WITH A FACTORY INSTALLED PLUG (TYPE 1, CLASS A, STYLE 2) AND RECEPTACLE (TYPE 1, CLASS A, STYLE 9). A TYPE 1, CLASS B, STYLE 3 PLUG AND TYPE 1, CLASS B, STYLE 10 RECEPTACLE SHALL BE INSTALLED ON THE 1/C, No. 8, 5000 V., L-824 TYPE C CABLES FOR CONNECTION TO EACH TRANSFORMER.
- TO FURTHER REDUCE THE POSSIBILITY OF WATER/MOISTURE ENTRANCE INTO THE CONNECTOR BETWEEN THE CABLE AND THE FIELD ATTACHED CONNECTOR, IT IS REQUIRED THAT A HEAT SHRINKABLE TUBING WITH INTERNAL ADHESIVE BE APPLIED OVER THE ENTIRE CABLE CONNECTOR.
- ALL LIGHTS, CABLES AND TRANSFORMERS TO BE REMOVED SHALL REMAIN THE PROPERTY OF THE AIRPORT. AT THE DISCRETION OF THE AIRPORT MANAGER, THE CONTRACTOR MAY BE REQUIRED TO DISPOSE OF THESE MATERIALS OFFSITE AT NO ADDITIONAL COST
- INSTALL 1/C #6 AWG BARE COPPER GROUND JUMPER CONNECTED TO GROUND LUG INSIDE BASE CAN OR STAKE AND EXOTHERMICALLY WELDED TO GROUND ROD.



STAKE MOUNTED MEDIUM INTENSITY RUNWAY EDGE/THRESHOLD LIGHT (LED) DETAIL

NOT TO SCAL



BASE MOUNTED MEDIUM INTENSITY RUNWAY EDGE LIGHT (LED) DETAIL

OT TO SCALE

IL. CONTRACT: FR040

IL. LETTING ITEM: 05A

IL. PROJECT: FEP-4296
S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX

	REVISIONS	
NUMBER	BY	DATE
0	1	2

THIS BAR IS EQUAL TO 2* AT FULL SCALE (34X22).

FREEPORT-ALBERTUS AIRPORT
FREEPORT, ILLINOIS
REHABILITATE RUNWAY 6/24
ELECTRICAL DETAILS - SHEET

CAMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

DESIGN BY: RMD

DRAWN BY: JRO

CHECKED BY: DKP


APPROVED BY: DLP


DATE: 06/03/2016

JOB No: 15294-03-00

FINAL


SHEET 22 OF 29 SHEETS






TYPE A - CABLE SPLICE


FOR SPLICES IN HOMERUNS AND FOR EXTENSIONS TO EXISTING CABLES ONLY N.T.S.




TYPE B - CABLE SPLICE

FOR SPLICES FOR USE AT JUNCTION OF HOMERUN WITH LOOP CIRCUIT NOT TO SCALE







CABLE IN UNIT DUCT - PLOWED


NOTE: CONTRACTOR SHALL HAVE THE OPTION TO TRENCH OR PLOW UNIT DUCT. NO ADDITIONAL PAYMENT SHALL BE MADE FOR TRENCHING.

TYPE C AND D - CABLE SPLICE

RUNWAY/TAXIWAY LIGHTS AND SIGNS NOT TO SCALE

CABLE SPLICE NOTES

- INSIDE DIAMETER OF CONNECTOR SHALL PROPERLY MATCH THE OUTSIDE DIAMETER OF CABLE.
- WRAP WITH AT LEAST ONE LAYER OF RUBBER OR SYNTHETIC RUBBER TAPE AND ONE LAYER OF PLASTIC TAPE, ONE—HALF LAPPED, EXTENDING AT LEAST 1-1/2 INCHES ON EACH SIDE OF JOINT.
- THE COST OF FURNISHING AND INSTALLING ALL SPLICE MATERIALS SHALL BE INCIDENTAL TO THE ASSOCIATED CABLE ITEMS.
- 4. THE CONTRACTOR SHALL HAVE A MINIMUM OF TWO (2) TYPE A SPLICE KITS ON THE JOB SITE AT ALL TIMES FOR EMERGENCY REPAIRS.



TURF AREA CABLE TRENCH DETAIL

NOT TO SCALE

NOTES

3/4"

.15"

PROPOSED PAVEMENT OR OVERLAY

DUCT MARKER DETAIL

3/16" R.¬

NON CORROSIVE METAL DISK (BRASS)

ELECTRICAL

DUCT/CONDUIT

- 1. TRENCHES WITH MORE THAN 2 CABLES SHALL BE INCREASED 4" IN WIDTH FOR EACH ADDITIONAL CABLE. IF SPECIFIED ON PLANS, TWO PARALLEL TRENCHES MAY BE CONSTRUCTED.
- 2. DEPTH OF TRENCHES SHALL BE AS SHOWN UNLESS OTHERWISE SPECIFIED ON THE PLANS.
- SAND BACKFILL SHALL BE USED IF THE EXISTING SOIL DOES NOT MEET THE BACKFILL REQUIREMENTS.

NUMBER OF DUCTS/CONDUITS AND

DUCT SIZE PRESTAMPED OR CHISELED ON THE JOB

DUCT MARKERS SHALL BE

DRILLED AND GROUTED SO THEY ARE RECESSED FROM THE


SURFACE OF THE PAVEMENTS.

ALL DUCTS LOCATIONS PROPOSED AND

FIELD. (COST INCIDENTAL TO CONTRACT)

EXISTING AS SHOWN ON THE CABLING AND DUCT PLAN. (COST INCIDENTAL) CONTACTOR SHALL LOCATE EXISTING DUCT LOCATIONS IN


4. ALL DISTURBED SURFACES SHALL BE RESTORED TO THEIR ORIGINAL CONDITION. COST IS INCIDENTAL.



TURF CABLE MARKER DETAIL

NOTES

- 1.) CABLE MARKERS SHALL BE INSTALLED AT ALL BENDS AND EVERY 200' ALONG THE CABLE RUN.
- 2.) ITEM 610 CONCRETE SHALL BE USED.
- 3.) ALL EXPOSED EDGES SHALL BE EDGED WITH A 1/4" RADIUS TOOL.
- 4.) THE COST OF FURNISHING AND INSTALLING NEW MARKERS SHALL BE INCIDENTAL TO THE ASSOCIATED CABLE ITEMS.
- 5.) 0.049 CU. YD. CONCRETE PER MARKER



LIGHT IDENTIFICATION DETAIL

NOTES:

- INSTALL A NONCORROSIVE DISC OF 2" MINIMUM DIAMETER WITH THE NUMBER PERMANENTLY STAMPED, CUT OUT, OR
- SHALL BE TAGGED AS DIRECTED BY THE RESIDENT ENGINEER. ALL LIGHTS ON EXISTING CIRCUITS THAT HAVE LIGHTING IMPROVEMENTS (PROPOSED OR RELOCATED LIGHTS) SHALL BE RETAGGED.

- PLATE BOLT OR ATTACHED TO LIGHT FLANGE WITH A SET SCREW. NUMERALS SHOWN ARE FOR ILLUSTRATIVE PURPOSES ONLY, ALL EXISTING AND PROPOSED TAXIWAY AND RUNWAY LIGHTS
- COST OF TAGGING LIGHTS SHALL NOT BE PAID FOR SEPERATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.



IL. CONTRACT: FR040 IL. LETTING ITEM: 05A IL. PROJECT: FEP-4296

S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX

NUMBER

FREEPORT-ALBERTUS AIRPORT FREEPORT, ILLINOIS REHABILITATE RUNWAY 6/24

REVISIONS

BY

THIS BAR IS FOUAL TO 2" AT FULL SCALE (34X22)

DATE

က


SHEET

DETAILS

ELECTRICAL

DRAWN BY: JRO CHECKED BY DKP APPROVED BY DLP DATE: 06/03/2016 JOB No: 15294-03-00 **FINAL**

SHEET 24 OF 29 SHEETS



IL. CONTRACT: FR040

IL. PROJECT: FEP-4296

SURVEY BOO	DK # BOOK I	xxxx										
REVISIONS												
NUMBER	BY	DATE										
0	1	2										
	DAD IO FOLIAL											

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

PAVEMENT MARKING DETAILS


RMD JRO DKP DLP DATE: 06/03/2016

FINAL

SHEET 25 OF 29 SHEETS

ADJUST UNDERDRAIN COLLECTION STRUCTURE


NOT TO SCALE



ADJUST MANHOLE (DRAINAGE OR ELECTRICAL)

NOT TO SCALE

- CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD CHECKING EXISTING MANHOLE CONFIGURATIONS AND SIZES FOR THE NECESSARY ADJUSTMENT.
- THE MAXIMUM AMOUNT OF ADJUSTING RINGS ALLOWED SHALL BE THREE. STRUCTURES WITH THREE ADJUSTING RINGS ALREADY IN PLACE SHALL HAVE THE EXISTING RINGS REMOVED AND LARGER RINGS INSTALLED TO COMPLETE THE ADJUSTMENT. COSTS OF REMOVING AND DISPOSING OF EXISTING RINGS SHALL BE INCLUDED IN THE UNIT PRICE FOR THE ADJUSTMENT.
- 3. THE MAXIMUM HEIGHT OF ANY SINGLE ADJUSTING RING(S) SHALL BE 8 INCHES. INCLUDING EXISTING RINGS.
- ADJUSTING RINGS SHALL BE PRE-CAST REINFORCED CONCRETE. ALL
 ADJUSTING RINGS AND METAL FRAME SHALL BE MORTARED INTO PLACE
 WITHOUT THE USE OF SHIMS OF ANY TYPE.
- 5. CONTRACTOR SHALL TAKE CARE TO PREVENT DIRT AND DEBRIS FROM ENTERING THE STRUCTURE. CONTRACTOR SHALL REMOVE ANY DIRT AND DEBRIS FOUND IN THE STRUCTURE PRIOR TO OR AFTER THE ADJUSTMENT, COSTS INCLUDED IN THE UNIT PRICE FOR THE ADJUSTMENT.
- TOPSOIL PLACED AROUND STRUCTURES IN TURF SHALL BE THOROUGHLY COMPACTED TO PREVENT SETTLING.
- AT THE CONTRACTOR'S OPTION AND AT NO ADDITIONAL COST TO THE CONTRACT, HEAVY DUTY IRON ADJUSTING RINGS MAY BE USED IN LIEU OF PRECAST ADJUSTING RINGS. ONLY ONE EXTENSION RING SHALL BE ALLOWED PER STRUCTURE.
- 8. EXISTING CASTINGS DAMAGED BY THE CONTRACTOR DURING REMOVAL OPERATIONS SHALL BE REPLACED AT NO ADDITIONAL COST TO THE





IL. CONTRACT: FR040

IL. LETTING ITEM: 05A IL. PROJECT: FEP-4296 S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX

	-	
	REVISIONS	
NUMBER	BY	DATE
0	- 1	2

THIS BAR IS FOUAL TO 2" AT FULL SCALE (34X22)

FREEPORT-ALBERTUS AIRPORT FREEPORT, ILLINOIS REHABILITATE RUNWAY 6/24 DETAIL DRAINAGE


NEERS -00061 ΣU

DESIGN BY: KD DRAWN BY: JRO CHECKED BY DKP DLP APPROVED BY DATE: 06/03/2016 JOB No: 15294-03-00

FINAL

SHEET 26 OF 29 SHEETS

STRUCTURE ADJUSTMENT NOTES:



Final Overlay Grades

Freeport - Albertus Airport

Runway 6/24 Rehabilitation

$\overline{}$	Grading	г	_	50'	Left			Т	_	25'	' Left					12.5' L	.eft		Г		Cente	rline				_	25' R	ight			$\overline{}$	_	50'	Right			Grading	
Station	Prop. Dist. To Grading	Prop.				Leveling						Leveling											Leveling						Leveling								Prop. Dist. To Grading	Station
	Limits (ft.)	Elev.	Slope (25' - 50')	Elev.	Thick. (ft.)	Thick. (ft.)	Thick. (ft.)	. Elev.	Slope (0' - 25'		Thick. (ft.)	Thick. (ft.)	Thick. (ft.)	Elev.	Elev.	Thick. (ft.)	Thick. (ft.)	Thick. (ft.)	Elev.	Slope (0' - 12.5')	Elev.	Thick. (ft.)	Thick. (ft.)	Thick. (ft.)		Slope (12.5' - 25')	Elev.	Thick. (ft.)	Thick. (ft.)	Thick. (ft.)		Slope (25' - 50')		Thick. (ft.)	Thick. (ft.)	Thick. (ft.)	Limits (ft)	
10+97.35				859.70		0.41	0.54		5 1.25%			0.25	0.37			0.13	0.28	0.41	860.55		860.26	0.13	0.16	0.29	860.24	1.25%	859.70	0.13	0.41	0.54		1.25%	859.50		0.30	0.42		10+97.35
11+00.00 11+50.00	Тху В	859.82	1.25%	859.71 859.37	0.13	0.38	0.45	860.1	3 1.25% 3 1.25%	859.82	0.13	0.20	0.31	860.29	859.98		0.24	0.37	860.53 860.13	3 1.25%	860.26 859.93	0.13	0.14	0.27	860.22 859.82	1.25%	859.74 859.45	0.13	0.35	0.37	859.51	1.25%	859.48 859.19	0.13	0.30	0.42	11.0 18.9	11+00.00 11+50.00
12+00.00 12+50.00		859.42 859.02	1.25%	858.98 858.57	0.13	0.31	0.44	859.3	3 1.25% 3 1.25%	858.96	0.13	0.20	0.32	859.49	859.14		0.21	0.34	859.73 859.33	3 1.25%	859.45 859.07	0.13	0.15	0.28	859.42 859.02	1.25%	859.00 858.59	0.13	0.29	0.42	858.71	1.25%	858.74 858.33	0.13	0.24	0.37	25.2 15.0	12+00.00 12+50.00
13+00.00 13+50.00	90.0	858.22	1.25%		0.13	0.32	0.45	858.53	3 1.25% 3 1.25%	858.23		0.21	0.34		858.77 858.39	0.13	0.19	0.32	858.93 858.53	3 1.25%	858.66 858.28	0.13	0.14	0.27	858.62 858.22	1.25%	858.27 857.90	0.13	0.22	0.35	857.91	1.25%	857.92 857.52		0.26	0.38	25.0 31.6	13+00.00 13+50.00
14+00.00	90.0 91.5	857.82 857.42		857.45 857.06	0.13	0.24	0.37	858.13 857.73	3 1.25% 3 1.25%	857.86 857.46	0.13	0.14	0.27		858.02		0.14	0.27	858.13 857.73		857.93 857.51	0.13	0.08	0.20	857.82 857.42	1.25%	857.52 857.03	0.13	0.17	0.30	857.51 857.11	1.25%	857.17 856.76	0.13	0.21	0.34	29.2 31.1	14+00.00 14+50.00
15+00.00 15+50.00	81.6 42.8	857.02 856.62	1.25%	856.65 856.19	0.13	0.24	0.37	855.93		856.61	0.13	0.15	0.32	857.09	856.73		0.18	0.31	857.33 856.93	3 1.25%	857.09 856.63	0.13	0.12	0.30	857.02 856.62	1.25%	856.69 856.28	0.13	0.20	0.36	856.71 856.31	1.25%	856.35 855.95	0.13	0.23	0.36	30.5 29.8	15+00.00 15+50.00
16+00.00	Txy C			855.88 855.50	0.13	0.21	0.34		3 1.25% 3 1.25%			0.17	0.30		856.39 856.01	0.13	0.17	0.30	856.53 856.13		856.31 855.94	0.13	0.10	0.22	856.22 855.82	1.25%	855.92 855.51	0.13	0.17	0.30	855.91 855.51	1.25%	855.55 855.07	0.13	0.23	0.36	27.7 15.1	16+00.00 16+50.00
17+00.00 17+50.00	10.0 53.9	855.42 855.02	1.25%	855.11 854.62	0.13	0.18	0.31		3 1.25% 3 1.25%		0.13	0.15	0.28	***	855.58		0.18	0.31	855.73 855.33		855.49 855.09	0.13	0.12	0.24	855.42 855.02	1.25%	855.09 854.74	0.13	0.20	0.33	855.11 854.71	1.25%	854.76 854.42	0.13	0.22	0.35	13.1 13.3	17+00.00 17+50.00
18+00.00	54.8 48.6	854.62 854.22		854.24 853.85	0.13	0.25	0.38	854.93	3 1.25% 3 1.25%	854.68	0.13	0.13	0.25		854.81	0.13	0.15	0.28	854.93 854.53		854.73 854.34	0.13	0.07	0.20	854.62 854.22	1.25%	854.36 853.95	0.13	0.13	0.26	854.31 853.91	1.25%	854.00 853.64	0.13	0.18	0.30	11.5 10.0	18+00.00 18+50.00
19+00.00	42.9 44.0				0.13	0.20	0.33		3 1.25% 3 1.25%			0.08	0.20		854.07	0.13	0.09	0.22	854.13	1.2010	853.97 853.62	0.13	0.03	0.16	853.82 853.42	1.25%	853.95 853.57 853.21	0.13	0.12		853.51 853.11		853.24 852.86	0.13	0.14	0.26	10.0	19+00.00 19+50.00
20+00.00	43.6 32.8	853.02 852.62		852.78 852.38	0.13	0.11	0.24	853.33	3 1.25% 3 1.25%	853.18		0.03		000,10	853.34 852.94	0.13	0.02	0.15	853.33 852.93	1.25%	853.24 852.84	0.13	-0.03	0.09	853.02 852.62	1.25%	852.87 852.46	0.13	0.02		852.71 852.31		852.49 852.13	0.13	0.09	0.22	10.0	20+00.00
21+50.00	31.2	852.22	1.25%	851.99	0.13	0.10	0.23	852.5	3 1.25% 3 1.25%	852.38		0.02	0.15	852.69		0.13	0.07	0.20	852.53 852.13	1.25%	852.37	0.13	0.03		852.22 851.82	1.25%	852.02	0.13	0.07		851.91	1.25%	851.79	0.13	-0.01	0.12	10.0	21+00.00
22+00.00	44.7	851.45		851.14	0.13	0.18	0.31		6 1.25%		0.13	0.10	0.22	851.92	851.67	0.13	0.12	0.25	851.76	1.25%	851.56 851.18	0.13	0.08	0.20		1.25%	851.27	0.13	0.05	0.18	851.14 850.79		851.04 850.61	0.13	-0.03 0.05	0.10	10.0	22+00.00 22+50.00
23+00.00	26.7 36.9		1.25%	850.75 849.97	0.13	0.31	0.44		9 1.25%	850.76	0.13	0.21	0.33	851.25	850.89	0.13	0.23	0.36	851.09 850.79	1.25%	850.81 850.44	0.13	0.16		850.78 850.48	1.25%	850.42 850.05	0.13	0.23		850.47 850.17		850.09 849.73	0.13	0.25	0.38	14.3	23+00.00
24+00.00	29.4 33.2		1.25%		0.13	0.44	0.57		2 1.25%		0.13	0.35	0.47	850.68	850.19 849.92	0.13	0.36	0.49	850.52 850.27	1.25%	850.10 849.83	0.13	0.29	0.42	850.21 849.96	1.25%	849.72	0.13	0.36	0.49	849.90		849.36 849.08	0.13	0.41	0.53	27.7	24+00.00
25+00.00	32.3	849.74	1.25%	849.14	0.13	0.47	0.60	850.0	5 1.25%	849.54	0.13	0.38	0.51	850.21	849.70	0.13	0.38	0.51	850.05	1.25%	849.60	0.13	0.32	0.45	849.74	1.25%	849.17	0.13	0.44	0.57	849.43	1.25%	348.80	0.13	0.50	0.63	24.6	25+00.00
25+50.00 26+00.00	35.7 32.8	849.36		010.01	0.13 0.13	0.49	0.62 0.55	849.6	5 1.25% 7 1.25%	849.22	****	0.39 0.32	****	849.83	849.48 849.34	0.13	0.40	0.53 0.49	849.85 849.67	1.25%	849.38 849.23	0.13 0.13	0.35 0.31	0.44	849.54 849.36	1.25%	849.04 848.91	0.13 0.13	0.37 0.32			1.25%	348.69 348.47	0.13 0.13	0.41 0.45	0.53 0.57	25.3 21.0	25+50.00 26+00.00
26+50.00 27+00.00	32.1 33.0		1.25%	848.66 848.62	0.13 0.13	0.42 0.34	0.55 0.47	849.4	2 1.25% 0 1.25%	848.97	0.13 0.13	0.31 0.30	0.44 0.43	849.56	849.21 849.09	0.13	0.34 0.34	0.47 0.47	849.52 849.40	1.25%	849.11 849.00	0.13 0.13	0.28 0.27		849.21 849.09	1.25% 1.25%	848.79 848.66	0.13 0.13	0.29 0.30		848.90 848.78	1.25%	348.44 348.30	0.13 0.13	0.33 0.35	0.45 0.48	22.4 21.9	26+50.00 27+00.00
27+50.00 28+00.00	34.5 31.5		1.25%	0.10.10	0.13 0.13	0.36 0.30	0.49 0.43		2 1.25%			0.26 0.25	*1**	849.38	849.03 848.98	0.13	0.30 0.27	0.43 0.40	849.30 849.22	1.25%	848.92 848.86	0.13 0.13	0.25 0.24	0.36	848.99 848.91	1.25% 1.25%	848.59 848.53	0.13 0.13	0.27 0.20	0.33	848.68 848.60		348.23 348.27	****	0.32 0.20	0.44 0.33	22.6 18.6	27+50.00 28+00.00
28+50.00 29+00.00	32.9 30.8	848.77	1.25%	848.39 848.38	0.13 0.13	0.32 0.26	0.45 0.39	849.0	5 1.25% 8 1.25%	848.71	0.10	0.25 0.25	0.38 0.37		848.88 848.82		0.30 0.29	0.43 0.42	849.15 849.08	1.25%	848.75 848.69	0.13 0.13	0.27 0.26		848.84 848.77	1.25% 1.25%	848.47 848.36	0.13 0.13	0.24 0.28	0.37 0.41	848.46	1.25% 1.25%	348.14 347.97	0.13 0.13	0.26 0.36	0.38 0.49	23.2 15.3	28+50.00 29+00.00
29+50.00 30+00.00	69.6 Txy D		1.25%		0.13 0.13	0.30 0.19	0.43 0.32		4 1.25%			0.25 0.22			848.75		0.29 0.26	0.42 0.39	849.01 848.94		848.63 848.60	0.13 0.13	0.25 0.22		848.70 848.63	1.25% 1.25%	848.30 848.30	0.13 0.13	0.27 0.20		848.32	1.25% 1.25%	847.96 847.95		0.30 0.24	0.42 0.37	15.6 10.0	29+50.00 30+00.00
30+50.00 31+00.00	16.0		1.25%			0.13 0.08		848.79	6 1.25% 9 1.25%	848.56		0.16 0.11	0.23		848.69 848.67	0.13	0.20 0.15	0.33 0.28	848.86 848.79	1.25%	848.58 848.54	0.13 0.13	0.15 0.13	0.25	848.55 848.48	1.25% 1.25%	848.23 848.27	0.13 0.13	0.13 0.08	0.21		1.25%	847.95 847.92		0.16 0.12	0.28 0.25	15.5 10.0	30+50.00 31+00.00
31+50.00 32+00.00	10.0 17.0	848.34		848.20 848.09	0.13 0.13	0.08 0.12	0.21 0.25	848.6	2 1.25% 5 1.25%	848.48	0.13	0.04 0.04	0.16 0.17	848.81	848.66 848.60	0.13	0.09 0.08	0.22 0.21	848.72 848.65	1.25%	848.54 848.49	0.13 0.13	0.06 0.03	0.16	848.41 848.34	1.25% 1.25%	848.26 848.22	0.13 0.13	0.02 -0.01		848.03		847.86 847.83	0.13 0.13	0.11 0.07	0.24 0.19	10.0 10.0	31+50.00 32+00.00
32+50.00 33+00.00	25.5 19.9		1.25% 1.25%	847.94 847.88	0.13 0.13	0.20 0.18	0.33 0.31	0.40.0	8 1.25% 0 1.25%	848.25	0.13 0.13	0.10 0.13			843.47 843.38		0.14 0.17	0.27 0.30	848.58 848.50		848.35 848.24	0.13 0.13	0.11 0.13		848.27 848.19	1.25% 1.25%	848.04 847.91	0.13 0.13	0.10 0.15	0.23 0.28	847.96 847.88	1.25% 1.25%	347.68 347.54	0.13 0.13	0.15 0.21	0.28 0.34	18.1 10.2	32+50.00 33+00.00
33+50.00 34+00.00	18.8 30.7	848.12 848.04		847.75 847.61	0.13 0.13	0.24 0.30	0.37 0.43	848.4 848.3	3 1.25% 5 1.25%		0.13 0.13	0.16 0.22	0.29 0.34		848.26 848.15		0.20 0.23	0.33 0.36	848.43 848.35		848.14 848.03	0.13 0.13	0.16 0.20	0.29 0.32	848.12 848.04	1.25% 1.25%	847.83 847.72	0.13 0.13	0.16 0.19	0.29 0.32	847.81 847.73	1.25% 1.25%	847.44 847.32	0.13 0.13	0.24 0.28	0.36 0.40	10.0 10.0	33+50.00 34+00.00
34+50.00 35+00.00	30.9 23.2		1.25% 1.25%	847.49 847.40	0.13 0.13	0.31 0.27	0.44		4 1.25% 1 1.25%			0.21 0.20	0.33 0.32		843.04 847.92		0.23 0.22	0.36 0.35	848.24 848.11		847.92 847.80	0.13 0.13	0.20 0.19		847.93 847.80	1.25% 1.25%	847.63 847.53	0.13 0.13	0.17 0.14			1.25% 1.25%	847.21 847.08	0.13 0.13	0.28 0.28	0.40 0.40	10.0 10.0	34+50.00 35+00.00
35+50.00 36+00.00	15.4 10.5	847.64 847.46	1.25% 1.25%	847.25 847.13	0.13 0.13	0.26 0.20	0.39	847.9 847.7	5 1.25% 7 1.25%		0.13 0.13	0.22 0.18	0.34 0.31	848.11 847.93	847.74	0.13 0.13	0.24 0.25	0.37 0.38	847.95 847.77	5 1.25% 7 1.25%	847.63 847.43	0.13 0.13	0.20 0.22		847.64 847.46	1.25% 1.25%	847.32 847.11	0.13 0.13	0.19 0.22		847.33 847.15	1.25% 1.25%	846.89 846.67	0.13 0.13	0.31 0.35	0.44 0.48	10.0 10.0	35+50.00 36+00.00
36+50.00 37+00.00	12.4 10.0	847.25 847.02	1.25% 1.25%	846.98 846.76	0.13 0.13	0.14 0.13	0.27 0.26		6 1.25% 3 1.25%		0.13 0.13	0.13 0.09	0.25 0.21		847.38 847.18		0.21 0.18	0.34 0.31	847.56 847.33		847.26 847.06	0.13 0.13	0.17 0.15	0.30 0.27	847.25 847.02	1.25% 1.25%	846.94 846.77	0.13 0.13	0.18 0.12	0.31 0.25	846.94 846.71	1.25% 1.25%	346.54 346.38	0.13 0.13	0.27 0.20	0.39	17.0 10.4	36+50.00 37+00.00
37+50.00 38+00.00	18.0 22.7		1.25% 1.25%	846.50 846.29	0.13 0.13	0.14 0.11	0.27 0.24		8 1.25% 4 1.25%			0.12 0.13			846.89 846.64	0.13	0.22 0.23	0.35 0.36	847.08 846.84		846.76 846.49	0.13 0.13	0.20 0.23		846.77 846.53	1.25% 1.25%	846.52 846.23	0.13 0.13	0.12 0.17		846.46 846.22	1.25% 1.25%	846.13 845.84	0.13 0.13	0.20 0.25	0.33 0.38	11.1 14.6	37+50.00 38+00.00
38+50.00 39+00.00	23.9 15.1	846.28 846.04	1.25% 1.25%	845.97 845.83	0.13 0.13	0.18 0.08	0.31 0.21	845.59 845.39	9 1.25% 5 1.25%	846.33 846.12	0.13 0.13	0.13 0.11	0.26 0.23	846.75 846.51	846.38 846.14	0.13	0.24 0.24	0.37 0.37	846.59 846.35	9 1.25% 5 1.25%	846.21 845.98	0.13 0.13	0.25 0.25	0.38 0.37	846.28 846.04	1.25% 1.25%	845.91 845.73	0.13 0.13	0.24 0.18	0.37	845.97 845.73	1.25% 1.25%	845.51 845.33	0.13 0.13	0.33 0.27	0.46 0.39	21.4 10.3	38+50.00 39+00.00
39+50.00 40+00.00	10.0 10.0	845.79 845.55		845.61 845.40	0.13 0.13	0.05 0.02	0.18 0.15		0 1.25% 6 1.25%		0.13 0.13	0.06	0.18 0.18		845.94 845.69		0.19 0.20	0.32 0.33	846.10 845.86		845.80 845.55	0.13 0.13	0.18 0.19	0.30 0.31	845.79 845.55	1.25%	845.58 845.34	0.13 0.13	0.10 0.08	0.23	845.48 845.24	1.25%	845.15 844.95	0.13 0.13	0.20 0.16	0.33 0.28	10.0 10.0	39+50.00 40+00.00
40+50.00 41+00.00	10.0 11.2	845.31 845.06	1.25% 1.25%	845.09 844.77	0.13 0.13	0.09	0.22		2 1.25% 7 1.25%		0.13	0.10 0.24	0.22		845.40	0.13	0.25 0.33	0.38	845.62 845.37		845.26 844.95	0.13	0.24		845.31 845.06	1.25%	845.06 844.63	0.13 0.13	0.12 0.25	0.25	845.00 844.75	1.25%	844.62 844.33	0.13	0.25 0.29	0.38 0.41	15.5 12.5	40+50.00 41+00.00
41+50.00 42+00.00	13.9	844.82 844.57	1.25%	844.49	0.13 0.13	0.20	0.33	845.13	3 1.25% 8 1.25%	844.78	0.13	0.23	0.35	845.29	844.83		0.33	0.46	845.13	1.25%	844.70 844.44	0.13	0.30	0.43	844.82 844.57	1.25%	844.45 844.18	0.13	0.24	0.37		1.25%	844.01 843.76	0.13	0.37	0.50	14.6 17.2	41+50.00 42+00.00
42+50.00 43+00.00	17.3 10.6	844.33	1.25%	843.92 843.71	0.13	0.28	0.41	844.6	4 1.25% 0 1.25%	844.24	0.13	0.27	0.40	844.80	844.31	0.13	0.36	0.49	844.64	1.25%	844.19 843.95	0.13	0.32		844.33 844.09	1.25%	843.95 843.69	0.13	0.25	0.38	844.02 843.78	1.25%	843.53 843.26	0.13	0.36	0.49 0.51	20.9	42+50.00 43+00.00
43+50.00 44+00.00	16.6	843.84	1.25%	843.52 843.32	0.13	0.19	0.32	844.1	5 1.25% 1 1.25%	843.82	0.13	0.20	0.33	844.31	843.83 843.61	0.13	0.35	0.48	844.15	1.25%	843.71 843.49	0.13	0.31	0.44	843.84 843.60	1.25%	843.48 843.28	0.13	0.23	0.36	843.53 843.29	1.25%	843.07 842.88	0.13	0.33	0.45 0.40	29.1	43+50.00 44+00.00
44+50.00 45+00.00	10.0	843.35	1.25%	843.05 842.81	0.13 0.13	0.17	0.30	843.6	6 1.25% 4 1.25%	843.36	0.13	0.17 0.18	0.30	843.82	843.38 843.19	0.13	0.31	0.44	843.66 843.44	1.25%	843.28 843.09	0.13	0.25 0.23	0.38	843.35 843.13	1.25%	843.03 842.84	0.13 0.13	0.14 0.16	0.27	843.04	1.25%	842.64 842.50	0.13	0.27	0.39	24.5 22.1	44+50.00 45+00.00
45+50.00	19.5	842.93	1.25%	842.60	0.13	0.20	0.33	843.2	4 1.25%	842.93	0.13	0.19	0.31	843.40	842.99	0.13	0.28	0.41	843.24	1.25%	842.87	0.13	0.25	0.37	842.93	1.25%	842.60	0.13	0.20	0.33	842.62	1.25%	842.31	0.13	0.18	0.31	28.7	45+50.00
46+50.00	23.9 29.3	842.60	1.25%	842.16	0.13	0.26	0.39	842.9	6 1.25% 1 1.25%	842.53	0.13	0.22	0.38	843.07	842.59		0.32	0.45	842.91	1 1.25%	842.67 842.52	0.13	0.26	0.39	842.75 842.60	1.25%	842.33	0.13	0.24	0.36	842.29	1.25%	842.05 841.85 841.75	0.13	0.26	0.43	29.8 34.8	46+00.00 46+60.00
47+50.00	Txy F	842.37	1.25%	841.99	0.13	0.27	0.40	842.6		842.28	0.13	0.26	0.39	842.84	842.48	0.13	0.33	0.46	842.68	3 1.25%	842.40 842.30	0.13	0.25	0.38	842.47	1.25%	842.13	0.13	0.21	0.37	842.16 842.06	1.25%	841.63	0.13	0.28	0.40	38.1 42.1	47+00.00 47+50.00
48+00.00 48+50.00	52.1	842.24	1.25%	841.88 841.80	0.13	0.28	0.41	842.5	0 1.25% 5 1.25%	842.18	0.13	0.27	0.37	842.71	842.30		0.31	0.44	842.60 842.55	1.25%	842.23 842.21	0.13	0.25	0.34	842.29 842.24	1.25%	841.91 841.83	0.13	0.25	0.38	841.93	1.25%	841.50 841.43	0.13	0.35	0.48	45.4 45.7	48+00.00 48+50.00
49+00.00 49+50.00	49.4 47.4	842.21	1.25% 1.25%	841.74	0.13	0.33	0.45	842.5	2 1.25% 2 1.25%	842.13	0.13	0.25	0.39	842.68	842.26	0.13	0.28	0.41	842.52 842.52	1.25%	842.15 842.15	0.13	0.25	0.37	842.21 842.21	1.25%	841.79 841.77	0.13	0.29	0.44	841.90	1.25%	841.32	0.13	0.44	0.56 0.57	49.5 52.4	49+00.00 49+50.00
50+00.00	43.0		1.25%	841.77	0.13	0.33	0.46		4 1.25%			0.22	0.35		842.31		0.26	0.39	842.54	1.25%	842.20	0.13	0.21	0.34	842.23	1.25%	841.80	0.13	0.30	0.43		1.25%		0.13	0.42	0.54	48.5	50+00.00

THE RESIDENT ENGINEER SHALL PROVIDE ELECTRONIC GRADE CHART TO THE CONTRACTOR FOR USE DURING CONSTRUCTION. FINAL ADJUSTMENTS SHALL BE MADE BY THE PROJECT ENGINEER.

IL. CONTRACT: FR040

- IL. LETTING ITEM: 05A
- IL. PROJECT: FEP-4296 S.B.G. PROJECT: 3-17-SBGP-XX

SURVEY BOOK # BOOK # XXXX

	REVISIONS	
NUMBER	BY	DATE

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

TABLE FREEPORT-ALBERTUS AIRPORT FREEPORT, ILLINOIS REHABILITATE RUNWAY 6/24

OVERLAY DEPTH SHEET 1 BITUMINOUS

CMT

DESIGN BY: DRAWN BY: JRO CHECKED BY: DKP APPROVED BY: DATE: 06/03/2016

FINAL

JOB No: 15294-03-00

SHEET 28 OF 29 SHEETS

	Grading 50' Left Prop. Dist. Prop.						25' Left 12.5' Left											Prop.	Cente	rline				Prop.	25' R	ight				Prop.	50' F	Grading Prop. Dist.						
Station	To Grading	Prop.	Cross	Eviet	Surface	Levelina	Total	Prop.		Eviet	Surface	Leveling	Total	Pron	Evist	Surface	I eveling	Total	Pron	Cross	Existing	Surface	l eveline	Total	Pron	Cross	Evist	Surface	Levelina	Total	Prop		Eviet	Surface	l eveline		To Grading	Station
Otation	Limits	Elev.	Slope	Elev.	Thick.	Thick.		Elev.	Slope		Thick.		Thick.			Thick.		Thick.		Slope	Elev.	Thick.		Thick.		Slope		Thick.		Thick.		Slope		Thick.	Thick.	Thick.	Limits	Otation
	(ft.)		(25' - 50')		(ft.)	(ft.)	(ft.)		(0' - 25'		(ft.)	(ft.)	(ft.)			(ft.)	(ft.)	(ft.)		(0' - 12.5')		(ft.)	(ft.)	(ft.)		(12.5' - 25')		(ft.)	(ft.)	(ft.)		(25' - 50')		(ft.)	(ft.)	(ft.)	(ft.)	1 L
								$\overline{}$																												$\overline{}$		$\overline{}$
50+50.00	40.4		1.25%			0.31			1.25%			0.20			842.40	0.13	0.22				842.27	0.13	0.20		842.28		841.88	0.13	0.27				841.44	0.13	0.40	0.52	45.3	50+50.00
51+00.00	93.2		1.25%			0.28			1.25%			0.18				0.13	0.21				842.37	0.13	0.17		842.36		842.00		0.23				841.56		0.36	0.49	46.2	51+00.00
51+50.00	91.2		1.25%			0.27			1.25%			0.14			842.62	0.13	0.17				842.51	0.13	0.13		842.45				0.16				841.70		0.31	0.43	43.9	51+50.00
52+00.00	37.3		1.25%			0.22			1.25%			0.13			842.77		0.15		842.89	1.25%	842.67	0.13	0.10		842.58		842.34		0.11				841.90		0.24	0.37	43.8	52+00.00
52+50.00	25.8		1.25%			0.18			1.25%			0.08			842.96	0.13	0.10				842.85	0.13	0.05		842.72		842.52		0.07				842.15		0.13	0.25	38.7	52+50.00
53+00.00	10.0		1.25%			0.07			1.25%			-0.04			843.21	0.17	-0.01			1.25%	843.12	0.17	-0.08		842.90		842.80		-0.07				842.41		0.01	0.18	31.7	53+00.00
53+50.00 54+00.00	10.0 10.0		1.25% 1.25%			-0.03 -0.02			1.25% 1.25%			-0.10			843.44 843.69		-0.05 -0.07			1.25%	843.34 843.57	0.17 0.17	-0.11 -0.11		843.09 843.32		843.04		-0.12 -0.10				842.63 842.85		-0.02 -0.01	0.14 0.15	29.7 10.0	53+50.00 54+00.00
54+50.00	10.0		1.25%			-0.02			1.25%			-0.10 -0.11			843.95		-0.07		843.88		843.83	0.17	-0.11		843.57		843.25 843.50		-0.10				843.09		0.00	0.15	33.5	54+50.00
55+00.00	37.3		1.25%			0.01			1.25%			-0.07			844.21		-0.07		844.15		844.08	0.17	-0.12		843.84		843.67		0.00				843.23		0.13	0.10	36.1	55+00.00
55+50.00			1.25%			0.13			1.25%			-0.04			844.47		-0.04		844.44	1.25%	844.36	0.17	-0.09		844.13		844.00	0.17	-0.04					0.17	0.08	0.25	41.4	55+50.00
56+00.00			1.25%			0.13			1.25%			-0.03					-0.01		844.71	1.25%	844.62	0.17	-0.08		844.40		844.26		-0.03						0.09	0.25	45.4	56+00.00
56+50.00	49.7		1.25%			0.06			1.25%			-0.04			844.94		-0.01		844.94		844.85	0.17	-0.08		844.63		844.49		-0.03				844.06		0.09	0.26	46.4	56+50.00
57+00.00	52.0		1.25%			0.07			1.25%			-0.04			845.15		-0.02				845.05	0.17	-0.08		844.83		844.70		-0.04					0.17	0.10	0.26	47.2	57+00.00
57+50.00	57.7		1.25%			0.04	0.21	845.30	1.25%	845.20	0.17	-0.07	0.10	845.46	845.32	0.17	-0.03	0.14	845.30		845.22	0.17	-0.09	0.08	844.99		844.88	0.17	-0.06					0.17	0.10	0.26	35.2	57+50.00
58+00.00		845.11	1.25%	845.00	0.17	-0.06	0.11	845.42	1.25%	845.33	0.17	-0.08	0.09	845.58	845.43	0.17	-0.02	0.15	845.42	1.25%	845.32	0.17	-0.07	0.10	845.11	1.25%	844.96	0.17	-0.02	0.15	844.80	1.25%	844.50	0.17	0.13	0.29	39.8	58+00.00
58+50.00	Txy G	845.19	1.25%	845.13	0.17	-0.11			1.25%			-0.11	0.06	845.66	845.51	0.17	-0.02	0.15	845.50	1.25%	845.38	0.17	-0.05	0.12	845.19	1.25%	845.04	0.17	-0.02	0.15	844.88	1.25%	844.61	0.17	0.10	0.26	50.3	58+50.00
59+00.00		845.24	1.25%	845.23	0.17	-0.16			1.25%			-0.12	0.05	845.71	845.59	0.17	-0.05	0.12	845.55	1.25%	845.46	0.17	-0.08	0.09	845.24	1.25%	845.13	0.17	-0.06	0.11	844.93	1.25%	844.72	0.17	0.04	0.20	37.6	59+00.00
59+50.00	12.2		1.25%			-0.24			1.25%			-0.20			845.65	0.17	-0.11		845.55		845.53	0.17	-0.15		845.24		845.26		-0.19				844.79		-0.03	0.13	10.0	59+50.00
60+00.00	10.0		1.25%			-0.28			1.25%			-0.22			845.65	0.17	-0.14		845.52		845.49	0.17	-0.14		845.21		845.22		-0.18				844.79		-0.06	0.11	10.0	60+00.00
60+50.00	10.0		1.25%			-0.23			1.25%			-0.19			845.56		-0.11			1.25%	845.42	0.17	-0.13		845.15		845.15		-0.17				844.71		-0.04	0.13	10.0	60+50.00
61+00.00	15.6		1.25%			-0.21			1.25%			-0.20			845.46		-0.12		845.35		845.30	0.17	-0.12		845.04		845.09		-0.22				844.65		-0.09	0.08	10.0	61+00.00
61+50.00	11.3		1.25%			-0.25			1.25%			-0.24			845.34		-0.14				845.20	0.17	-0.16		844.90		844.98		-0.25				844.56		-0.14	0.03	10.0	61+50.00
62+00.00	14.0		1.25%			-0.23			1.25%			-0.23			845.14		-0.12			1.25%	844.98	0.17	-0.12		844.72		844.71		-0.16				844.34		-0.10	0.06	10.0	62+00.00
62+50.00			1.25%			-0.18			1.25%			-0.20			844.91		-0.11		844.81	1.25%	844.76	0.17	-0.12		844.50		844.54		-0.21				844.10		-0.08	80.0	10.0	62+50.00
63+00.00	10.0		1.25%			-0.21			1.25%			-0.20			844.66		-0.12				844.52	0.17	-0.14		844.24				-0.24				843.89		-0.13	0.03	10.0	63+00.00
63+50.00	10.0 10.0		1.25%			-0.20 -0.19			1.25% 1.25%			-0.18 -0.13			844.35 844.00		-0.10 -0.08		844.26 843.93		844.19 843.83	0.17 0.17	-0.10 -0.07		843.95 843.62		843.93 843.61		-0.15 -0.16				843.58		-0.11 -0.05	0.05 0.11	10.0 10.0	63+50.00 64+00.00
64+00.00 64+50.00			1.25% 0.90%			-0.19			0.90%			-0.13			843.61		-0.07			1.20%	843.46		-0.07		843.25		843.17		-0.10				843.19 842.82		-0.05	0.11	10.0	64+50.00
65+00.00			1.00%			-0.05			1.00%			-0.08			843.20		-0.07		843.17		843.08	0.17 0.17	-0.07		842.88		842.84		-0.09				842.49		-0.05	0.09	10.0	65+00.00
65+50.00	TxyH		1.18%			-0.00			1.18%			-0.10					-0.11		842.78		842.72	0.17	-0.05		842.47		842.48		-0.13				842.09		-0.08	0.09	22.7	65+50.00
65+98.00			1.86%			-0.11			1.86%			-0.10			842.34		-0.16			-0.40%	842.72	0.17	-0.16		842.04		842.12		-0.18				841.66			0.00		65+98.00
55.50.00		341.00	1.00/6	341.03	V.11	-0.20	-0.04	072.12	1.00 /6	042.00	V.17	-9.11	0.00	U 12.00	U+2.04	v.11	-7.10	0.01	04Z.40	-0.40 /6	342.03	V.11	-0.10	V.01	342.04	1,40 /6	542.12	0.17	-0.20	0.03	571.07	1.70/0	341.00	0.11	-0.10	0.01	20.5	00.00.00

THE RESIDENT ENGINEER SHALL PROVIDE ELECTRONIC GRADE CHART TO THE CONTRACTOR FOR USE DURING CONSTRUCTION. FINAL ADJUSTMENTS SHALL BE MADE BY THE PROJECT ENGINEER.

IL. CONTRACT: FR040

- IL. LETTING ITEM: 05A
- IL. PROJECT: **FEP-4296**S.B.G. PROJECT: **3-17-SBGP-XX**

SURVEY BOOK # BOOK # XXXX

REVISIONS												
NUMBER	BY	DATE										

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

FREEPORT-ALBERTUS AIRPORT FREEPORT, ILLINOIS REHABILITATE RUNWAY 6/24

BITUMINOUS OVERLAY DEPTH SHEET 2

DESIGN BY: KD DRAWN BY: JRO CHECKED BY: DKP APPROVED BY: DATE: 06/03/2016 JOB No: 15294-03-00

FINAL

SHEET 29 OF 29 SHEETS